

Multiple Vessel Mooring System –
Ad Hoc Committee Pilot Program Evaluation
Final Report

City Council Study Session
June 10, 2014

Background

- ▶ **“Multiple Vessel Mooring System” (MVMS)** currently allowed per NBMC 17.60.040 (B)(1)(c) & 17.01.030 (J)(15) in the single-point mooring fields only (e.g. NHYC and BYC fields)



Pilot Program Evaluation

▶ February 2014:

- ▶ Mayor Hill tasked the Harbor Commission to:
 - ▶ Study the MVMS in the double-point mooring areas; and
 - ▶ Return to Council with a recommended **pilot program**

▶ Purpose of the Pilot Program:



- ▶ Provide amenities to the mooring community by providing an easier way to moor a vessel
- ▶ Decrease the mooring field footprint, therefore increasing usable water area
- ▶ Provide a convenient load/unload point for a water taxi system



Examples of Full-Scale Mooring Conversion to MVMS “C” Field



Examples of Full-Scale Mooring Conversion to MVMS “H & J” Fields



Examples of Full-Scale Mooring Conversion to MVMS “D” Field



Timeline

- ▶ February 2014: Harbor Commission tasked to develop pilot program

- ▶ March 12: Ad-Hoc Committee formed
Commissioners Brad Avery (Chair) and Duncan McIntosh

- ▶ Publicly Noticed Meetings
 - ▶ March 24 Ad-Hoc Committee
 - ▶ March 31 Ad-Hoc Committee
 - ▶ April 9 **Harbor Commission**
 - ▶ April 14 Ad-Hoc Committee
 - ▶ April 28 Ad-Hoc Committee
 - ▶ May 14 **Harbor Commission**
 - ▶ May 21 Ad-Hoc Committee

-
- ▶ Newport Mooring Association Outreach (discussed later)

Ad-Hoc Committee Findings


- ▶ **No pilings**
 - ▶ Too “permanent” for pilot project (does not allow for adjustment)
 - ▶ Possible view issue
- ▶ **Work/Wash-Down Float (NMA suggestion)**
- ▶ **Legal Concerns with City Owned Dock? (liability)**
- ▶ **No Electricity / No Water**
 - ▶ Too complex for pilot program
 - ▶ Must be buried at least 5’ below sediment surface (Corps requirement)
 - ▶ Proximity to street-end required for utilities
 - ▶ Possible future option




Ad-Hoc Committee Findings cont'd

- ▶ **Anchor options:**
 - ▶ Existing buoy, weight & chain method
 - ▶ Helix anchor & elastic band method
 - ▶ Hybrid (weight + bands)
-


Floating Dock with Buoy, Weight & Chain Method



1 MOORING DOCK PLAN
SCALE: 1/4"=1'-0"



4 TYPICAL CHAIN MOORING
SCALE: ITS



3 MOORING DOCK AT HIGH TIDE
SCALE: 1/4"=1'-0"

Project: Newport Beach Mooring Improvement - Phase 1
 Drawing: Mooring Dock with Seaflex - Concept 2
 Date: 1/14/10
 Scale: AS NOTED

NO.	DATE	DESCRIPTION	BY




310 Garden Shores, Suite 100
 Long Beach, CA 90802
 Tel: (562) 506-2100
 Fax: (562) 298-7000


ENGINEER	-	SCALE	AS NOTED
DESIGNER	-	PROJECT NUMBER	-
CAD OPERATOR	-	DRAWING NUMBER	C-2
CHECKER	-		
PROJECT MANAGER	-		

PROJECT NUMBER	-
DRAWING NUMBER	C-2

Floating Dock with Helix Anchor & Seaflex Band Method



Floating Dock with Helix Anchor & Seaflex Band Method



NO.	DATE	DESCRIPTION	BY

URS


310 Golden Shore, Suite 100
 Long Beach, CA 90802
 Tel: (562) 908-2300
 Fax: (562) 298-7905

ENGINEER	-	
DESIGNER	-	
CAD OPERATOR	-	NEWPORT BEACH MOORING IMPROVEMENT
CHECKER	-	
PROJECT MANAGER	-	MOORING DOCK WITH SEAFLEX - CONCEPT 1

SCALE AS NOTED	△
PROJECT NUMBER	-
DRAWING NUMBER	C-1

Example of MVMS

Milford, CT
Installed 2003
75 mph Wind Rating
34' x 4' Floats



Seaflex[®]
The Environmental Mooring Solution

Community Surveys

- ▶ Newport Mooring Association Survey Results (web)
 - ▶ “Do you want floating docks?”
 - ▶ 61 responses
 - ▶ 85% negative
 - ▶ “Would you volunteer your mooring for a pilot program?”
 - ▶ 54 responses
 - ▶ 11 “yes”
 - ▶ “What are the top priorities for mooring permittees?”
 - ▶ 39 responses
 - ▶ Top Priority: Shore-side work dock (charge batteries, overnight, light mechanic work etc...)



Community Surveys (cont'd)

- ▶ **City Survey**

- ▶ No survey performed yet (short study period)

- ▶ Options:

- 1. Survey prior to pilot study

- 2. Survey during pilot program after floats are installed



Conclusions & Recommendations

- ▶ Implement Pilot Program for at least 2 summers
- ▶ Install 6 floats (or more...or less per Council direction)
 - ▶ 40' – 50' long
 - ▶ 6' wide
 - ▶ Performance specs for any type of float (wood, concrete, fiberglass, aluminum etc...)
 - ▶ 3 floats using buoy, weight & chain method
 - ▶ 3 floats using Helix anchor & Seaflex band method (or hybrid)
 - ▶ Sea lion deterrents



Conclusions & Recommendations

- ▶ **\$248,000** Estimated Total Cost (conservative)
 - ▶ **\$210,000** (\$35,000 x 6 floats – variable)
 - ▶ Floats
 - ▶ Anchor system (weight, chain & buoy, and Helix/Seaflex)
 - ▶ Underwater “Pull Test” (test anchoring systems)
 - ▶ Installation
 - ▶ Contingency
 - ▶ **\$20,000** (Engineering – fixed)
 - ▶ Design floats
 - ▶ Prepare bid package
 - ▶ Respond to bidders questions
 - ▶ Implement “Pull-Test” program
 - ▶ Respond to contractor’s questions
 - ▶ **\$18,000** (Sea Lion Deterrents @ \$3,000 x 6 floats – variable)



Conclusions & Recommendations

- ▶ Place floats in multiple mooring fields
- ▶ Survey users & community during and after pilot project
- ▶ Post pilot project
 - ▶ Report to Council
 - ▶ Remove floats (Store? Sell? Continue program?)
 - ▶ Restore permittee's mooring equipment



Next Steps

- ▶ June 10: City Council Study Session
Proceed? If so:
- ▶ Mid-July 2014: Prepare plans & contract documents
- ▶ Early August: Bid package released
- ▶ Late September: Bid opening, Council award
- ▶ December/January: Floats installed
- ▶ January 2015 to September 2016:
 - ▶ Pilot project (2 summers)



For More Information:

Chris Miller

(949) 644-3043

cmiller@newportbeachca.gov

Shannon Levin

(949) 644-3041

shannon@newportbeachca.gov