



June 30, 2017

Rincon Consultants, Inc.

180 North Ashwood Avenue
Ventura, California 93003

805 644 4455

FAX 644 4240

info@rinconconsultants.com

www.rinconconsultants.com

Mr. Gregg Ramirez
Senior Planner
City of Newport Beach
Community Development Department, Planning Division
100 Civic Center Drive
Newport Beach, CA 92660

Subject: City of Newport Beach Balboa Island Coping Repair Project (C-7066-1)

Dear Mr. Ramirez,

On behalf of the City of Newport Beach Public Works Department and COWI Marine North America (the project engineer), Rincon Consultants, Inc. (Rincon) is pleased to submit the enclosed Coastal Development permit application to the Community Development Department for the above referenced project. In submitting this application, the City is proposing repair and maintenance of the existing seawall coping located along the perimeter of the North/South Bay Front boardwalk on Balboa Island.

We have enclosed the following documents used by the City in processing this application:

Completed CDP application form

Attachment 1 – Project Description

Attachment 2 – Vicinity Map and Site Photographs

Attachment 3 – Project Plans

Attachment 4 – Bulkhead Condition Report

Attachment 5 – Consistency Analysis - Newport Beach Municipal Code Appendix A (*Sea Level Rise*)

Attachment 6 – Construction Access Plan

Attachment 7 – Bird Survey Protocol

Attachment 8 – Construction Management Plan

Attachment 9 – Construction Pollution Prevention Plan

Attachment 10 – Public Notice Materials

We look forward to working with you and the Planning Division Staff in the processing of this CDP request. If you have any questions regarding these application materials, please do not hesitate to contact us at 805.644.4455.


Sincerely,

RINCON CONSULTANTS, INC.

A handwritten signature in blue ink, appearing to read 'Lynette Leighton'.

Lynette Leighton

Associate Environmental Planner

A handwritten signature in blue ink, appearing to read 'Jasch Janowicz'.

Jasch Janowicz

Principal



Community Development Department Planning Permit Application

CITY OF NEWPORT BEACH
100 Civic Center Drive
Newport Beach, California 92660
949 644-3200
newportbeachca.gov/communitydevelopment

1. Check Permits Requested:

- | | | |
|--|--|---|
| ☐ Approval-in-Concept - AIC # | ☐ Lot Merger | ☐ Staff Approval |
| ☒ Coastal Development Permit | ☐ Limited Term Permit - | ☐ Tract Map |
| ☐ Waiver for De Minimis Development | ☐ Seasonal ☐ < 90 day ☐ >90 days | ☐ Traffic Study |
| ☐ Coastal Residential Development | ☐ Modification Permit | ☐ Use Permit - ☐ Minor ☐ Conditional |
| ☐ Condominium Conversion | ☐ Off-Site Parking Agreement | ☐ Amendment to existing Use Permit |
| ☐ Comprehensive Sign Program | ☐ Planned Community Development Plan | ☐ Variance |
| ☐ Development Agreement | ☐ Planned Development Permit | ☐ Amendment - ☐ Code ☐ PC ☐ GP ☐ LCP |
| ☐ Development Plan | ☐ Site Development Review - ☐ Major ☐ Minor | ☐ Other: |
| ☐ Lot Line Adjustment | ☐ Parcel Map | |

2. Project Address(es)/Assessor's Parcel No(s)

Seawall parallel to North/South Bay Front boardwalk on Balboa Island, at the terminus of 30 street ends (Marine Avenue to Emerald Avenue)

3. Project Description and Justification (Attach additional sheets if necessary):

See Attachment.

4. Applicant/Company Name

City of Newport Beach, Public Works Department

Mailing Address

100 Civic Center Drive

Suite/Unit

City

Newport Beach

State

CA

Zip

92660

Phone

(949) 644-3319

Fax

(949) 644-3318

Email

mvukojevic@newportbeachca.gov

5. Contact/Company Name

Mark Vukojevic, Deputy Public Works Director/City Engineer

Mailing Address

100 Civic Center Drive

Suite/Unit

City

Newport Beach

State

CA

Zip

92660

Phone

949-644-3319

Fax

Email

mvukojevic@newportbeachca.gov

6. Owner Name

City of Newport Beach

Mailing Address

100 Civic Center Drive

Suite/Unit

City

Newport Beach

State

CA

Zip

92660

Phone

949-644-3319

Fax

Email

mvukojevic@newportbeachca.gov

7. Property Owner's Affidavit*: (I) (We)

depose and say that (I am) (we are) the owner(s) of the property (ies) involved in this application. (I) (We) further certify, under penalty of perjury, that the foregoing statements and answers herein contained and the information herewith submitted are in all respects true and correct to the best of (my) (our) knowledge and belief.

Signature(s): _____

Title: _____

Date: _____

DD/MO/YEAR

Signature(s): _____

Title: _____

Date: _____

*May be signed by the lessee or by an authorized agent if written authorization from the owner of record is filed concurrently with the application. Please note, the owner(s)' signature for Parcel/Tract Map and Lot Line Adjustment Application must be notarized.



NOTICE OF APPLICATION FILING

THE PLANNING DIVISION OF THE COMMUNITY DEVELOPMENT DEPARTMENT OF THE CITY OF NEWPORT BEACH RECENTLY RECEIVED A **COASTAL DEVELOPMENT PERMIT** APPLICATION FOR THE FOLLOWING PROJECT:

PROPOSED PROJECT: Balboa Island Seawall Coping Repair Project

Repair and maintenance of existing seawalls, and increase
height of seawalls by 9 inches.

LOCATION: Seawall parallel to North/South Bay Front on
Balboa Island

APPLICANT: City of Newport Beach

APPLICATION NO.: _____

DATE NOTICE POSTED: _____

The public hearing for this application has not yet been scheduled. When the hearing, or determination are scheduled, further notice will be provided.

The application is available for your review at the Community Development Department Permit Center (Bay C-1st Floor), at 100 Civic Center Drive, Newport Beach, California, CA 92660. Prior to the public hearing, the agenda, staff report, and documents may be reviewed. For more information, call (949) 644-3200 (please reference the application number).

ATTACHMENT 1

CITY OF NEWPORT BEACH

Balboa Island Coping Repair Project Description

Introduction

The proposed project involves the repair and maintenance of the existing seawall located along the perimeter of North/South Bay Front boardwalk on Balboa Island in conformance with the City of Newport Beach Balboa Island Coping Repair Project (C-7066-1) and the City of Newport Beach (City) certified Coastal Land Use Plan (See Attachment 2 – Vicinity Map). The purpose of the repair is to preserve the structural integrity and increase the height of the seawall on Balboa Island. These improvements would reduce the potential for water overtopping the walls during high tides, local wind waves, storm surges, and periods of larger ocean swells by increasing the height of the seawalls by 9 inches. The project is not considered “new development” according to the California Coastal Act Section 30212(b)(4). The project would also be one of the City’s first steps toward implementing plans to reduce the impact of sea level rise.

Surrounding Land Uses

Land uses located adjacent to the project area include public beaches, public walkways and streets, public ferry system, public and private docks, and privately owned parcels with the following certified Coastal Land Use Plan designations: RT-E (Two-Unit Residential), and MU-W (Mixed-Use Water Related). The majority of privately owned parcels are developed with single- and two-family residences. A number of private and publicly accessible docks have landings at the top of the seawall in order to provide access to boats moored in the bay or to provide the public with coastal recreational opportunities (See Attachment 2 – Site Photographs).

Balboa Island has approximately eight acres of public beaches around the island. There are 33 street ends and the Bay Front Boardwalk that provide access to and along the shoreline and to Balboa Island’s public beaches. There are also four street ends that provide access to the Grand Canal. There are five public docks on Balboa Island for loading and unloading passengers, supplies, and boating gear and for similar purposes. Hand-carried boat launching is permitted at 22 street end beaches.

Project Timing and Schedule

The construction of the proposed project is anticipated to occur over eight months, from October through May to avoid active bird nesting and peak tourism seasons.

A total of six construction rotations are anticipated for the 17 work areas identified along the North/South Bay Front boardwalk. Construction of the seawall segments will be phased such that no more than three non-contiguous segments will be constructed during the first five rotations, and the final rotation will consist of two work areas. Construction of each segment will take approximately ten days to complete (See Attachment 8 – Construction Management Plan).

Construction activities will be limited to non-holiday weekdays from 7:00 A.M. to 5:00 P.M., per Section 10.28.040 of the Municipal Code. Any activity outside of the specified hours shall be authorized in writing by the Building Official with the incorporation of sound mitigation measures.

Project Construction Activities

Seawall repair and construction activities will consist of two phases. The initial pre-construction phase will last approximately two months, and involve equipment mobilization and minor demolition of the corners and tops of the seawall segments and roughening the existing exterior concrete surface of the seawall segments to create a proper bonding surface for construction of the reinforced concrete seawall cap (See Attachment 3 - Project Plans). Existing cracks will also be repaired or patched during the pre-construction phase.

The construction phase will last approximately six months, and entail:

1. The construction of a reinforced nine-inch high concrete cap on top of the existing seawall;
2. The construction of new concrete steps along portions of the seawall base fronting the North/South Bay Front boardwalk to preserve ease of access to each public or private dock; and,
3. The construction of three-foot wide “gaps” at pre-defined locations within the tops of the seawall segments fronting North/South Bay Front to preserve a sufficient level of vertical access to the waterside beaches. These gaps would be located where the beach sand is higher to preserve ease of entry for those wishing to access the beach. To provide for flood protection during high tide events, these gaps are designed to accommodate a removable, nine-inch high barrier.

The seawall cap, steps, and access “gaps” have been integrated directly onto or adjacent to the existing landside segments of the seawall and thus the improvements can be constructed without impacting marine resources within Newport Harbor, and with minimal impact to public access to beach and harbor areas.

Project Construction Equipment

The proposed seawall repair activities will require the use of medium-duty equipment, such as light-weight jackhammers, pneumatic impact equipment, saws, forms, and hand tools along the seawall. Other equipment, such as pick-up trucks, haul trucks, and cement trucks with pumping equipment will be staged at the end of the nearest street end adjacent to the work.

A total of 16 staging areas are identified in the construction management plan, amongst the 17 work areas. The contractor will have exclusive use of the street portion of the staging area, and keep sidewalks on both sides clear for pedestrians and public access. The Construction Management Plan (Attachment 8) provides further details regarding construction activities and contains a list of anticipated construction equipment.

Construction Management and Access

Construction plans have been developed such that the project site consists of a total of 17 consecutive work areas along the perimeter of Balboa Island (Figure 1). Contractors would occupy and work in three work areas during each of the first five rotations, and two work areas during the final rotation. The work areas included in each rotation would be cleaned and cleared of any and all construction debris upon completion of construction-related activities, prior to beginning work in the next rotation. Work areas within each rotation would be spaced apart (with five unoccupied work areas between each active area), which would minimize interference with public access to the boardwalk and docks on the perimeter of Balboa Island. Additional information is provided in the Construction Management Plan (Attachment 8).

Project haul routes are identified in Figure 1. No road closures would occur as a result of the project, and circulation around Balboa Island would not be impacted as a result of construction-related traffic, since all construction-related vehicles would be limited to traveling on the access routes identified in Figure 1, and all construction-related vehicles would be parked in active staging areas, thereby not detracting from any additional street parking spaces for residents or visitors.

All construction vehicles would enter and leave Balboa Island via the Balboa Island Bridge and Marine Avenue, which is considered a primary access road. Secondary access roads directly lead to respective work and staging areas where active construction take place and are specified in the Construction Management Plan (Attachment 8) and in Figure 1.

Public beach access is discussed in Attachment 6 and the Construction Management Plan (Attachment 8).

Figure 1 - Staging Areas and Construction Routes




Imagery provided by Google and its licensors © 2017.
Additional data provided by City of Newport Beach, 2017.

Fig. Work Areas and Construction Routes

ATTACHMENT 2


Vicinity Map and Site Photographs

City of Newport Beach
Balboa Island Seawall Coping Repair



Imagery provided by National Geographic Society, ESRI and its licensors © 2016. The topographic representation depicted in this map may not portray all of the features currently found in the vicinity today and/or features depicted in this map may have changed since the original topographic map was assembled.

0 1,000 2,000
Scale in Feet



Vicinity Map

Figure 1

City of Newport Beach

























ATTACHMENT 3


3 Sets of Full Size Project Plans



CITY OF NEWPORT BEACH
PUBLIC WORKS DEPARTMENT

BALBOA ISLAND COPING REPAIR

CONTRACT NO. C-7066-1




VICINITY MAP



LOCATION MAP

SCOPE OF PROJECT



BALBOA ISLAND
COPING REPAIR
PROJECT

SCOPE OF PROJECT

DRAWING INDEX

SHEET	SHEET TITLE
1	TITLE SHEET, VICINITY MAP, LOCATION MAP, DRAWING INDEX
2	GENERAL NOTES
3	OVERALL PLAN
4	SECTION PLANS
5	SECTION PLANS
6	SECTION PLANS
7	SECTION PLANS
8	SECTION PLANS
9	SECTION PLANS
10	SECTION PLANS

SHEET	SHEET TITLE
13	DETAILS
14	DETAILS
15	DETAILS
16	DETAILS
17	DETAILS
18	DETAILS

SHEET	SHEET TITLE

80% REVIEW
SUBMITTAL
NOT FOR
CONSTRUCTION




CALL TOLL FREE
1-800-227-2600
BEFORE YOU DIG

BASIS OF BEARINGS:

BENCHMARK:

EMERGENCY TELEPHONE NUMBERS
13251
SOUTHERN CALIFORNIA GAS COMPANY
CITY OF NEWPORT BEACH
NEWPORT BEACH POLICE DEPARTMENT
NEWPORT BEACH FIRE DEPARTMENT
NEWPORT BEACH WATER DEPARTMENT
NEWPORT BEACH PUBLIC WORKS DEPARTMENT




(949) 444-3777

REVIEWED:






WARREN A. STEWART, P.E. C-12558
CIVIL ENGINEER NORTH AMERICA
DESIGNED BY: MCLS
CHECKED BY: JAW
DATE: 03/18/16


BALBOA ISLAND COPING REPAIR
TITLE SHEET, VICINITY MAP,
LOCATION MAP, DRAWING INDEX
CITY OF NEWPORT BEACH
PUBLIC WORKS DEPARTMENT
H-5235-S
SHEET 1 OF XX




80% REVIEW
SUBMITTAL
NOT FOR
CONSTRUCTION

 CALL TOLL FREE 1-800-227-2600 BEFORE YOU DIG	BASIS OF BEARINGS:		EMERGENCY TELEPHONE NUMBERS		REVIEWED:		BALBOA ISLAND COPING REPAIR
	BENCHMARK:		SOUTHERN CALIFORNIA GAS COMPANY (800) 424-4663 CITY OF NEWPORT BEACH (949) 444-3777 NEWPORT BEACH FIRE DEPARTMENT (949) 444-3777 NEWPORT BEACH POLICE DEPARTMENT (949) 444-3777 THE WARDEN CABLE (714) 442-4622 ENGINEER OF RECORD		WARDEN A. STEWART, RCE, CSES COMM. WARDEN, NORTH AMERICA DESIGNED: WCL CHECKED: WCL DATE: 03/18/16		
OVERALL PLAN							
SCALE N.T.S.							
CITY OF NEWPORT BEACH							
PUBLIC WORKS DEPARTMENT							
H-5235-S							
SHEET 3 OF XX							







APOLENA AVE. - CORAL AVE. (SOUTH BAY FRONT)



CORAL AVE. - SAPPHIRE AVE. (SOUTH BAY FRONT)




SAPPHIRE AVE. - DIAMOND AVE. (SOUTH BAY FRONT)



DIAMOND AVE. - RUBY AVE. (SOUTH BAY FRONT)

80% REVIEW
SUBMITTAL
NOT FOR
CONSTRUCTION

[illegible]





BASIS OF BEARINGS:

BENCHMARK:

EMERGENCY TELEPHONE NUMBERS	
	DAY
SOUTHERN CALIFORNIA GAS COMPANY	(800) 824-8153
SOUTHERN CALIFORNIA Edison COMPANY	(800) 715-7011
AT&T TELEPHONE COMPANY	(800) 333-1321
CITY OF NEWPORT BEACH UTILITIES DIVISION	(949) 444-3011
ORANGE COUNTY SANITATION DISTRICT	(714) 962-2411
TIME WARNER CABLE	(714) 542-6222
COX COMMUNICATIONS	
ENGINEER OF RECORD	

[illegible]


REVIEWED


WARREN A. STEWART, RCE C413				
COWI MARINE NORTH AMERICA				
DESIGNED:	W/ST	DRAWN:	MC	
CHECKED:		DATE:		

CITY OF NEWPORT BEACH


H-5235--S	SHEET 7 OF 11
-----------	---------------

H-5235--S	SHEET 7 OF 11
-----------	---------------







GARNET AVE. - PEARL AVE. (NORTH BAY FRONT)



PEARL AVE. - AGATE AVE. (NORTH BAY FRONT)



AGATE AVE. - COLLINS AVE. (NORTH BAY FRONT)



COLLINS AVE. - RUBY AVE. (NORTH BAY FRONT)

80% REVIEW
SUBMITTAL
NOT FOR
CONSTRUCTION



CALL TOLL FREE
1-800-227-2600
BEFORE YOU DIG

BASIS OF BEARINGS:

BENCHMARK:

EMERGENCY TELEPHONE NUMBERS

13251

13252

13253

13254

13255

13256

13257

13258

13259

13260

13261

13262

13263

13264

13265

13266

13267

13268

13269

13270

13271

13272

13273

13274

13275

13276

13277

13278

13279

13280

13281

13282

13283

13284

13285

13286

13287

13288

13289

13290

13291

13292

13293

13294

13295

13296

13297

13298

13299

13300

13301

13302

13303

13304

13305

13306

13307

13308

13309

13310

13311

13312

13313

13314

13315

13316

13317

13318

13319

13320

13321

13322

13323

13324

13325

13326

13327

13328

13329

13330

13331

13332

13333

13334

13335

13336

13337

13338

13339

13340

13341

13342

13343

13344

13345

13346

13347

13348

13349

13350

13351

13352

13353

13354

13355

13356

13357

13358

13359

13360

13361

13362

13363

13364

13365

13366

13367

13368

13369

13370

13371

13372

13373

13374

13375

13376

13377

13378

13379

13380

13381

13382

13383

13384

13385

13386

13387

13388

13389

13390

13391

13392

13393

13394

13395

13396

13397

13398

13399

13400

13401

13402

13403

13404

13405

13406

13407

13408

13409

13410

13411

13412

13413

13414

13415

13416

13417

13418

13419

13420

13421

13422

13423

13424

13425

13426

13427

13428

13429

13430

13431

13432

13433

13434

13435

13436

13437

13438

13439

13440

13441

13442

13443

13444

13445

13446

13447

13448

13449

13450

13451

13452

13453

13454

13455

13456

13457

13458

13459

13460

13461

13462

13463

13464

13465

13466

13467

13468

13469

13470

13471

13472

13473

13474

13475

13476

13477

13478

13479

13480

13481

13482

13483

13484

13485

13486

13487

13488

13489

13490

13491

13492

13493

13494

13495

13496

13497

13498

13499

13500

13501

13502

13503

13504

13505

13506

13507

13508

13509

13510

13511

13512

13513

13514

13515

13516

13517

13518

13519

13520

13521

13522

13523

13524

13525

13526

13527

13528

13529

13530

13531

13532

13533

13534

13535

13536

13537

13538

13539

13540

13541

13542

13543

13544

13545

13546

13547

13548

13549

13550

13551

13552

13553

13554

13555

13556

13557

13558

13559

13560

13561

13562

13563

13564

13565

13566

13567

13568

13569

13570

13571

13572

13573

13574

13575

13576

13577

13578

13579

13580

13581

13582

13583

13584

13585

13586

13587

13588

13589

13590

13591

13592

13593

13594

13595

13596

13597

13598

13599

13600

13601

13602

13603

13604

13605

13606

13607

13608

13609

13610

13611

13612

13613

13614

13615

13616

13617

13618

13619

13620

13621

13622

13623

13624

13625

13626

13627

13628

13629

13630

13631

13632

13633

13634

13635

13636

13637

13638

13639

13640

13641

13642

13643

13644

13645

13646

13647

13648

13649

13650

13651

13652

13653

13654

13655

13656

13657

13658

13659

13660

13661

13662

13663

13664

13665

13666

13667

13668

13669

13670

13671

13672

13673

13674

13675

13676

13677

13678

13679

13680

13681

13682

13683

13684

13685

13686

13687

13688

13689

13690

13691

13692

13693

13694

13695

13696

13697

13698

13699

13700

13701

13702

13703

13704

13705

13706

13707

13708

13709

13710

13711

13712

13713

13714

13715

13716

13717

13718

13719

13720

13721

13722

13723

13724

13725

13726

13727

13728

13729

13730

13731

13732

13733

13734

13735

13736

13737

13738

13739

13740

13741

13742

13743

13744

13745

13746

13747

13748

13749

13750

13751

13752

13753

13754

13755

13756

13757

13758

13759

13760

13761

13762

13763

13764

13765

13766

13767

13768

13769

13770

13771

13772

13773

13774

13775

13776

13777

13778

13779

13780

13781

13782

13783

13784

13785

13786

13787

13788

13789

13790

13791

13792

13793

13794

13795

13796

13797

13798

13799

13800

13801

13802

13803

13804

13805

13806

13807

13808

13809

13810

13811

13812

13813

13814

13815

13816

13817

13818

13819

13820

13821

13822

13823

13824

13825

13826

13827

13828

13829

13830

13831

13832

13833

13834

13835

13836

13837

13838

13839

13840

13841

13842

13843

13844

13845

13846

13847

13848

13849

13850

13851

13852

13853

13854

13855

13856

13857

13858

13859

13860

13861

13862

13863

13864

13865

13866

13867

13868

13869

13870

13871

13872

13873

13874

13875

13876

13877

13878

13879

13880

13881

13882

13883

13884

13885

13886

13887

13888

13889

13890

13891

13892

13893

13894

13895

13896

13897

13898

13899

13900

13901

13902

13903

13904

13905

13906

13907

13908

13909

13910

13911

13912

13913

13914

13915

13916

13917

13918

13919

13920

13921

13922

13923

13924

13925

13926

13927

13928

13929

13930

13931

13932

13933

13934

13935

13936

13937

13938

13939

13940

13941

13942

13943

13944

13945

13946

13947

13948

13949

13950

13951

13952

13953

13954

13955

13956

13957

13958

13959

13960

13961

13962

13963

13964

13965

13966

13967

13968

13969

13970

13971

13972

13973

13974

13975

13976

13977

13978

13979

13980

13981

13982

13983

13984

13985

13986

13987

13988

13989

13990

13991

13992

13993

13994

13995

13996

13997

13998

13999

14000

14001

14002

14003

14004

14005

14006

14007

14008

14009

14010

14011

14012

14013

14014

14015

14016

14017

14018

14019

14020

14021

14022

14023

14024

14025

14026

14027

14028

14029

14030

14031

14032

14033

14034

14035

14036

14037

14038

14039

14040

14041

14042

14043

14044

14045

14046

14047

14048

14049

14050

14051

14052

14053

14054

14055

14056

14057

14058

14059

14060

14061

14062

14063

14064

14065

14066

14067

14068

14069

14070

14071

14072

14073

14074

14075

14076

14077

14078

14079

14080

14081

14082

14083

14084

14085

14086

14087

14088

14089

14090

14091

14092

14093

14094

14095

14096

14097

14098

14099

14100

14101

14102

14103

14104

14105

14106

14107

14108

14109

14110

14111

14112

14113

14114

14115

14116

14117

14118

14119

14120

14121

14122

14123

14124

14125

14126

14127

14128

14129

14130

14131

14132

14133

14134

14135

14136

14137

14138

14139

14140

14141

14142

14143

14144

14145

14146

14147

14148

14149

14150

14151

14152

14153

14154

14155

14156

14157

14158

14159

14160

14161

14162

14163

14164

14165

14166

14167

14168

14169

14170

14171

14172

14173

14174

14175

14176

14177

14178

14179

14180

14181

14182

14183

14184

14185

14186

14187

14188

14189

14190

14191

14192

14193

14194

14195

14196

14197

14198

14199

14200

14201

14202

14203

14204

14205

14206

14207

14208

14209

14210

14211

14212

14213

14214

14215

14216

14217

14218

14219

14220

14221

14222

14223

14224

14225

14226

14227

14228

14229

14230

14231

14232

14233

14234

14235

14236

14237

14238

14239

14240

14241

14242

14243

14244

14245

14246

14247

14248

14249

14250

14251

14252

14253

14254

14255

14256

14257

14258

14259

14260

14261

14262

14263

14264

14265

14266

14267

14268

14269

14270

14271

14272

14273

14274

14275

14276

14277

14278

14279

14280

14281

14282

14283

14284

14285

14286

14287

14288

14289

14290

14291

14292

14293

14294

14295

14296

14297

14298

14299

14300

14301

14302

14303

14304

14305

14306

14307

14308

14309

14310

14311

14312

14313

14314

14315

14316

14317

14318

14319

14320

14321

14322

14323

14324

14325

14326

14327

14328

14329

14330

14331

14332

14333

14334

14335

14336

14337

14338

14339

14340

14341

14342

14343

14344

14345

14346

14347

14348

14349

14350

14351

14352

14353

14354

14355

14356

14357

14358

14359

14360

14361

14362

14363

14364

14365


14366

14367

14368


14369

14



	CALL TOLL FREE 1-800-227-2600 BEFORE YOU DIG		BASIS OF BEARINGS:		BENCHMARK:		EMERGENCY TELEPHONE NUMBERS SOUTHERN CALIFORNIA GAS COMPANY (800) 854-4653 CITY OF NEWPORT BEACH (949) 333-3321 NEWPORT BEACH FIRE DEPARTMENT (949) 333-3321 NEWPORT BEACH POLICE DEPARTMENT (949) 333-3321 ORANGE COUNTY SANITATION DISTRICT (714) 862-3411 NEWPORT BEACH HARBOUR (714) 862-3422 NO. COMMUNICATIONS EXEMPT OF RECORD		NO. DATE REVISION		NO. DATE REVISION		DESIGNED: MCL CHECKED: GWP		DATE: 03/18/16		WARREN A. STEWART, P.E. 00258 COMM. MARINE NORTH AMERICA		SECTION PLANS		SCALE 1:10		BALBOA ISLAND COPING REPAIR	

80% REVIEW
SUBMITTAL
NOT FOR
CONSTRUCTION



CALL TOLL FREE
1-800-227-2600
BEFORE YOU DIG

BASIS OF BEARINGS:

BENCHMARK:

EMERGENCY TELEPHONE NUMBERS
Southern California Gas Company (800) 441-4343
City of Newport Beach (949) 441-3111
City of Newport Beach (949) 441-3111
Newport Beach Police Department (949) 441-2000
Newport Beach Fire Department (949) 441-2000
Newport Beach Harbor Police (949) 441-2000
Newport Beach Harbor Police (949) 441-2000



NO.	DATE	REVISION

REVIEWED:
WARREN A. STEWART, P.E. C2259
COWI MARINE NORTH AMERICA
DESIGNED (MST) DRAWN: MCLS
CHECKED: GAWP DATE: 03/09/16



BASIS OF BEARINGS:

CALL TOLL FREE
1-800-227-2600
BEFORE YOU DIG

BENCHMARK:

EMERGENCY TRI EDHANE NII MPEDS

EMERGENCY TELEPHONE NUMBERS	DAY	NIGHT
SOUTHERN CALIFORNIA GAS COMPANY	(800) 824-8153	
SOUTHERN CALIFORNIA Edison COMPANY	(800) 811-1911	
AT&T TELEPHONE COMPANY	(800) 332-1201	
CITY OF NEWPORT BEACH UTILITIES DIVISION	(949) 644-1301	(949) 644-3771
ORANGE COUNTY SANITATION DISTRICT	(714) 962-2411	
THE MANNING CABLE	(714) 542-6222	
COX COMMUNICATIONS		
ENGINEER OF RECORD		

REVIEWED:






WARREN A. STEWART, ROE C41358	
COWI MARINE NORTH AMERICA	
DESIGNED: WNST	DRAWN: MCLS

BALBOA ISLAND COPING REPAIR

TYPICAL SECTION


CITY OF NEWPORT BEACH	H-5235-S
-----------------------	----------

CITY OF NEWPURI BEACH
PUBLIC WORKS DEPARTMENT
SHEET 13 OF XX




80% REVIEW
SUBMITTAL
NOT FOR
CONSTRUCTION

1. ROUT TOP OF CRACK TO FORM VEE-GROVE; THOROUGHLY CLEAN WITH COMPRESSED AIR AND WIRE-WHEEL TOOL.
2. FOR CRACKS $\frac{1}{8}$ " WIDE AND GREATER: FILL CRACK WITH OVEN DRIED SILICA SAND
3. APPLY METHACRYLATE SEALER FOLLOWING MANUFACTURER'S RECOMMENDATIONS AND ALLOW TO PENETRATE CRACK.
4. CAST OVEN DRY SILICA SAND ON TOP OF THE CRACK TO ABSORB EXCESS. SCRAPE OFF AFTER INITIAL SET.




1. THOROUGHLY CLEAN WITH COMPRESSED AIR AND WIRE WHEEL. TOOL REMOVE ALL LOOSE DEBRIS.
2. FOR CRACKS $\frac{1}{8}$ " WIDE AND GREATER, FILL CRACK WITH OVER DRIED SILICA SAND.
3. SEAL SURFACE OF CRACK AND INSTALL INJECTION PORTS AT IF O.C. USING CRACK INJECTION KIT. FOLLOW ALL PREPARED EPOXY PER MANUFACTURER'S INSTRUCTIONS.
4. START INJECTION AT THE LOWEST PORT UNTIL EPOXY SHOWS AT THE UPPER PORT. STOP INJECTION AT THE UPPER PORT. REPEAT UNTIL ALL PORTS HAVE BEEN INJECTED.
5. WHEN INJECTED EPOXY HAS CURED, REMOVE PORTS AND SEALING EPOXY. GRIND SURFACE SMOOTH.
6. FOR SURFACES THAT WILL BE REMAIN FINISH TO MATCH SURROUNDING SURFACE




VERTICAL SURFACE CRACKS

TOP SURFACE CRACKS ONLY



2 SPALL REPAIR



3 EXPANSION JOINTS

1. WHERE INDICATED ON DRAWINGS, COMPLETELY REMOVE EXISTING JOINT MATERIALS BEFORE CONSTRUCTING CAP RAISE AND MAKE ANY CONCRETE REPAIRS NEEDED AT CORNERS AND EDGES TO PROVIDE BASE FOR JOINT SEALANT. OTHERWISE START W/ NOTE #2.
2. CONSTRUCT NEW CAP RAISE WITH GAP FOR EXPANSION JOINTS ON TOP OF EXISTING. MATCH WIDTHS.
3. AFTER CAP RAISE HAS CURED, REMOVE ANY FORM MATERIALS IN GAP AND COMPLETELY CLEAN.
4. APPLY BONDING AGENT RECOMMENDED BY SEALANT MFR. FOLLOW MFR'S INSTRUCTIONS.
5. INSTALL BACKING ROD AS RECOMMENDED BY MFR. ROD SHOULD BE 1/2" BELOW SURFACE OF JOINT. FOLLOW RECOMMENDATION FOR MAKING 90° CORNERS.
6. FILL JOINTS WITH EXISTING (IF INDICATED) WITH SEALANT AND ALLOW TO CURE. SEALANT SHALL COVER ENTIRE JOINT WITH NOT Voids. SCHEDULE JOINT SEALING SO THAT SEAL WILL NOT BE IMPACTED BY HIGH TRAFFIC UNTIL FULLY CURED.

EXPANSION JOINT NOTES:

1. WHERE INDICATED ON DRAWINGS, FOUR-STEP 1) REMOVE EXISTING JOINT MATERIAL, 2) PREPARE JOINT, 3) APPLY SEALANT, 4) FINISH JOINT. IF ANY CONCRETE REPAIRS ARE NEEDED AT CORNERS AND EDGES TO PROVIDE BASE FOR JOINT SEALANT, OTHERWISE START W/ NOTE #2.
2. CONSTRUCT NEW PAISE WITH GAP FOR EXPANSION JOINTS ON TOP OF EXISTING. MATCH WIDTHS.
3. AFTER PAISE HAS CURED, REMOVE ANY FORM MATERIALS IN GAP AND COMPLETELY CLEAN.
4. APPLY BONDING AGENT RECOMMENDED BY SEALANT MFR. FOLLOW MFR'S INSTRUCTIONS.

EXPANSION JOINT NOTES:

5. INSTALL BACKING ROD AS RECOMMENDED BY MFR. ROD SHOULD BE $\frac{1}{2}$ " BELOW SURFACE OF JOINT. FOLLOW RECOMMENDATION FOR MAKING 90° CORNERS.
6. FILL JOINTS (NEW & EXISTING IF INDICATED) WITH SEALANT AND ALLOW TO CURE. SEALANT SHALL COVER ENTIRE JOINT WITH NOT VOIDS. SCHEDULE JOINT SEALING SO THAT THEY WILL NOT BE IMPACTED BY HIGH TIDES UNTIL FULLY CURED.

EXPANSION JOINT NOTES:

3	EXP	N.T.S.
---	-----	--------



CALL TOLL FREE
1-800-227-2600
BEFORE YOU DECIDE

BASIS OF BEARINGS:

BENCHMARK.

EMERGENCY TELEPHONE NUMBERS	
	DAY
SOUTHERN CALIFORNIA GAS COMPANY	(800) 824-8153
SOUTHERN PACIFIC COMPANY	(800) 824-8153
AT&T TELEPHONE COMPANY	(800) 332-1321
CITY OF NEWPORT BEACH UTILITIES DIVISION	(949) 644-3011
ORANGE COUNTY SANITATION DISTRICT	(714) 962-2411
TIME WARNER CABLE	(714) 542-4222
COX COMMUNICATIONS	
ENGINEER OF RECORD	

REVIEWED:

REPAIR DETAILS

DESIGNED:	DRAWN:
-----------	--------

CITY OF NEWPORT BEACH

INST	MCLS
CHECKED:	DATE:

CITY OF NEWPORT BEACH
PUBLIC WORKS DEPARTMENT

80% REVIEW
SUBMITTAL
NOT FOR
CONSTRUCTION

ATTACHMENT 4

Bulkhead Condition Report

JUNE 2017
CITY OF NEWPORT BEACH

Bulkhead Condition Report for Portions of the Balboa Island Seawall

COWI

JUNE 2017
CITY OF NEWPORT BEACH

Bulkhead Condition Report for Portions of the Balboa Island Seawall

PROJECT NO.

A074385

DOCUMENT NO.

VERSION

1

DATE OF ISSUE

6/30/2017

DESCRIPTION

Deliverable

PREPARED

WNSX

CHECKED

JWK

APPROVED

WNSX

CONTENTS

1	Executive Summary	4
2	Background and Purpose	6
2.1	Project Background	6
2.2	Report Purpose	6
2.3	Statement of the Preparer's Qualifications	7
3	Condition Assessment	8
3.1	Original Construction	8
3.2	Previous Reports	9
3.3	Current Structural Condition of the Seawall	11
3.4	Capacity of the Wall to Resist Flooding	12
4	Structural Capacity for Coping Raise	13
4.1	Description of Existing Coping	13
4.2	Details of the Coping Raise	15
5	References	17

Appendices

1 Executive Summary

The current height of the seawall is insufficient to resist flooding due to overtopping during very high tides, especially when combined with storm conditions. Refer to the main report "Assessment for Seawall Structural Integrity and Potential for Seawall Over-Topping for Balboa Island and Little Balboa Island" for complete details. Within the cover letter of Appendix C of the report (URS/Everest, 2011, p. iii), the first phase towards a long-term solution for the wall is to raise the current cap elevation. This recommendation is being implemented with this project.

In December 2015, the City of Newport Beach, Department of Public Works (City) commissioned COWI North America, Inc. (COWI) to prepare contract documents for the construction of a 9-in. high addition to the existing seawall coping of the bulkhead that surrounds Balboa Island. The project starts from Bayfront South and Grand Canal, continues around the west end of the island, and finishes at Bayfront North and Grand Canal. The total length of the proposed coping raise is approximately 7,400 LF. Prior projects raised the top of the coping along the Grand Canal (as well as all of Little Balboa Island); thus, this project raises only the coping not yet raised.

The purpose of this report is to provide a stand-alone attachments based on previous analyses and our own investigation per standard requirements. A statement of the preparer's qualifications is provided.

The current bulkhead for the majority of the perimeter of the island was rebuilt circa 1938 using plans completed a few years earlier (Newport Beach, 1935). The design utilized precast soldier concrete piles spaced typically at 11 ft – 8 in. on-center, with precast concrete in-fill panels between the piles. The soldier piles were restrained at the top with 1¼" steel tie-back rods anchored to Douglas fir timber pile dead men. A 500 ft reach of the then pre-existing concrete sheet pile wall at the west end of the island (between Emerald Avenue at Bayfront South and Park Avenue) was incorporated "as is", with just a partial replacement of the coping to match the rest of the project.

A number of previous condition reports and repair project drawings were provided by the City for this review. These included:

- > Cash & Associates (1985) and Repair Project (1988)
- > Little Balboa Island Seawall Raising (1989)
- > Cash & Associates (2005)
- > URS (2010/2011)
- > COWI (2016)
- > Current Project Inspection

The current condition of the Balboa Island seawall within the scope of this project is **Fair**, in accordance with the rating requirements of American Society of Civil Engineers, Manual of Standard Practice, MOP 130 – Waterfront Facilities Inspection and Assessment (ASCE, 2015, p. 64). As such, all primary structural elements are sound; but minor to moderate defects or deterioration observed. Localized areas of moderate to advanced deterioration may be present, but do not significantly reduce the load bearing capacity of the structure. Repairs are recommended, but the priority of the recommended repairs is low.

In constructing the coping raise, a number of the defects that still occur on top of the coping will be corrected by the process itself. Typically, the existing top surface will be roughened to bond the new concrete to the old. However where loose concrete is encountered, it will be removed to sound substrata before placing new concrete on top.

The condition of the tieback system has not been re-examined since 1985 and the tie rods are assumed to be in critical condition, either severely corroded or severed. Because of this, seawalls must not have a mudline or rip-rap in front of the wall lower than 4 ft below the pavement behind the wall. Otherwise, the seawall must have the tieback system restored. Based upon our most recent inspection (June 2017), there is only one reach, 350± ft from the Collins Island bridge along the Bayfront North boardwalk, that doesn't conform to this requirement. However, there is no visible signs of distress, and other factor maybe contributing to the success of this wall.

There is no positive connection provided between the top of the precast wall planks and soldier piles and the cast-in-place coping. The coping remains in place due to its own self-weight and any bond value and friction that might develop along the boundary between it and the pre-cast elements, which are embedded into the coping. This will be corrected with the project.

The coping raise will add 9 in. to the height of the walls. To accomplish this, the existing corner chamfers and rounds will be removed and the top of existing coping will be intentionally roughed to create a good bond with the new concrete. When found, any loose and deteriorated concrete will be removed to sound concrete. Next hooked rebar dowels will be drilled and grouted into the top of the existing concrete. Continuous rebar will be placed along the top, and the new raise will be poured. The positive connection between the coping and the piles below is made by extending one of the dowel holes that falls over each pile an additional 2 ft or so, through the cap and into the pile underneath. A singular, larger and longer dowel is grouted in place.

Any other repairs can be made at this time at the discretion of the City.

2 Background and Purpose

2.1 Project Background

In December 2015, the City of Newport Beach, Department of Public Works (City) commissioned COWI North America, Inc. (COWI) to prepare contract documents for the construction of a 9-in. high addition to the existing seawall coping¹ of the bulkhead that surrounds Balboa Island. The project starts from Bayfront South and Grand Canal, continues around the west end of the island, and finishes at Bayfront North and Grand Canal. The total length of the proposed coping raise is approximately 7,400 LF. Prior projects raised the top of the coping along the Grand Canal (as well as all of Little Balboa Island); thus, this project raises only the coping not yet raised.

In July 2016, the City requested COWI prepare a Coastal Development Permit (CDP) application to the California Coastal Commission (CCC) for the project. This was submitted in October, 2016. In November 2016, the CCC responded requesting more information regarding the project. One of the requested items was a Bulkhead Condition Report. Response to the CCC's November letter was submitted to the City in March of 2017. During this period, jurisdiction for the project switched from the CCC to the City's Planning Department, and the responses to the November CCC letter were re-directed to the Planning Department. In early May, 2017, COWI received a request to provide additional information from the Planning Department, of which one item was a Bulkhead Condition Report.

2.2 Report Purpose

The purpose of this report is (as defined by the City's Planning Department in their request for additional information):

"1. Create these stand-alone attachments:

- a. Create a **Bulkhead Condition Report** (Section 21.30.15.E.3) – based on previous analyses and your own investigation per the standard requirements listed below. Include a statement that existing bulkhead is in good condition and can support the coping extension.
 3. *Bulkhead Condition Report. Where a coastal hazards report shows that an existing bulkhead on the site cannot be removed and/or an existing or replacement bulkhead is required to protect existing principal structures or public facilities, the applicant shall submit a bulkhead condition report that includes the following:*
 - a. *A statement of the preparer's qualifications;*
 - b. *An analysis of the condition of any existing bulkhead including whether the top elevation meets current City standards, the condition of the sheetpiles or panels, the condition of existing tiebacks and/or deadmen or similar, and any other relevant conditions;*

¹ The City's preferred term is "coping" to reference the cast-in-place concrete poured on top of the precast concrete slab and pile bulkhead system. These are the terms used in the original construction documents. Other terms (i.e., "cap") have also been used in previous reports.

- c. Recommendations regarding the need for repair, augmentation or replacement of the bulkhead or any parts thereof;*
- d. If augmentation or replacement in the existing alignment is necessary, recommendations that will avoid seaward encroachment of the bulkhead;*
- e. If replacement is necessary and the existing bulkhead is not in alignment with adjacent bulkheads, recommended alternatives that will relocate the bulkhead in as much in alignment with adjacent bulkheads, and as far landward, as possible."*

2.3 Statement of the Preparer's Qualifications

COWI is a highly competent specialty engineering firm, with over 85 years of experience in the design, repair, and construction of marine and coastal structures such as the Balboa Island Seawall. With more than 6,400 staff worldwide and 100 marine-specialty technical staff in 12 North American offices, our team has extensive experience in consultation, planning, inspection, analysis, and design services, solving structural engineering issues associated with the inspection and rehabilitation of existing structures. Our quality lies in the composition of our inspection teams: all of our inspections are performed by our in-house California registered Professional Engineers and Structural Engineers, including (when needed) our commercially trained engineer-divers.

The author of this report is a California registered Structural Engineer and has over 40 years of professional engineering experience on a variety of projects for local, state, and federal agencies, private utilities and institutional clients. This includes over 25 years managing marine, waterfront, port and harbor, transportation, and other infrastructure projects Southern California. On over 150 projects, he has been responsible for the production, coordination and review of engineering design and construction documents, cost estimates, project specifications, construction management, report writing and/or reviews. He was elected to the American Society of Civil Engineers (ASCE) Academy of Coastal, Ocean, Port & Navigation Engineers (ACOPNE) and has been a member of the Coasts, Oceans, Ports, & Rivers Institute (COPRI) Ports & Harbor Committee for a number of years. He sits on the national ASCE/COPRI committee that wrote *Waterfront Facilities Inspection and Assessment, Manual of Practice MOP-130*, which was recently published by ASCE.

3 Condition Assessment

3.1 Original Construction

According to a Cash & Associates Report (C&A, 2005), the current bulkhead for the majority of the perimeter of the island was rebuilt circa 1938 using plans completed a few years earlier (Newport Beach, 1935). The design utilized precast soldier concrete piles spaced typically at 11 ft – 8 in. on-center, with precast concrete in-fill panels between the piles. The soldier piles were restrained at the top with 1¼" steel tie-back rods anchored to Douglas fir timber pile dead men. Figure 1, taken from the original drawings, shows the typical cross-section of the seawall.




Figure 1 - Original Seawall Construction, 1938

Previously constructed timber bulkheads were replaced by this project. However, a 500 ft reach of the then pre-existing concrete sheet pile wall at the west end of the island (between Emerald Avenue at Bayfront South and Park Avenue) was incorporated "as is", with just a partial

replacement of the coping to match the rest of the project. Apparently, this wall was constructed in the mid-1920's, and evidently was considered sufficiently adequate to be incorporated into the project in lieu of removal and reconstruction. Figure 2, taken from the original drawings, shows the 1920's wall with the new coping.




Figure 2 - Existing Seawall Incorporated into Project

3.2 Previous Reports

A number of previous reports and repair project drawings were provided by the City. Some of these had significant bearing on this report. All of the reports are included in the appendices. All of the reports specifically excluded seismic issues from the analysis and reporting. These reports are further discussed below.

3.2.1 Cash & Associates (1985) and Repair Project (1988)

A 1985 investigation of the entire seawall was conducted by Cash & Associates (C&A, 1985). They found a number of issues that resulted in repair projects being undertaken. Of foremost concern was the condition of the tiebacks (see Figure 1). Six locations were selected for excavation (test pits) to uncover the tiebacks and observe their conditions. Four of the pits were located on Little Balboa Island behind the 1938 wall, but are indicative of the probable condition of all 1938 tiebacks throughout. The remaining two pits were located at the west end behind the 1920's concrete sheet pile wall as described above. The drawings do not indicate that the tie-rods were replaced in 1938; hence they are assumed original. All tie-rods were found to be heavily corroded with significant loss of section or severed, and no longer effective. These conditions are probably representative of all the tiebacks throughout. However based upon calculation that they prepared,

tiebacks are not needed if the soil in front (waterside) of the seawall is not lower than 5 ft from the top of the coping².

Rather than replacing the tiebacks, a project was initiated to place rock rip-rap along portions of the bulkhead (Newport Beach, 1988). This provides a buttress for the wall. The capacity of the wall in the cantilever configuration was checked in the 1985 report, A subsequent independent calculation has not been made.

3.2.2 Little Balboa Island Seawall Raising (1989)

In 1987 a project to raise the seawall along East Bay Front, Little Balboa Island was undertaken as a Department of Public Works in-house project, and completed two years later (Newport Beach, 1989). The method used was similar to that proposed for the current project; i.e., constructing a new continuous raise on top of the existing coping. The new elevation was given to be 9.0 ft MLLW for the majority of length with the southern-most 150 ft at 9.5 MLLW.

3.2.3 Cash & Associates (2005)

In 2005, Cash & Associates completed another inspection and condition assessment for Balboa Island and Little Balboa Island (C&A, 2005). The seawall was generally noted in good condition; but in 274 pages, the report detailed defects requiring repairs, with photos. Repairs were categorized according to three priorities: (1) non-seismic, structural repairs that posed greatest danger to life safety; (2) repair of property damage; and (3) cosmetic damage. Only one non-structural Priority 1 was noted (a cover for an electrical pull box).

A cost estimate for the repairs was provided along with typical details for completing the repairs.

3.2.4 URS (2010/2011)

In 2010 URS (successor to Cash & Associates) issued another condition assessment report. This report was included as Appendix C in the Everest Consulting, Inc. report (URS/Everest, 2011).

The stated purpose of the report was "to assess the current structural condition and remaining lifespan of the Balboa Island seawall and its ability to withstand existing tidal and swell events and future projections of sea level rise ... [and] was not intended to include a detailed survey of individual distresses in the seawall, but rather to highlight general conditions for the purpose of determining remaining useful life of the seawall and repair/replacement options."

² It should be noted that the top of the coping is a convenient reference point but has little structural significance. The true measure of the wall stability is how far the soil in front of the wall (mudline) is below the top of the sidewalk behind the wall. Thus, any raising of the coping has no effect on the wall capacity or stability as thus calculated. Note that the 2011 URS report (discussed in § 3.2.4 below) states that the wall "would be stable without tie-rods for gravity loads, if the exposed height of support (i.e., the difference in elevation between top of boardwalk and top of mudline) was no greater than 5 feet." This is different than the 1985 statement. In reviewing the calculations included with the 1985 report, the top of side walk is assumed to be 13 in. below the top of coping, and the max distance to the mudline is shown as 4.85 ft. Thus, the statement above should say "... the difference in elevation between top of boardwalk and top of mudline was no greater than 4 feet", using rounded numbers.

The report notes that the "1985 Report prompted the City to stabilize the toe of the seawall at four locations around the Island by constructing rock revetments. These locations are at the three corners of Little Balboa and along the aforementioned 500-foot-long section of seawall at the western end of Big Balboa (see Photo 1). Rock revetments were also installed at the two corners of Big Balboa that form the Grand Canal. Observations also noted a separate seawall stabilization project performed along the seawall east of the Balboa Island Ferry Boat Landing. Earth anchors were installed, as shown in Photo 2, and a submerged concrete block revetment was placed at the toe of the seawall."

It further notes "The City of Newport Beach also pursued a repair and maintenance program in response to the 2005 Report which detailed extensive distress (i.e., cracks and spalls) in the Balboa Island seawalls. Most of the noted distresses in the seawall cap and soldier piles were repaired (see Photo 3 for an example of a typical repair)."

The report went on to document the various modifications that had been made over the years and additional repairs needed. It also included discussions on other elements (e.g. bridges, ferry) that are not included in this project.

3.2.5 COWI (2016)

At the request of the City, COWI completed an inspection and condition assessment of the west end bulkhead (COWI, 2016). Two primary areas were investigated: (1) the condition of 500 LF of wall south of Park Avenue (i.e., the old concrete sheet pile wall as described in § 3.1 above); and (2) the condition and panel tip elevation of a similar length of wall north of Park Avenue (typical soldier pile & infill panel construction). In addition to the condition of the concrete for both, the revetment placed in 1988 to buttress the old wall was checked for current condition and any signs of settlement or instability. The tip of the wall panels on the north side were probed to see how deep they were placed.

In general, the wall and coping conditions were rated as Fair per MOP-130 (ASCE, 2015), with isolated defects rated minor to major. The revetment along the south wall was found to be essentially as shown in the drawings and the tip elevations of the wall panels were found to be much deeper than shown on the drawings (surprising but welcomed news).

3.2.6 Current Project Inspection

Prior to starting design of the current project in 2016 to raise the coping, an inspection and condition assessment of the seawall was undertaken primarily to document defects that would need to be addressed in conjunction with the proposed construction. Cosmetic repairs that would not affect the new construction were not included in the project. The required repairs are included in the project drawings.

3.3 Current Structural Condition of the Seawall

The current condition of the Balboa Island seawall within the scope of this project is **Fair**, in accordance with the rating requirements of American Society of Civil Engineers, Manual of Standard Practice, *MOP 130 – Waterfront Facilities Inspection and Assessment* (ASCE, 2015, p. 64). In rating the wall as such, it is recognized that "all primary structural elements are sound; but

minor to moderate defects or deterioration observed. Localized areas of moderate to advanced deterioration may be present, but do not significantly reduce the load bearing capacity of the structure. Repairs are recommended, but the priority of the recommended repairs is low."

Most of the defects noted in the reports in §3.2 above are cosmetic in nature or of a low priority so that they can be repaired when most economically advantageous. All of the major defects noted in these earlier reports have been repaired along with some of the more unsightly cosmetic defects.

In constructing the coping raise, a number of the defects that still occur on top of the coping will be corrected by the process itself. Typically, the existing top surface will be roughened to bond the new concrete to the old. However where loose concrete is encountered, it will be removed to sound substrata before placing new concrete on top.

The condition of the tieback system has not been re-examined and the tie rods are assumed to be in critical condition, either severely corroded or severed. Because of this, seawalls must not have a mudline or rip-rap in front of the wall greater than 4 ft lower than the pavement behind the wall, as discussed in §3.2.1 above, including footnote 2. Otherwise, the seawall must have the tieback system restored. In the most recent inspections (July 2016 / June 2107) these conditions were all met, with the exception of ±350 ft of the north-west end seawall between Park Avenue / Collins Island Bridge and Emerald & North Bayfront. As discussed in the west-end seawall report noted above (COWI, 2016), the exact structural conditions are unknown. However, there does not appear to be structural distress to the wall even though the mudline is as much as 6 to 7 ft below the pavement in some locations.

It is also noted in the reports referenced above, and reiterated here, that seismic performance has not been evaluated and is specifically excluded from the analyses.

3.4 Capacity of the Wall to Resist Flooding

The current height of the seawall is insufficient to resist flooding due to overtopping during very high tides, especially when combined with storm conditions. Refer to the main report *"Assessment for Seawall Structural Integrity and Potential for Seawall Over-Topping for Balboa Island and Little Balboa Island"* for complete details. Within the cover letter of Appendix C of the report (URS/Everest, 2011, p. iii), the first phase towards a long-term solution for the wall is to raise the current cap elevation. This recommendation is being implemented with this project.

4 Structural Capacity for Coping Raise

4.1 Description of Existing Coping

As mentioned in previous reports and confirmed herein, there is no positive connection between the top of the 1938 precast wall planks (slabs) and cast-in-place coping. As shown below (Figure 3), reproduced to scale from the original construction drawings, the only connection is the lifting hook in the precast soldier pile (shown as a dashed line). We cannot be sure that this even exists, as there is the possibility it was burned-off to facilitate driving. In fact, there is a handwritten notation on the current version of the drawings that this hook does not exist for most of the piles. In any case, calculations show that this hook would not be sufficient to transmit all of the lateral loads against the coping into the wall (or more likely the soldier piles) below.




Figure 3 - Coping cross-sections, A, B, C, and D

Thus, the coping remains in place due to its own self-weight and any bond value and friction that might develop along the boundary between it and the pre-cast plank, embedded 6 to 8 in. into the coping. Coping type D is unique in that it re-uses an existing wall constructed before the 1938 project, and modifies the existing coping to resemble the other coping types used in the project.

The connection between the previous and modified is simply two pins extending across the cold joint, each pin embedded 3 in. on either side of the joint. The connections appears to have held over the years, but the joint is visible from the outside as shown in Figure 4.



Figure 4 - Cold joint visible along Coping Type D

The location of the various coping is shown in Figure 5.




Figure 5 - Location of coping types

4.2 Details of the Coping Raise

The coping raise will add 9 in. to the height of the walls. To accomplish this, the existing corner chamfers and rounds will be removed and the top of existing coping will be intentionally roughed to create a good bond with the new concrete. Next hooked rebar dowels will be drilled and grouted into the top of the existing concrete. These will be staggered, and the exact spacing will be determined during design. Two continuous rebars will be placed at the top, and the new raise will be poured as shown in Figure 6. Reinforcing shown is preliminary and subject to change. Where needed for access, a concrete step about 3 ft long will be constructed as shown.




Figure 6 – Details of Typical Coping Raise

Because of the lack of a positive connection between the existing coping and the wall and piles below, and because the added height will add some extra lateral load to the wall, a positive connection is desirable. This can be easily accomplished by extending one of the dowel holes shown in Figure 6 that falls over each pile an additional 2 ft or so, through the cap and into the pile underneath. A singular, larger and longer dowel is grouted in place. See Figure 7.




Figure 7 - Detail of Proposed Connection between (E) Coping and (E) Pile

4.3 Summary

Based upon the review of the previous reports and our more recent inspections, it is determined that the existing seawall can be raised 9 in. by constructing a new concrete coping raise on top of the existing coping providing the all of the following is including in the project:

- > The top of the existing coping is removed and/or roughened to allow the new concrete to bond to the existing.
- > When found, any loose and deteriorated concrete is removed to sound concrete and the void filled with the new raise pour.
- > Anchor dowels are drilled and grouted into the top of the existing coping to provide a positive load resisting connection.
- > A positive connection between the existing coping and the existing soldier piles below is made by extending one of the anchor dowel holes into the pile below using a longer and larger diameter rebar dowel.
- > The new coping raise is adequately reinforced to accept all new loads applied.
- > The new concrete be of high-strength, high quality, marine-grade concrete.

5 References

- ASCE. (2015). *MOP 130 – Waterfront Facilities Inspection and Assessment*. Reston VA: American Society of Civil Engineers.
- C&A. (1985). *Condition Assessment of Balboa Island Sea Walls*. Newport Beach: Cash & Associates.
- C&A. (2005). *Balboa and Little Balboa Island Bulkhead Inspection Report*. Newport Beach, CA: Cash & Associates.
- COWI. (2016). *Condition Assessment Inspection Report, West End Seawall, Balboa Island*. Long Beach: COWI North America, Inc.
- Newport Beach. (1935, Sep 30). Plan No. 400 for Improvement of S. Bay Front, N. Bay Front, E. Bay Front and the E. and W. Promenades of Grand Canal. *R-5457-S*. Newport Beach, Department of Public Works: City of Newport Beach.
- Newport Beach. (1988, Mar 31). Balboa Island Bulkhead Repair Near Waters Way. *Contract No. 2525*. City of Newport Beach, Department of Public Works.
- Newport Beach. (1989). *Little Balboa Island Seawall Raising, H-5122-2*. Newport Beach: City of Newport Beach, Department of Public Works.
- NOAA. (2016). *Mean Sea Level Trend - 9410580 Newport Beach, California*. Retrieved Sep 6, 2016, from http://tidesandcurrents.noaa.gov/sltrends/sltrends_station.shtml?stnid=9410580
- URS/Everest. (2011, April 21). Appendix C - Balboa Island Seawalls Condition Assessment Study and Report. *Assessment for Seawall Structural Integrity and Potential for Seawall Over-Topping for Balboa Island and Little Balboa Island*. Newport Beach: URS Corporation and Everest International Consultants, Inc.

Appendices

Appendix 1

Cash & Associates (1985) and Repair Project (1988)

TABLE OF CONTENTS

INTRODUCTION	1
EXECUTIVE SUMMARY	3
SITE CONDITIONS	3
FIELD INVESTIGATIONS	
Approach	3
DATA COLLECTION ("Little Balboa Island")	
Test Pit No. 1	6
No. 2	6
No. 3	6
No. 4	9
Cap & Soldier Piles	9
DATA COLLECTION (West End of Balboa Island)	
Test Pit No. 5	9
No. 6	9
Cap & Sheet Piles	12
RESULTS & CONCLUSIONS	
"Little Balboa Island"	12
West End of Balboa Island (496'-0)	13
GENERAL DISCUSSION	14
RECOMMENDATIONS	14
APPENDIX	
Photographs	
Bulkhead Calculations	
Miscellaneous Sounding Information	
Reference Document Listing	
Drawing No. 2565-1 (in front cover holder)	
ILLUSTRATIONS	
Fig. No. 1 - Vicinity Map	2
Fig. No. 2 - Type 1 Bulkhead	4
Fig. No. 3 - Type 2 Bulkhead	5
Fig. No. 4 - Test Pit No. 1	7
Fig. No. 5 - Test Pit No. 3	8
Fig. No. 6 - Test Pit No. 4	10
Fig. No. 7 - Test Pit No. 5 & 6	11
Fig. No. 8, 9, 10 - Alternate Design Concepts	16

INTRODUCTION

Cash & Associates Engineers has been requested by the City of Newport Beach to evaluate the structural integrity of the existing bulkheads in specified areas around Balboa Island. The investigation was accomplished by observation and measurements at the project site and calculations evaluating the observed existing condition. The existing bulkheads included in this study are all over 50 years old. We have been told that in 1935 the concrete caps were extended in several areas around the perimeter of the island to provide greater protection from storm conditions.

This study was conducted at two basic localities on Balboa Island. Site No. 1 is considered "Little Balboa Island" just east of The Grand Canal. Site No. 2 is a 496 foot length of curved bulkhead on the far west end of Balboa Island across from Collins Island. See Figure 1 for the vicinity map locating the two sites and the test pits excavated in the investigation.


The scope of the investigation was as follows:

- o Make a visual condition survey of the bulkhead cap and wall
- o Administer the unearthing of tie-rods at six (6) representative locations
- o Evaluate the structural integrity of the existing tie-rods and tie-back system
- o Evaluate, if possible, the condition of the timber piles being utilized as dead men
- o Provide documentation regarding the existing mudline elevations around the island
- o Provide calculations evaluating the structural stability of the existing bulkhead systems
- o Provide alternative concepts and conceptual cost estimates for bulkhead repair.

EXECUTIVE SUMMARY

Based on the test pits investigated, measurements taken and calculations made to determine existing adequacy of the bulkhead support systems, the following conclusions can be summarized:

- o The 496'-0" curved bulkhead on the west end of Balboa Island is at high risk of failure if severe soils movements, seismic and/or tidal activity were to occur. Tie-rods are corroded and severed and the cap has shown evidence of structural cracking and movement.
- o All tie-rods observed have accumulated heavy amounts of deposits and scale attributable to corrosion. No evidence of any corrosion protection currently exists.



- o In most cases, the timber piles acting as dead men lie within the active pressure zone of the soil behind the wall and should not be considered as fully resisting the lateral forces imposed.
- o The concrete caps require remedial repair at designated locations as indicated in this report. In general, cap condition is satisfactory.
- o Concrete sheet and soldier piles are also in good condition.

SITE CONDITIONS

Bulkhead Types

The bulkheads observed fall into two (2) basic types:

Type 1

- o Concrete soldier pile and horizontal concrete lagging w/tie-backs to a timber pile dead man.

Type 2

- o Vertical concrete sheet piles and cap w/tie-backs to a timber pile dead man¹

See Figures No. 2 and 3 illustrating the two basic types of systems involved in this investigation.

FIELD INVESTIGATIONS

Approach


Six (6) sites were chosen to observe the existing condition of tie-rods and timber pile dead men. These sites were selected because they either represented the different basic conditions around the island or showed visible evidence of cap damage. The length of excavations parallel to the bulkhead were selected at between 15 and 20 feet to assure locating at least one tie-rod per test pit.

Excavation was accomplished by demolishing the existing concrete sidewalks at the designated sites and digging by hand to uncover the steel tie-rods beneath the surface. Photographs were taken of all rods both before removing the scale and deposits around the rods and then again after the material was removed. See Appendix for reference photographs taken of representative conditions encountered. Measurements were taken of the rod diameters and condition of the timber piles were logged.

Samples of special conditions were removed and tagged for reference (Exhibits A, B and C).

The concrete cap was visually surveyed and existing mudlines measured around the perimeter of the island.

¹ No existing as-built drawings can be located for the Type 2 condition.



TYPE 1

FIGURE NO. 2




FIGURE NO. 3

* SEE APPENDIX FOR
SURVEY OF WALL
BY THE CITY OF
NEWPORT BEACH-PUBLIC
WORKS

DATA COLLECTION

Test Pit No. 1 (See Figure No. 4)

Rods

1. All rods observed evidenced excessive corrosion (See Exhibit A)
2. Rods ranged from 40% to 90% of their original cross-sectional area
3. All rods appeared to be in tension
4. Rods did not show any evidence of corrosion protection
5. Rod interface at soldier piles and timber pile appeared good
6. Rods were in one piece from soldier pile to timber pile without splice, eyes or turnbuckles

Timber Piles

1. Diameter of the butt end of those piles observed was approximately 13 inches.
2. Piles were only exposed in their uppermost 1'-6" to 2'-0" of length.
3. Pile #4 was located well within the residential property boundary line.
4. Pile #3 was excessively out-of-plumb.
5. Piles appeared to be in satisfactory condition in regards to integrity of the timber.
6. Excessive corrosion deposits formed at the timber piles (See Exhibit B).

Test Pit No. 2

1. No tie-back support system was uncovered at this test pit.

Test Pit No. 3 (See Figure No. 5)

Rods

1. Of the three soldier piles within this pit, only one tie-rod was observed
2. The tie-rod observed was approximately 50% of its original cross-sectional area, assuming a 1-inch original diameter
3. The tie-rod showed no evidence of any existing corrosion protection
4. The tie-back assembly consisted of a "U" bar embedded into the cap and a tie-rod with a hook engaging the "U" bar. This assembly was not in the plane of the line of stress. See Photos - Test Pit No. 3 - Frames 23 and 3A.

◇ — ROD NO.

○ — PILE NO.





FIGURE NO. 4



TEST PIT NO. 3

Timber Pile

1. The timber pile was beneath existing improvements and could not be fully observed, but appeared to be in satisfactory condition based on the portion of the pile which was observed.

Test Pit No. 4 (See Figure No. 6)

Rods

1. All conditions were similar to that observed in Pit No. 1 with the following additional findings:
 - a. Rod #3 was found to be completely corroded and severed within the timber pile (See Exhibit C).

Timber Piles

1. All conditions were similar to that observed in Pit No. 1.

Cap, Sheet and Soldier Pile Investigation ("Little Balboa Island") See Dwg. No. 2565-1

In general, the soldier and sheet piles observed were in good condition and showed little evidence of concrete deterioration or reinforcing bar corrosion.

The caps around Little Balboa Island are of two basic types. The cap along the Grand Canal was extended by doweling and casting additional concrete on top of the original cap. The remaining two sides of the island remain in their original condition.

As illustrated on Drawing No. 2565-1, the most prevalent cap condition around the island is evidenced by a longitudinal cracking or spalling of concrete on the waterside of the cap. This condition is sometimes accompanied by the exposure of the reinforcing bar or the evidence of corroding steel.

Cracks in the cap can also be seen at installations of power pull-boxes.


Major cap distress can be seen at the southeastern most tip of the island at the site of Test Pit No. 1. The cap has heaved and fractured. (See photo frame #19 - Pit No. 1.)

Test Pits No. 5 and 6 (See Figure No. 7)

Rods

1. Two rods in both Pits No. 5 and 6 were uncovered.
2. All rods were severely corroded and severed within 2'-0" of the timber pile.
3. Based on the existing spacing of the rods uncovered, one rod was missing in Test Pit No. 6.

◇ — ROD NO.
○ — PILE NO.



TEST PIT NO. 4




FIGURE NO. 7

Timber Piles

1. Timber piles observed appeared to be in satisfactory condition.

Cap and Sheet Pile Investigation (West end of Balboa Island)

1. The cap in this 496'-0" section has shown definite signs of distress. Structural cracks occur continuously along the cap and a re-distribution of load has resulted. The cap and wall show signs that a seaward movement has occurred, but it can not be ascertained at this time if this condition is in an active state.
2. The sheet piles appear to be in satisfactory condition.

RESULTS AND CONCLUSIONS

A. "Little Balboa Island"

1. Test Pit No. 1

Of the four rods uncovered in Test Pit No. 1, two rods have approximately 40% of their original area. The corrosion process is excessive, but the rods appear to still be in tension and carrying load. All timber piles observed within this pit are out-of-plumb to some extent. It is difficult to ascertain if the piles have rotated over time or if they were originally installed in this fashion. Most probably, the piles were both installed out-of-plumb to some extent and have rotated over time as well. It does appear that the timber piles are in a stable condition at present and are carrying load.

The damage to the concrete cap at Pit No. 1 appears to have been caused by two conditions.

- a) Rotation of timber piles seaward.
- b) A settlement of the bulkhead centered around the soldier pile connected to rod number 3.

These conditions combined would account for the cap damage observed. It can not, at this time, be determined if this condition is in an active state.

It should also be noted that the conditions observed do not coincide with the existing drawing information. Drawings indicated that a common timber pile existed at the intersection of rod numbers 2 and 3. The condition which exists is that shown in Figure No. 4. The as-built geometry has greater lateral resistance than that shown on Dwg. No. R-5457-S sheet 10.

2. Test Pit No. 2

No tie-back system was found within this test pit. Calculations indicate that if the mudline is no greater than approximately 5'-0" below the top

of cap, no tie-back system is necessary and the wall system can support lateral forces as a cantilevered wall. Since the mudline at Test Pit No. 2 was much less than this 5'-0" criteria, there is no cause for concern, unless a drastic loss of beach sand were to occur.

3. Test Pit No. 3

Only one tie-back system was observed in this test pit. Since the mudline is greater than 5'-0" from top of cap, each soldier pile should be tied-back. The one tie rod assembly observed was poorly designed and would conceivably allow the wall to move seaward before receiving full value of the timber pile deadman. Excessive corrosion was also evidenced at this rod.

4. Test Pit No. 4

The conditions found in Test Pit No. 4 were similar to those found in Test Pit No. 1. Rod No. 3 was fully severed within the timber pile.

5. The concrete cap around "Little Balboa Island" requires remedial repair at locations indicated on Dwg. No. 2565-1. If the corrosion process at these locations is to be corrected, the damaged areas should be chipped back to expose good rebar, splice new bars to the old, and patch the cap with poured-in-place concrete.

At the location of Test Pit No. 1, it may be worthwhile to set-up a long term monitoring program to determine if the wall is in an active or stable condition. If stable, a simple patching procedure would suffice.

6. Along the full length of bulkhead, evidence of a grouting effort to seal the joints at soldier piles was observed. Since the excavation was no more than 2 to 3 feet deep, only the top section of this grouting effort could be observed. Large amounts of grout were observed near the surface (approximately 2 CF/FT) but diminished rapidly 1 to 2 feet below the slab level. No determination of the effectiveness of this effort could be made during our investigation.

B. West End of Balboa Island (496'-0")

1. The 496'-0" bulkhead is at high risk of failure if severe soils movement, seismic and/or tidal activity were to occur. Tie-rods are corroded and severed and the cap has shown evidence of structural cracking and movement.
2. Timber pile dead men are located between 5'-6" and 6'-6" of the inside face of sheet pile. This distance lies within the active pressure zone of the soil loads and can be only partially effective as restraint for the wall.
3. At the end of the 496'-0" bulkhead near Park Ave., a vertical construction joint exists. The relative position of the walls on either side of this joint indicate a seaward displacement of the bulkhead has occurred. This is coupled with evidence of large gaps between the sidewalk and cap; all indicating that wall movement has occurred and may be in an active state.

4. It is our opinion that the structural integrity of the reinforced concrete cap has redistributed the stresses and is now resisting the lateral forces imposed on the wall in a "hoop stress" mode.

C. General Discussion

Based on calculations, the Type 1 bulkhead can support lateral load as a cantilevered system when the mudline is no greater than 5'-0" below the top of cap. Therefore, where the mudline is high, the effect of the tie-rods and timber pile is redundant, since these tie-back devices are not required to support the wall.

The locations where the mudline is greater than 5'-0" below top of cap occurs in the following areas;

1. The three (3) corners of Little Balboa Island
2. The entire length of bulkhead facing The Grand Canal

The conclusions reached above are based on the current mudline elevations. If future erosion of the mudline were to occur, a re-evaluation of those areas requiring attention would be required.

For calculations supporting the results above, see Appendix.

There is another condition which exists at the bulkheads in question that requires added comment. Through the years, sidewalks have rotated and/or heaved creating an uneven walking surface. Since there is no evidence that a loss of sand is occurring creating cavities or pockets beneath the slabs, it is our opinion that the condition of the slabs is the result of the tidal cycle and soil saturation.

As the base material supporting the slabs becomes saturated, a shift of sand can take place thus causing the slabs to rotate. Although movements during any one cycle would be imperceivable, over time these movements could accumulate until a difference in elevation between two adjacent slabs could result.

It is our opinion that this situation does not constitute a major structural condition.

Where the mudline is near the elevation of the bottom of the bulkhead, a flow net analysis by a Soils Consultant would evaluate the stability of the soil behind the wall.

RECOMMENDATIONS

The following recommendations are based on our opinion from the point-of-view of 1) relative degree of risk to residential structures and 2) project phasing.

PRIORITY NO. 1

Based on our investigations, it is our opinion that the bulkhead at the west end of Balboa Island should be repaired as soon as possible. Several methods of repair should be investigated including:

1. Toe Piles and a waler on the waterside of the wall and re-establishment of new tie-rods to the timber pile dead men. (See Figure No. 8.)
2. Battered piles on the waterside of the wall, keyed into the cap. (See Figure No. 9.)
3. Earth anchors through the wall with a waler, if necessary. (See Figure No. 10.)

We estimate that the probable construction cost range of these possible repairs could run from between \$550.00 and \$800.00 dollars per foot of bulkhead length. Structural design and cost analysis of these alternatives is required to determine the best and most economical method of repair.

PRIORITY NO. 2

The three (3) corners of "Little Balboa Island" should be reinforced by re-establishing the structural integrity of the tie-back system. This could be accomplished using the methods stated above or additionally by placing rock on the waterside of the wall.

PRIORITY NO. 3

Re-establish the structural integrity of the tie-back system on the west face of "Little Balboa Island" by using one of those methods stated previously.

It is our opinion that even though the timber piles acting as dead men are not fully effective to restrain the lateral forces imposed, tie-rods should be reinstalled to the timber piles to afford the wall support during the repair process utilizing one of the methods described in the Priority No. 1 work. This would mitigate the possibility of a wall failure during the repair phase.

We strongly recommend that a Soils Consultant begin evaluations of the existing conditions and the proposed repairs as soon as possible so that design of the repair can begin.

We recommend that a Soils Consultant with waterfront experience be selected. Cash & Associates Engineers could provide the City of Newport Beach with a list of such consultants if requested.




FIGURE NO. 8




FIGURE NO. 9




FIGURE NO. 10




JOB NO. 2565.00

SHEET 1 OF

MADE BY BE DATE 5/6/85

CHECKED BY _____ DATE _____

TYPE 2



ASSUMED BULKHEAD SECTION
(WEST END - BTWN PARK & EMERALD AVE)



CASH & ASSOCIATES
ENGINEERS

CLIENT CITY OF NEWPORT BEACH

PROJECT BULKHEAD

CALCULATIONS FOR _____

JOB NO. 2565.00

SHEET 2 OF _____

MADE BY BE DATE 5/6/85

CHECKED BY _____ DATE _____


TYPE 2

REFERENCES -

1) CITY OF NEWPORT BEACH
PLAN NR 400 - SEPT 30, 1935

2) C&A JOB #1719.03

3) L.A. CITY BLDG CODE



SUBMERGED WT OF SOIL = 60 PCF
SATURATED WT OF SOIL = 110 PCF

$$P_p = 1.867 (60) = 112 \text{ PCF}$$


$$P_p = 2.224 (60) = 133 \text{ PCF}$$

USE 112 PCF

CHECK CAPACITY OF ANCHOR PILE

DESIGN ASSUMPTION -

PILE W/O LATERAL RESTRAINT
PER L.A. CITY BLDG CODE



$$f_1 = \frac{2.85 P}{bd} + \frac{f_2}{4}$$

$$f_2 = \frac{7.62 P (2h + d)}{bd^2}$$

IF $h = 0$
 $b = 1'$
 $d = 10'$

ACTIVE PRESSURE (P_a) = 29 PCF (ABOVE G.W.)

ACTIVE PRESSURE (P_a') = 81 PCF (BELOW G.W.)

PASSIVE PRESSURE (P_p):

$\phi = 30^\circ$ SLOPE = 1:4 $K_p = 1.867$
 $\phi = 30^\circ$ " = 1:6 $K_p = 2.224$



CASH & ASSOCIATES
ENGINEERS

CLIENT CITY OF NEWPORT BEACH JOB NO. 2565.00
PROJECT BULKHEAD SHEET 4 OF
CALCULATIONS FOR MADE BY BE DATE 5/1/85
CHECKED BY DATE

TYPE 2

↓ W.R.T. ANCHOR

#	LOAD	ARM	-	D	D ²	D ³
P1	362.5	2.33	844.6			
P2	435.0	5.50	2392.5			
P3	364.5	6.00	2187.0			
P4	1552.0	9.00	13968.0			
P5	136.0	9.667	1314.7			
P6	456(D)	11 + .5D		5016 D	228 D ²	
P7	8.5(D) ²	11 + .667 D			93.5 D ²	5.67 D ³
P8	-56(D) ²	11 + .667 D			-616 D ²	-37.35 D ³
			20706.8	5016 D	-294.5 D ²	-31.68 D ³

$$-31.68(D)^3 - 294.5(D)^2 + 5016(D) + 20706.8 = 0$$

$$\therefore \underline{D = 10.85'}$$

$$T = 456(D) + 8.5(D)^2 - 56(D)^2 + 2850$$

$$\therefore \underline{T = 2205.8 \# / 1}$$

$$\text{APPROXIMATE MAX. ANCHOR PILE SPACING} = \frac{5249}{2205.8} = 2.38'$$

$$P_6 = 456(10.85) = 4947.6 \#$$

$$P_7 = 8.5(10.85)^2 = 1000.6 \#$$

$$P_8 = -56(10.85)^2 = -6592.5 \#$$

ANCHOR PILES FROM FIELD INV. ARE ≈ 7 APART -

$$\text{LOAD} = 2205.8(7) = 15441 \#$$



CHECKED BY _____ DATE _____

TYPE 2

#	LOAD	ARM	
P1	362.5	19.52	7076.0
P2	435.0	16.35	7112.3
P3	364.5	15.85	5777.3
P4	1552.0	12.85	19943.2
P5	136.0	12.18	1656.5
P6	4947.6	5.43	26865.5
P7	1000.6	3.62	3622.2
P8	-6592.5	3.62	-23864.5
T	-2205.8	21.85	-48196.7
			-8.2 OK



CASH & ASSOCIATES
ENGINEERS

CLIENT CITY OF NEWPORT BEACH

JOB NO. 2565.00

PROJECT BULKHEAD

SHEET 0

OF

CALCULATIONS FOR


MADE BY BE

DATE 5/10


CHECKED BY

DATE

TYPE 2



REVISED ASSUMED BULKHEAD SECTION
(WEST END - BTWN PARK & EMERALD AVE)
(FROM FIELD INVESTIGATION)



CLIENT CITY OF NEWPORT BEACH JOB NO. 2565.00
 PROJECT BULKHEAD SHEET 7 OF
 CALCULATIONS FOR MADE BY BE DATE 5/10
TYPE 2 CHECKED BY DATE

$$P_1 = \frac{1}{2}(126)(4.34) = 273.4$$

$$P_2 = 126(3) = 378.0$$

$$P_3 = \frac{1}{2}(243)(3) = 364.5$$

$$P_4 = 369(1.5) = 184.5$$

$$P_5 = \frac{1}{2}(9)(1.5) = 2.3$$

$$P_6 = 378(D)$$

$$P_7 = \frac{1}{2}(17)(D)^2$$

$$P_8 = \frac{1}{2}(112)(D)^2$$

#	LOAD	Area	—	D	D ²	D ³
P1	273.4	2.89	790.2			
P2	378.0	5.84	2207.5			
P3	364.5	6.34	2310.9			
P4	184.5	7.59	1400.4			
P5	2.3	7.67	17.6			
P6	378(D)	7.84 + 5D		2963.5(D)	189(D) ²	
P7	8.5(D) ²	7.84 + .667D			66.6(D) ²	5.7(D) ³
P8	-56(D) ²	7.84 + .667D			-439.1(D) ²	-37.4(D) ³
			6726.6	2963.5(D)	-183.5(D) ²	-31.7(D) ³

$$-31.7(D)^3 - 183.5(D)^2 + 2963.5(D) + 6726.6 = 0$$

$$\therefore D = 8.35'$$

$$T = 378(D) + 8.5(D)^2 - 56(D)^2 + 1202.7$$

$$\therefore T = 1047 \#/\text{ft}$$



CASH & ASSOCIATES
ENGINEERS

CLIENT CITY OF NEWPORT BEACH

PROJECT BULKHEAD -

CALCULATIONS FOR _____

JOB NO. 2565.00

SHEET 8 OF _____

MADE BY BE DATE 5/17/85

CHECKED BY _____ DATE _____

TYPE 2

EARTH ANCHOR

REF. SUPPLEMENTAL GEOTECHNICAL
STUDY

BAYSIDE MARINA BULKHD.

by MOORE & TABER

ULTIMATE FRICTION COEFF = .60

F.S. = 2

WORKING FRICTION COEFF = .30

WEIGHT OF OVERBURDEN = 120 PLF

ASSUME DIAMETER OF ANCHOR
= 8"

$CIR = TD = 25.2 \text{ IN} = 2.1 \text{ FT}$

AVG DEPTH BELOW GROUND = 4'

$ALLOW \text{ LOAD} = .3 (4) (120) (2.1) = 302 \text{ \#}$

SPACING OF ANCHOR = 7'

$P = 2205.8 (7) = 15441 \text{ \#}$


$L = \frac{15441}{302} = 51.1 \text{ FT}$ 

10" DIAMETER -

$CIR = 2.62'$

$ALLOW \text{ LOAD} = .3 (4) (120) (2.62) = 378 \text{ \#}$

$L = 40.8 \text{ FT}$ 



CASH & ASSOCIATES
ENGINEERS

CLIENT CITY OF NEWPORT BEACH

JOB NO. 2565.00

PROJECT BULKHEAD


SHEET 9 OF

CALCULATIONS FOR

MADE BY BE DATE 6/10/85


CHECKED BY DATE

TYPE I



(SOUTH-WEST CORNER @ LITTLE BALBOA)

FILE TYPE "B" OR "H", SHEET TYPE "B" OR "H"



CASH & ASSOCIATES
ENGINEERS

CLIENT CITY OF NEWPORT BEACH

JOB NO. 2565.00

PROJECT BULKHEAD

SHEET 10 OF

CALCULATIONS FOR

MADE BY BE DATE 6/10/85


CHECKED BY DATE

TYPE 1

PILE TYPES -

PILE	LENGTH	SHEET	WIDTH
B	12'-3"	B	7'-3"
D	13'-3"	D	8'-3"
E	14'-3"	E	9'-3"
F	14'-3"	F	8'-3" @ CORNER
G	15'-3"	G	9'-3" @ CORNER
H	12'-3"	H	7'-3"

NOTE - ALL SHEETS ARE 10'-10" LONG



CASH & ASSOCIATES
ENGINEERS

CLIENT CITY OF NEWPORT BEACH

PROJECT BULKHEAD

CALCULATIONS FOR _____


JOB NO. 2565.00

SHEET 11 OF _____


MADE BY BE DATE 6/10/81

CHECKED BY _____ DATE _____

TYPE 1



ASSUMED SECTION @ SOLDIER PIPE



CASH & ASSOCIATES
ENGINEERS

CLIENT CITY OF NEWPORT BEACH

JOB NO. 2565.00

PROJECT BULKHEAD


SHEET 12 OF

CALCULATIONS FOR

MADE BY BE DATE 6/12/8


CHECKED BY DATE

TYPE I



ASSUMED DESIGN SECTION

(DESIGN BASED ON L.A.C.B.C.)



CASH & ASSOCIATES
ENGINEERS

CLIENT CITY OF NEWPORT BEACH

JOB NO. 2565.00

PROJECT BULKHEAD


SHEET 13 OF

CALCULATIONS FOR

MADE BY BE DATE 6/12/81

CHECKED BY DATE

TYPE I



$$f_1 = .298(P) + .25(f_2)$$

$$f_2 = \frac{7.62(P)(2h+5)}{47.75}$$

R = RESULTANT FORCE

$$= P_1 + P_2 + P_3 - P_4$$

$$F_{1 \text{ MAX}} = 112 \text{ PCF}(1.67) = 187 \text{ PSF}$$

$$F_{2 \text{ MAX}} = 112(5) = 560 \text{ PSF}$$

$$f_1 = \frac{2.85(P)}{b(D)} + \frac{f_2}{4}$$

$$f_2 = \frac{7.62(P)(2h+D)}{bD^2}$$

$$b = 1.27 \sqrt{18''} = 1.91'$$

$$D = 5'$$


$$h = \frac{P_1(.33A+B) + P_2(.5)(B) + P_3(.33)(B) - P_4(.33)(D)}{P_1 + P_2 + P_3 + P_4}$$

$$P_1 = .5(348)(A)(A)$$

$$P_2 = 348(A)(B)$$

$$P_3 = .5(972)(B)(B)$$

$$P_4 = (.5)(1344)(D)(D)$$



CASH & ASSOCIATES
ENGINEERS

CLIENT CITY OF NEWPORT BEACH

JOB NO. 2565.00

PROJECT BULKHEAD

SHEET 14 OF

CALCULATIONS FOR

MADE BY BE DATE 6/12/1

CHECKED BY DATE

TYPE I

A FT	B FT	D FT	WALL HT FT	P(1) LBS	P(2) LBS	P(3) LBS	-P(4) LBS	R LBS	H FT	f(1) PSF	f(2) PSF
0.00	0.86	0.00	6.94	0.00	0.00	359.45	0.00	359.45	0.28	187.11	319.36
0.00	0.90	0.25	6.98	0.00	0.00	393.66	42.00	351.66	0.28	182.85	311.60
0.00	1.04	0.50	7.12	0.00	0.00	525.66	168.00	357.66	0.30	186.64	319.63
0.00	1.23	0.75	7.31	0.00	0.00	735.27	378.00	357.27	0.35	187.92	325.22
0.00	1.45	1.00	7.53	0.00	0.00	1021.82	672.00	349.82	0.42	185.89	325.97
0.00	1.69	1.25	7.77	0.00	0.00	1388.06	1050.00	338.06	0.50	181.68	323.17
0.00	1.95	1.50	8.03	0.00	0.00	1848.02	1512.00	336.01	0.58	182.76	329.95
0.00	2.22	1.75	8.30	0.00	0.00	2395.20	2058.00	337.20	0.66	185.68	340.19
0.00	2.49	2.00	8.57	0.00	0.00	3013.25	2688.00	325.25	0.75	181.29	336.90
0.00	2.77	2.25	8.85	0.00	0.00	3729.03	3402.00	327.03	0.83	184.55	347.80
0.14	3.00	2.50	9.22	3.41	146.16	4374.00	4200.00	323.57	0.92	184.86	353.18
0.86	3.00	2.75	9.94	128.69	897.84	4374.00	5082.00	318.53	1.02	184.57	358.04
1.52	3.00	3.00	10.60	402.01	1586.88	4374.00	6048.00	314.89	1.14	185.34	365.48
2.14	3.00	3.25	11.22	796.85	2234.16	4374.00	7098.00	307.01	1.26	183.68	369.25
2.74	3.00	3.50	11.82	1306.32	2860.56	4374.00	8232.00	308.88	1.38	187.93	382.99
3.32	3.00	3.75	12.40	1917.90	3466.08	4374.00	9450.00	307.98	1.51	190.55	394.54
3.88	3.00	4.00	12.96	2619.47	4050.72	4374.00	10752.00	292.19	1.64	183.79	386.35
4.44	3.00	4.25	13.52	3430.17	4635.36	4374.00	12138.00	301.53	1.77	192.83	411.40
4.98	3.00	4.50	14.06	4315.27	5199.12	4374.00	13608.00	280.39	1.90	182.22	394.18
→ 5.52	3.00	4.75	14.60	5301.85	5762.88	4374.00	15162.00	276.73	2.04	182.74	400.63
6.05	3.00	5.00	15.13	6368.84	6316.20	4374.00	16800.00	259.03	2.17	173.75	385.78

- SEE SHT 15 -

ASSUMPTIONS -

- 1) LOW WATER LEVEL IS AT THE BOTTOM OF HORIZ. SHEETS
- 2) MUDLINE WILL NEVER GO BELOW HORIZ. SHEETS
- 3) SPACING OF SOLDIER PILES = 12'-0"
- 4) WIDTH OF SOLDIER PILES = 1.5'

REFERENCE DOCUMENTS

1. City of Newport Beach

Plan No. 400
September 30, 1935
R-5457-6 Sheet Nos. 1 thru 12

2. Misc. Soundings Near Collins Isle/Balboa Island
Sheet 1 of 1 and attached profile

BY *RLW-JDM*

DATE *5/9/83*

SUBJECT *MISC SOUNDINGS NEAR*

SHEET NO. *1* OF *1*

CHKD. BY

DATE


Collins Isle / BALEOA ISLAND

JOB NO.

ELEV'S SHOWN ~ MLLW DATUM

⑤ *18'-7"*
R between #124 & #130

⑥ *19'-0"*
Southerly corner of pier
in front of #132





CITY OF
NEWPORT BEACH
PUBLIC WORKS DEPARTMENT

BALBOA ISLAND BULKHEAD REPAIR NEAR WATERS WAY

CONTRACT NO. 2525



APPROVED *R. E. No. 12806* DATE 9-15-87
PUBLIC WORKS DIRECTOR
R.E. NO. 12806



- SYMBOL LEGEND**
- POWER POLE
 - MANHOLE
 - FIRE HYDRANT
 - METER BOX
 - VALVE
 - POWER POLE ANCHOR
 - MONUMENT
 - FENCE
 - BLOCK WALL
 - TREE
 - SHRUBBERY
 - ASPHALT PAVEMENT
 - BRICK WALK
 - CONCRETE
 - BUILDING
 - EXISTING CONSTRUCTION
 - NEW CONSTRUCTION
 - CENTERLINE
 - EWER LINE
 - WATER LINE
 - GAS LINE
 - POWER LINE
 - TELEPHONE LINE
 - CABLEVISION LINE
 - SPRINKLER SYSTEM
 - STREET LIGHT

EMERGENCY TELEPHONE NUMBERS	AGENCY	NUMBER
SOUTHERN CALIFORNIA GAS COMPANY		834-3250
SOUTHERN CALIFORNIA Edison COMPANY		855-0221
PACIFIC TELEPHONE COMPANY		581-7726
CITY OF NEWPORT BEACH (PUBLIC UTILITIES)		644-3011
COUNTY OF SAN DIEGO DISTRICTS		942-2411 EXT. 222
COUNTY OF SAN DIEGO		732-2255
COMMUNITY CABLEVISION		1-800-492-4353
UNDERGROUND SERVICE ALERT		




AERIAL PHOTO

INDEX OF SHEETS

SHEET	DESCRIPTION
1	TITLE SHEET
2	GENERAL NOTES
3	PLAN & PROFILES
4	STRUCT. DETAILS
5	WALKWAY RECONSTRUCTION




H-5111-S
SHT. 1 OF 5



NOTE: SOUNDINGS WERE TAKEN ON JUNE 10, 1966 BY THE CITY OF NEWPORT BEACH PUBLIC WORKS DEPARTMENT AND ARE SUBJECT TO CHANGE.

NOTE: SEE SHEET 5 FOR PILE LOCATIONS.



AS BUILT

AS BUILT




CA

COSE ASSOCIATES
PLANNERS
10000 Wilshire Blvd., Suite 1000
Los Angeles, CA 90024

2566.00

PLAN AND PROFILES


CITY OF NEWPORT BEACH
PUBLIC WORKS DEPARTMENT
BUILT 3 OF 5

SCALE: 1/4" = 1'-0" **EXCEPT AS NOTED**

APPROVAL: *[Signature]* **DATE:** 9/1/78

REVISIONS:

NO.	DATE	REVISION
1	9/1/78	FOR FINAL APPROVAL
2	9/1/78	FOR APPROVAL
3	9/1/78	FOR APPROVAL





Appendix 2


Little Balboa Island Seawall Raising (1989)

CONTRACT NO. 2468

APPROVED James D. Nelson DATE 7-22-88
PUBLIC WORKS DIRECTOR R.C.E. NO. 12806




1. **CLEAN WALL, BOX BOLTS (CONCRETE W/OUT BOLTS)**
2. **CUT IN, SANDBLAST COPING TO REMOVE EX. REIN. FULL BOX.**
3. **SANDBLAST NEW WALL MAX TO 8" AHEAD OF ALLOW. NEW WALL BOX TO BE CAST INTO COPING ADDITION.**
4. **REINFORCING COPING AND EXPANSION JOINTS.**
5. **APPLY SURFACE FINISHING ADHESIVE TO ALL CONCRETE SURFACES THAT THE COPING ADDITION WILL BE CAST AGAINST.**
6. **CLEAN AND SANDBLAST EXISTING COPING AND ADDITION.**



LIGHTING STANDARD NOTES

- ① **ENR 14. BILLINGU CODES TO ENR 14. 5/8" A.S.**
- ② **ENR 14. 5/8" CODES TO ENR 14. 5/8" A.S.**
- ③ **ENR 14. 5/8" CODES TO ENR 14. 5/8" A.S.**
- ④ **ENR 14. 5/8" CODES TO ENR 14. 5/8" A.S.**



AS BUILT

C-2468

U-2498
LITTLE BALBOA ISLAND
SEAWALL RAISING

DATE	1-1-88	DATE	1-1-88
REVISIONS		REVISIONS	
NO.		NO.	
DESCRIPTION		DESCRIPTION	
APPROVED		APPROVED	
DESIGNED	LD	DESIGNED	LD
DRAWN	LD	DRAWN	LD
CHECKED		CHECKED	
CITY OF NEWPORT BEACH		CITY OF NEWPORT BEACH	
PUBLIC WORKS DEPARTMENT		PUBLIC WORKS DEPARTMENT	
PROJECT	101	PROJECT	101
DATE	1-1-88	DATE	1-1-88

Appendix 3

Cash & Associates (2005)



CASH & ASSOCIATES
ENGINEERING AND ARCHITECTURE

10001 E. 17th Avenue
Suite 1100
Denver, CO 80202
Phone: (303) 755-1100
Fax: (303) 755-1101

January 31, 2005

City of Newport Beach
Public Works Department
3300 Newport Boulevard
Newport Beach, CA 92663

Attention: Mr. Lloyd R. Dalton, P.E.

Subject: BALBOA ISLAND AND LITTLE BALBOA ISLAND
BULKHEADS AND COLLINS ISLAND BRIDGE
INSPECTIONS AND REPORTS
(C&A Project No. 6253.00)

Dear Mr. Dalton:

Cash & Associates is pleased to provide two DRAFT copies of our inspection reports for the Balboa Island and Little Balboa Island Bulkheads and the Collins Island Bridge for review and comment.

Upon receipt of written comments from you, we will prepare five (5) copies of the final report as requested for your use. If you have any questions, please do not hesitate to contact me.

Very truly yours,

CASH & ASSOCIATES

Christopher T. Mansour, P.E.
California Civil Engineer No. C058566

BALBOA AND LITTLE BALBOA ISLAND BULKHEAD INSPECTION REPORT

TABLE OF CONTENTS

		Page No.
SECTION I. FIELD INVESTIGATION		
1.0	Introduction.....	1
1.1	Executive Summary.....	2
1.2	History of Balboa Island/Little Balboa Island Bulkheads.....	3
1.3	Construction of Bulkheads.....	3
SECTION II. DATA COLLECTION		
2.0	Survey Methods Used.....	1
2.1	Approach.....	3
2.2	Measurements.....	3
2.3	Obstructions.....	3
2.4	Soundings.....	3
2.5	Limitations.....	4
SECTION III. PRIORITY AND COST REPAIR SUMMARY		
3.0	Repairs.....	1
3.1	Priority for Repairs.....	1
3.1.1	Priority 1 – Life Threatening Structural Damage Repairs.....	1
3.1.2	Priority 2 – Property Damage Repairs.....	2
3.1.3	Priority 3 – Cosmetic Damage, All Bulkheads.....	2
3.2	Cost Estimate for Repairs.....	3
SECTION IV. INSPECTION		
<u>Tab</u>		
1.	North Bay Front Between Park Avenue and Emerald Avenue	
2.	North Bay Front Between Emerald Avenue and Garnet Avenue	
3.	North Bay Front Between Garnet Avenue and Pearl Avenue	
4.	North Bay Front Between Pearl Avenue and Agate Avenue	
5.	North Bay Front Between Agate Avenue and Collins Avenue	
6.	North Bay Front Between Collins Avenue and Ruby Avenue	
7.	North Bay Front Between Ruby Avenue and Diamond Avenue	
8.	North Bay Front Between Diamond Avenue and Sapphire Avenue	
9.	North Bay Front Between Sapphire Avenue and Coral Avenue	
10.	North Bay Front Between Coral Avenue and Apolena Avenue	
11.	North Bay Front Between Apolena Avenue and Amethyst Avenue	
12.	North Bay Front Between Amethyst Avenue and Onyx Avenue	
13.	North Bay Front Between Onyx Avenue and Marine Avenue	
14.	North Bay Front Between Marine Avenue and Grand Canal West	

TABLE OF CONTENTS

SECTION IV. INSPECTION (Continued)

Tab

15.	South Bay Front Between Park Avenue and Emerald Avenue
16.	South Bay Front Between Emerald Avenue and Garnet Avenue
17.	South Bay Front Between Garnet Avenue and Pearl Avenue
18.	South Bay Front Between Pearl Avenue and Agate Avenue
19.	South Bay Front Between Agate Avenue and Opal Avenue
20.	South Bay Front Between Opal Avenue and Topaz Avenue
21.	South Bay Front Between Topaz Avenue and Turquoise Avenue
22.	South Bay Front Between Turquoise Avenue and Collins Avenue
23.	South Bay Front Between Collins Avenue and Ruby Avenue
24.	South Bay Front Between Ruby Avenue and Diamond Avenue
25.	South Bay Front Between Diamond Avenue and Sapphire Avenue
26.	South Bay Front Between Sapphire Avenue and Coral Avenue
27.	South Bay Front Between Coral Avenue and Apolena Avenue
28.	South Bay Front Between Apolena Avenue and Amethyst Avenue
29.	South Bay Front Between Amethyst Avenue and Onyx Avenue
30.	South Bay Front Between Onyx Avenue and Marine Avenue
31.	South Bay Front Between Marine Avenue and Grand Canal West
32.	South Bay Front Between Grand Canal East and Abalone Avenue
33.	South Bay Front Between Abalone Avenue and Crystal Avenue
34.	South Bay Front Between Crystal Avenue and Jade Avenue
35.	South Bay Front Between Jade Avenue and East Bay Front
36.	Grand Canal West Between North Bay Front and Balboa Avenue
37.	Grand Canal West Between Balboa Avenue and Park Avenue
38.	Grand Canal West Between Park Avenue and South Bay Front
39.	Grand Canal East Between South Bay Front and Park Avenue
40.	Grand Canal East Between Balboa Avenue and Park Avenue
41.	Grand Canal East Between Balboa Avenue and East Bay Front
42.	East Bay Front Between Grand Canal East and Balboa Avenue
43.	East Bay Front Between Balboa Avenue and Park Avenue
44.	East Bay Front Between Park Avenue and South Bay Front
45.	Leaking Bulkheads Around Both Islands

Page No.

SECTION V. APPENDIX

5.0	Reference Drawings	1
5.1	Repair Methods	2
5.1.1	Crack Injection	2
5.1.2	Sealant Repair	3
5.1.3	Spall Repair	4
5.1.4	Shotcrete Repair	5
5.1.4.1	Shotcrete Repair, Bulkhead Cap	6
5.1.4.2	Shotcrete Repair, Underside of Bulkhead Cap	6
5.2	Options for Corrosion Protection and Other Considerations	7
5.2.1	Bonding Agents	7
5.2.2	Coating for High Voltage Boxes	7

SECTION I. FIELD INVESTIGATION

1.0 Introduction

Cash & Associates was contracted by the City of Newport Beach, Public Works Department, to inspect and report on the condition of 2.5 miles of bulkhead walls around Balboa Island and Little Balboa Island. The work included field inspection and photographic documentation of the walls and preparation of the following report. This report defines the inspection procedures used, identifies observed defects, and discusses findings in regards to the structural integrity and physical condition of the Balboa Island and Little Balboa Island bulkheads. This report also contains photographic documentation of observed conditions, recommendations for repairs, sketches for repair methods, and estimates of construction cost for repairs.

As noted on the map below, Balboa Island and Little Balboa Island are divided into specific blocks. For ease of reference, this report has been organized by street blocks that have been identified by the corresponding street names, as shown in the Table of Contents. Each block section includes a list of observed distress, photographs from the site visit, and an estimate of construction cost for repairs.



FIG 1. Balboa Island Street Map

1.1 Executive Summary

Based on the field investigations, measurements taken and calculations made to determine the adequacy of the bulkheads, we have made the following conclusions:

1. The majority of sealant at construction joints is cracked and split and in need of repair.
2. Transverse shrinkage cracking of the concrete bulkhead cap occurs throughout both islands and can be easily mitigated with the use of modern surface applied sealants or epoxy injection technology.
3. Shotcrete coverings on the Grand Canal bulkhead are cracked and spalling throughout. The bottom of the shotcrete covering has been subjected to seawater intrusion that has caused areas of delamination of the shotcrete from the base materials. This area has a high potential for the shotcrete to delaminate from the base material. The scope of Cash & Associates' inspection did not include methods to observe the condition of the bulkhead beneath the shotcrete surface, therefore no determination as to the condition of the original bulkhead is included in this report.
4. Leakage and piping through and/or under the bulkhead was observed during extreme high tides.
5. Concrete sheets and soldier piles, where exposed for visual inspection, are in good condition. Concrete caps are spalled and cracked throughout the length of the bulkhead on both islands but does not pose a structural problem at this time.
6. Overall, the majority of the bulkheads pose little danger of failure during a seismic event. Areas around the west end of Balboa Island between Emerald Avenue and Park Avenue have the greatest potential for failure during a seismic event.

1.2 History of Balboa Island/Little Balboa Island Bulkheads

Prior to 1906, much of what is now Balboa Island, Harbor Island, Collins Island and Little Balboa Island was underwater at high tide. In 1906, W.S. Collins, an early day developer, brought a small steam dredge into Newport Harbor and began dredging up sand to build what is now known as Balboa Island. The first "bulkhead", a wooden structure that protected part of Balboa Island, was constructed in 1909. This structure was partially replaced by a cement barrier in 1912.

In 1913, the Grand Canal, separating Little Balboa Island, was created, and dredging to complete Balboa Island was finished. In 1918 the Balboa Island Improvement Association (BIIA) was started. The BIIA was a strong motivating force in working with the City of Newport Beach on repair of the bulkhead, instituting ferry service, and providing a sewer system, water, gas and electricity service, paved streets and sidewalks, and street lighting.

The Balboa Island Bulkhead was rebuilt in 1922 and the Grand Canal wooden bulkhead and walk were rebuilt in concrete in 1929. The present day North, South and East Bay Front bulkheads, walks and public piers were completed in 1938¹. In the 1980's and 1990's, a series of public works projects placed shotcrete over the existing bulkheads along the Grand Canal east and west promenades. In addition, the bulkhead coping on Little Balboa Island was raised approximately 12 inches around the entire island.

1.3 Construction of Bulkheads

With the exception of the bulkhead along South Bay Front between Park Avenue and Emerald Avenue, all bulkheads are constructed using concrete soldier piles tied back to a wooden "deadman" pile. Concrete sheets, placed between the soldier piles, span the walls horizontally between the soldier piles and retain earth behind the walls. The bulkhead located along South Bay Front between Park Avenue and Emerald Avenue originally was designed using a concrete sheet embedded into sand and tied back to wood piles placed at seven feet on center. The concrete sheets span vertically between the concrete cap and the embedment into the mud. In 1987, a bulkhead investigation

¹ *Balboa Island History web site - www.balboaislandmuseum.com*

performed by Cash & Associates, concluded that these sheet pile wall tiebacks were corroded and inadequate. Subsequently, rock was placed in front of the bulkhead to provide stability to the system on the assumption that all tie-backs were corroded and not providing adequate support to the wall. The addition of this rock work in front of the wall, effectively turned the simply-supported bulkhead into a cantilevered bulkhead. Additional calculations prepared by Cash & Associates for bulkhead stability established that the original walls were not designed to withstand seismic loads or the potential loads and differential settlement resulting from liquefaction.

SECTION II. DATA COLLECTION

2.0 Survey Methods Used

1. The survey performed for this investigation was a visual survey, only. Testing and/or measuring (except location from known points) was not included in Cash & Associates Scope of Work. All visual information was taken during low tides.
2. All notations for locations of repairs are related to the center line of streets and/or light poles located at the ends of streets. (Refer to Photographs).
3. In addition to field investigation, we reviewed as-built and design drawings furnished by the City of Newport Beach, Public Works Department. A list of these drawings is provided in Section V Appendix, 5.0 Reference Drawings.
4. The notations relate only to the wall visible above the sand elevation.
5. No attempt was made to determine the elevation of the bottom of the panels; or, to inspect tie backs. If the City of Newport Beach wishes to assess the structural stability of bulkheads in the future, an assessment of the wall depth of penetration will be required.
6. No calculations were made to determine the stresses in the wall.
7. Photographs were taken of each area of distress to facilitate the identification of the condition of the walls. Copies of the photographs taken will be provided on separate electronic media. These photos can also be used in future wall investigations to assess historical wall distress.
8. Repair Identification

- a. Cracks. Cracks are divided into two categories, small and large. Repair of small cracks will not require use of a form. Repair of larger cracks will require a form. Pressure injection using epoxy is the recommended method of repair for cracks. Refer to Section V, Appendix, 5.1 Repair Methods for illustrations of repair methodology as follows:

Sketch C-1 Small cracks, no form required.

Sketch C-2 Larger cracks, form required.

- b. Spalling. Repair of spalling will involve removal of loose concrete and pouring or placing new concrete by hand. Refer to Section V, Appendix, 5.1 Repair Methods for illustrations of repair methodology for spalling as follows:

Sketch S-1 Does not include existing reinforcing.

Sketch S-2 Does include existing; or, new reinforcing.

- c. Sealant Repair. Repair of cracked and splitting sealant at existing construction joints or crack control joints will involve removing the existing sealant from the joints and replacing damaged or missing joint material with new backing rod between the concrete caps. New sealant will then be applied over the construction joint to provide a water tight seal. Refer to Section V, Appendix, 5.1 Repair Methods for an illustration of repair methodology for substrate failure. Refer to Sketch J-1.

- d. Shotcrete Repair. Repair of shotcrete will involve the use of either crack injection as described in Section 8a above, spall repair as explained in Section 8b above, or removal of shotcrete material back to sound base material. Refer to Section V, Appendix, 5.1 Repair Methods, Sketch SC-1 for illustrations of repair methodology for substrate failure.

2.1 Approach

Visual inspections from the landside and waterside of the Balboa Island and Little Balboa Island bulkheads were performed over a period of several days as follows: December 17, 20, 21 and 27, 2004 and January 5, 6, 10 and 21, 2005. Tide charts were used to determine the best time to observe the bulkheads at low tide to ensure maximum exposure of the walls. During the site investigations, measurements, photographs and soundings were taken to determine the condition of the bulkheads.

2.2 Measurements

All measurements along the bulkheads were taken from the centerline of street and/or light poles as a reference of 0.0 feet. All measurements were made using a calibrated distance wheel. The wheel was placed on top of the bulkhead and distances from the reference point to the point of note were observed and recorded. All elevations, where mentioned, are based on visual estimation relative to MLLW.

2.3 Obstructions

During each site investigation every attempt was made to gain access to every visible part of the bulkhead. Bulkheads or portions of the bulkheads obscured by rocks, high sand levels, and piers were assumed to be in good condition. A minimum of two passes from both landside and waterside of all bulkheads were made to identify any problems or areas of deficiencies. Sketches were made and photographs were taken to document areas of observed deficiencies. Where cracks or spalls were observed and partially obstructed by sand, the sand was removed to the greatest extent possible with hand tools to observe potential problem areas.

2.4 Soundings

Sounding where spalling has occurred can determine if the area is a spall (loose material), or a crack (solid material with a crack present). During Cash & Associates site investigations, if spalling was observed or suspected, a sounding of the area was made using a 16 ounce hammer on and around the suspect spalled area. Where

spalling was identified, the location of the spall was traced to determine the approximate size of the spall. Depth of the spall, where available, was determined through visual inspection. The sounding method is not accurate in determining spall depth.

2.5 Limitations

The majority of the concrete sheets were buried in sand and could not be observed. In areas where these sheets could be observed, no damage was evident. Based on the condition of the concrete sheets that could be inspected, this report assumes that the buried sheets are in good condition and further investigation is not necessary at this time. Due to operational conditions and obstructions at the ferry landing on South Bay Front at Agate Avenue, no investigation could be performed under the loading ramp and electrical equipment room adjacent to Agate Avenue. A visual survey by boat was performed with no apparent observed damage to the seawall in this area.

This report is based on the assumption that the bulkheads were designed and constructed conforming to the codes in effect at the time of construction. This investigation was limited to the visual observation of items noted in this report. No assurances can be given or otherwise implied that all deficiencies were uncovered.

Our investigation was performed using the degree of care and skill ordinarily exercised, under similar circumstances, by reputable Registered Engineers practicing in this or similar localities. Our professional opinions, conclusions and recommendations are based on visual observation of those parts of the structure which are noted in this report. No opinions are expressed or implied concerning the actual condition of parts of the structure we did not observe.

SECTION III. PRIORITY AND COST OF REPAIR SUMMARY

3.0 Repairs

Detailed breakdowns by block, defined by individual street names, together with recommendations for repairs and the associated estimates for construction costs are contained in Section IV Inspection.

3.1 Priority for Repairs

Although the overall condition of the Balboa Island and Little Balboa Island bulkheads is good, there are some problem areas. The order of priority for recommended repairs is broken down into three levels as:

- Priority 1: Non-seismic, structural repairs that posed greatest danger to life safety.
- Priority 2: Repair of property damage
- Priority 3: Cosmetic damage.

A prioritized list of recommended repairs follows:

3.1.1 Priority 1 – Life Threatening Structural Damage Repairs

1. No life threatening repairs of the bulkheads are required at this time.
2. Electrical Pull Box, North Bay Front Between Garnet Avenue and Pearl Avenue. The pull box lid is accessible to the general public through the loss of the access cover bolts. Access bolts should be replaced and tightened to prevent the general public access to the pullbox.

3.1.2 Priority 2 – Property Damage Repairs

Intrusion of seawater through cracks in the bulkhead or failed joints is the greatest threat for property damage. Intrusion is most likely to occur during high tides, or high tides coupled with heavy rains. These conditions were observed during the January 10th inspection of the bulkheads when both maximum high tide levels and heavy rainfall occurred. During these conditions leaking through construction joints, cracks in the bulkheads and piping under the sidewalks were observed. Cracks in the bulkheads can be easily corrected. Due to hydrostatic forces, piping under the sidewalks can be ~~the~~ difficult to repair. Sealing the bulkhead, concrete sheets and sidewalk will correct the piping problem temporarily but this is not a long term solution.

Recommended repairs include:

1. Repair construction/expansion joints using sealant throughout both islands.
2. Repair cracks in the bulkheads using crack injection.
3. Sealing bulkheads and sidewalks against piping to the property lines.

Refer to Section V, Appendix, 5.1 Repair Methods for sketches of these repairs.

3.1.3 Priority 3 – Cosmetic Damage, All Bulkheads

Cosmetic damage exists throughout the bulkheads however it poses little danger to the structural integrity of the wall or potential for property damage. The greatest danger posed by the observed cosmetic damage would be injuries to persons through tripping hazards or abrasions to persons walking on or playing near the bulkheads. This has the potential of being a liability issue and Public Works may want to consider addressing this issue. Observed cosmetic damage includes:

1. Grand Canal East and West Promenades. Shotcrete placed over the piles and concrete sheets is spalling off or being undermined. In general, the shotcrete coating is cracked and spalled throughout the length of the wall. In addition, large areas of corrosion and spalling were detected at the bottom of cap on the waterside of the bulkhead.
2. Waterside cracking and spalling at the bottom of the cap, located directly over the soldier piles, was observed on the bulkheads outside the Grand Canal area.
3. Cracking and spalling was observed in areas previously repaired. These conditions appear to be the result of continued corrosion of the existing reinforcing bars.

3.2 COST ESTIMATE FOR REPAIRS

The quantities used to prepare estimates are based on visual observations from the bulkhead, floating docks; or, where necessary, a boat. Sample repair methods are shown on attached sketches contained in Section V, Appendix 5.1 Repair Methods. The unit prices for this estimate were compiled from historical data obtained from similar projects over the past several years. The following is a summary of the estimated construction cost by block. Breakdowns of these costs are provided at the end of each tabbed section in Section IV Inspection of this report.

1.	North Bay Front Between Park and Emerald	\$ 16,345
2.	North Bay Front Between Emerald and Garnet	\$ 1,120
3.	North Bay Front Between Garnet and Pearl	\$ 2,016
4.	North Bay Front Between Pearl and Agate	\$ 1,540
5.	North Bay Front Between Agate and Collins	\$ 2,265
6.	North Bay Front Between Collins and Ruby	\$ 5,047
7.	North Bay Front Between Ruby and Diamond	\$ 3,332
8.	North Bay Front Between Diamond and Sapphire	\$ 5,110
9.	North Bay Front Between Sapphire and Coral	\$ 4,914
10.	North Bay Front Between Coral and Apolena	\$ 7,826
11.	North Bay Front Between Apolena and Amethyst	\$ 8,736
12.	North Bay Front Between Amethyst and Onyx	\$ 2,576

*Balboa Island and Little Balboa Island Bulkhead Inspection
City of Newport Beach*

13.	North Bay Front Between Onyx and Marine.....	\$ 4,228
14.	North Bay Front Between Marine and Grand Canal.....	\$ 1,470
15.	South Bay Front Between Park and Emerald.....	\$ 8,722
16.	South Bay Front Between Emerald and Garnet.....	\$ 6,874
17.	South Bay Front Between Garnet and Pearl.....	\$ 2,954
18.	South Bay Front Between Pearl and Agate.....	\$ 8,148
19.	South Bay Front Between Agate and Opal.....	\$ 1,876
20.	South Bay Front Between Opal and Topaz.....	\$ 4,823
21.	South Bay Front Between Topaz and Turquoise.....	\$ 14,917
22.	South Bay Front Between Turquoise and Collins.....	\$ 3,374
23.	South Bay Front Between Collins and Ruby.....	\$ 1,651
24.	South Bay Front Between Ruby and Diamond.....	\$ 1,106
25.	South Bay Front Between Diamond and Sapphire.....	\$ 504
26.	South Bay Front Between Sapphire and Coral.....	\$ 14,364
27.	South Bay Front Between Coral and Apolena.....	\$ 10,808
28.	South Bay Front Between Apolena and Amethyst.....	\$ 10,416
29.	South Bay Front Between Amethyst and Onyx.....	\$ 2,856
30.	South Bay Front Between Onyx and Marine.....	\$ 9,240
31.	South Bay Front Between Marine and Grand Canal.....	\$ 10,990
32.	South Bay Front Between Grand Canal and Abolena.....	\$ 2,478
33.	South Bay Front Between Abolena and Crystal.....	\$ 4,340
34.	South Bay Front Between Crystal and Jade.....	\$ 14,118
35.	South Bay Front Between Jade and East Bay Front.....	\$ 9,548
36.	Grand Canal West Between North Bay Front and Balboa.....	\$ 48,853
37.	Grand Canal West Between Balboa and Park.....	\$ 65,611
38.	Grand Canal West Between Park and South Bay Front.....	\$ 24,759
39.	Grand Canal East Between South Bay Front and Park.....	\$ 14,497
40.	Grand Canal East Between Balboa and Park.....	\$ 27,783
41.	Grand Canal East Between Balboa and East Bay Front.....	\$ 61,838
42.	East Bay Front Between Grand canal and Balboa.....	\$ 67,900
43.	East Bay Front Between Balboa and Park.....	\$ 58,828
44.	East Bay Front between Park and South Bay Front.....	\$ 29,855
GRAND TOTAL		\$610,556

SECTION IV. INSPECTION

This section has been organized for ease of reference. Each tabbed section (1 through 45) contains the results, by block, of our field investigation together with representative photographs and the associated estimate of construction cost for repairs.

Table of Contents

Tab

1. North Bay Front Between Park Avenue and Emerald Avenue
2. North Bay Front Between Emerald Avenue and Garnet Avenue
3. North Bay Front Between Garnet Avenue and Pearl Avenue
4. North Bay Front Between Pearl Avenue and Agate Avenue
5. North Bay Front Between Agate Avenue and Collins Avenue
6. North Bay Front Between Collins Avenue and Ruby Avenue
7. North Bay Front Between Ruby Avenue and Diamond Avenue
8. North Bay Front Between Diamond Avenue and Sapphire Avenue
9. North Bay Front Between Sapphire Avenue and Coral Avenue
10. North Bay Front Between Coral Avenue and Apolena Avenue
11. North Bay Front Between Apolena Avenue and Amethyst Avenue
12. North Bay Front Between Amethyst Avenue and Onyx Avenue
13. North Bay Front Between Onyx Avenue and Marine Avenue
14. North Bay Front Between Marine Avenue and Grand Canal West
15. South Bay Front Between Park Avenue and Emerald Avenue
16. South Bay Front Between Emerald Avenue and Garnet Avenue
17. South Bay Front Between Garnet Avenue and Pearl Avenue
18. South Bay Front Between Pearl Avenue and Agate Avenue
19. South Bay Front Between Agate Avenue and Opal Avenue
20. South Bay Front Between Opal Avenue and Topaz Avenue
21. South Bay Front Between Topaz Avenue and Turquoise Avenue
22. South Bay Front Between Turquoise Avenue and Collins Avenue
23. South Bay Front Between Collins Avenue and Ruby Avenue
24. South Bay Front Between Ruby Avenue and Diamond Avenue
25. South Bay Front Between Diamond Avenue and Sapphire Avenue
26. South Bay Front Between Sapphire Avenue and Coral Avenue
27. South Bay Front Between Coral Avenue and Apolena Avenue
28. South Bay Front Between Apolena Avenue and Amethyst Avenue
29. South Bay Front Between Amethyst Avenue and Onyx Avenue
30. South Bay Front Between Onyx Avenue and Marine Avenue
31. South Bay Front Between Marine Avenue and Grand Canal West
32. South Bay Front Between Grand Canal East and Abalone Avenue
33. South Bay Front Between Abalone Avenue and Crystal Avenue
34. South Bay Front Between Crystal Avenue and Jade Avenue
35. South Bay Front Between Jade Avenue and East Bay Front

Table of Contents (Continued)

Tab

- 36. Grand Canal West Between North Bay Front and Balboa Avenue
- 37. Grand Canal West Between Balboa Avenue and Park Avenue
- 38. Grand Canal West Between Park Avenue and South Bay Front
- 39. Grand Canal East Between South Bay Front and Park Avenue
- 40. Grand Canal East Between Balboa Avenue and Park Avenue
- 41. Grand Canal East Between Balboa Avenue and East Bay Front
- 42. East Bay Front Between Grand Canal East and Balboa Avenue
- 43. East Bay Front Between Balboa Avenue and Park Avenue
- 44. East Bay Front Between Park Avenue and South Bay Front
- 45. Leaking Bulkheads Around Both Islands

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture		
	 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 17-51850-2072 NATIONWIDE BRANCH CO.		
STREET LOCATION North Bay Front Between Park Ave and Emerald Ave	INSPECTOR: GTM	INSPECTION DATE: January 10, 2005	REVISION:
	ASSISTANT:		

Item	Location	Description
1	0' West of Emerald Avenue	Reference point at center line of street / public pier
2	17' West of Emerald Avenue	Waterside, mooring anchor insert, rusted
3	60'-74' West of Emerald Avenue	Waterside, crack at bottom of cap
4	74' West of Emerald Avenue	Construction joint, landside missing sealant at bottom of joint, both sides sealant in good condition
5	85' West of Emerald Avenue	Waterside, 72" crack above pile
6	97' West of Emerald Avenue	Waterside, 60" crack above pile
7	108' West of Emerald Avenue	Waterside, 72" crack above pile
8	120' West of Emerald Avenue	Waterside, 72" crack above pile
9	132' West of Emerald Avenue	Waterside, 84" crack above pile
10	143' West of Emerald Avenue	Waterside, 72" crack at top of cap
11	155' West of Emerald Avenue	Waterside, 72" crack above pile
12	167' West of Emerald Avenue	Waterside, 72" crack above pile
13	178' West of Emerald Avenue	Waterside, 12" crack with rust above pile
14	178' West of Emerald Avenue	Waterside, 72" crack under pier
15	190' West of Emerald Avenue	Landside, crack at lower step 60"
16	197' West of Emerald Avenue	Construction joint, landside missing sealant at bottom of joint, sealant both sides cracked and split
17	225' West of Emerald Avenue	Landside, lightpole spalled on landside
18	237' West of Emerald Avenue	Waterside, crack with rust over pile extending under pier 120"
19	248' West of Emerald Avenue	Waterside, crack with rust 72" long
20	260' West of Emerald Avenue	Waterside, crack over pile with rust 84"
21	261' West of Emerald Avenue	Waterside, longitudinal and transverse crack over pile. 72" long longitudinal crack
22	274' West of Emerald Avenue	Landside, transverse crack and repair. Repair in good shape
23	295' West of Emerald Avenue	Landside, transverse crack through cap
24	310' West of Emerald Avenue	Waterside, crack over pile with rust 60"
25	310' West of Emerald Avenue	Construction joint, sealant on both sides split and cracked
26	342' West of Emerald Avenue	Waterside, crack on east side of construction joint 48" long
27	356' West of Emerald Avenue	Waterside, crack at pile 2 each: (1) 48" long, (1) 36" long
28	367' West of Emerald Avenue	Waterside, crack at pile 48" long
29	369' West of Emerald Avenue	Waterside, crack at pile 36" long, void 12"x1/2"
30	377' West of Emerald Avenue	Landside, transverse crack through cap
31	415' West of Emerald Avenue	Waterside, crack over pile 60"x 1/8" with rust present
32	428' West of Emerald Avenue	Landside, lightpole crack at cap
33	428' West of Emerald Avenue	Construction joint, sealant cracked and split
34	428' West of Emerald Avenue	Waterside, crack 60" long extending east from construction joint
35	463' West of Emerald Avenue	Landside, spall on east side of construction joint
36	475' West of Emerald Avenue	Waterside, 60" crack above pile
		Waterside, 30" crack above cap

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005	REVISION:	



North Bay Front, 60' West of Emerald



North Bay Front, 73' West of Emerald



North Bay Front, 85' West of Emerald



North Bay Front, 97' West of Emerald



North Bay Front, 108' West of Emerald



North Bay Front, 120' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005	REVISION:	



North Bay Front, 132' West of Emerald



North Bay Front, 143' West of Emerald



North Bay Front, 155' West of Emerald



North Bay Front, 167' West of Emerald



North Bay Front, 178' West of Emerald



North Bay Front, 179' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Park Ave and Emerald Ave	INSPECTOR: GTM ASSISTANT:	INSPECTION DATE: January 10, 2006	REVISION:	



North Bay Front, 190' West of Emerald



North Bay Front, 191' West of Emerald



North Bay Front, 197' West of Emerald



North Bay Front, 225' West of Emerald



North Bay Front, 237' West of Emerald



North Bay Front, 248' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005	REVISION:	



North Bay Front, 260' West of Emerald



North Bay Front, 261' West of Emerald



North Bay Front, 274' West of Emerald



North Bay Front, 295' West of Emerald



North Bay Front, 307' West of Emerald



North Bay Front, 310' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1115 9TH AVE, SUITE 200 SAN FRANCISCO, CA 94133 (415) 774-2277
STREET LOCATION North Bay Front Between Park Ave and Emerald Ave	INSPECTOR: GTM ASSISTANT:	INSPECTION DATE: January 10, 2005	REVISION:	



North Bay Front, 355' West of Emerald



North Bay Front, 357' West of Emerald



North Bay Front, 369' West of Emerald



North Bay Front, 377' West of Emerald



North Bay Front, 415' West of Emerald



North Bay Front, 428' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005	REVISION:	



North Bay Front, 428' West of Emerald



North Bay Front, 463' West of Emerald



North Bay Front, 475' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture	
STREET LOCATION North Bay Front Between Park Ave and Emerald Ave		INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005 REVISION:



Item	Description	QUANTITY		MATERIAL COST	LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit				Unit Cost	Total
2	17' West of Emerald Avenue, mooring anchor	1	EA				\$25.00	\$25
3	60'-74' West of Emerald Avenue, crack injection	14	LF				\$70.00	\$980
5	85' West of Emerald Avenue, crack injection	6	LF				\$70.00	\$420
6	97' West of Emerald Avenue, crack injection	5	LF				\$70.00	\$350
7	108' West of Emerald Avenue, crack injection	6	LF				\$70.00	\$420
8	120' West of Emerald Avenue, crack injection	7	LF				\$70.00	\$490
9	132' West of Emerald Avenue, crack injection	6	LF				\$70.00	\$420
10	143' West of Emerald Avenue, crack injection	6	LF				\$70.00	\$420
11	155' West of Emerald Avenue, crack injection	6	LF				\$70.00	\$420
12	167' West of Emerald Avenue, crack injection	1	LF				\$70.00	\$70
13	178' West of Emerald Avenue, crack injection	6	LF				\$70.00	\$420
14	178' West of Emerald Avenue, crack injection	5	LF				\$70.00	\$350
15	190' West of Emerald Avenue, crack injection	6	LF				\$25.00	\$150
16	197' West of Emerald Avenue, sealant repair	2	SF				\$70.00	\$140
17	225' West of Emerald Avenue, crack injection	10	LF				\$70.00	\$700
18	237' West of Emerald Avenue, crack injection	6	LF				\$70.00	\$420
19	248' West of Emerald Avenue, crack injection	7	LF				\$70.00	\$490
20	260' West of Emerald Avenue, crack injection	6	LF				\$70.00	\$420
22	274' West of Emerald Avenue, crack injection	6	LF				\$70.00	\$420
23	295' West of Emerald Avenue, crack injection	5	LF				\$70.00	\$350
24	310' West of Emerald Avenue, crack injection	6	LF				\$25.00	\$150
25	310' West of Emerald Avenue, crack injection	4	LF				\$70.00	\$280
26	342' West of Emerald Avenue, crack injection	7	LF				\$70.00	\$490
27	356' West of Emerald Avenue, crack injection	4	LF				\$70.00	\$280
28	367' West of Emerald Avenue, crack injection	3	LF				\$70.00	\$210
29	369' West of Emerald Avenue, crack injection	6	LF				\$70.00	\$420
30	377' West of Emerald Avenue, crack injection	5	LF				\$70.00	\$350
31	415' West of Emerald Avenue, crack injection	5	LF				\$70.00	\$350
32	428' West of Emerald Avenue, crack injection	6	LF				\$25.00	\$150
33	428' West of Emerald Avenue, crack injection	5	LF				\$70.00	\$350
34	428' West of Emerald Avenue, crack injection	3	LF				\$70.00	\$210
35	463' West of Emerald Avenue, crack injection	5	LF				\$70.00	\$350
36	475' West of Emerald Avenue, crack injection	3	LF				\$70.00	\$210

Continued onto next page

ACTIVITY	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING AND ARCHITECTURE 1000 N. 10TH AVE. SUITE 100 ANCHORAGE, ALASKA 99503
Balboa Island Bulkhead Inspection	INSPECTOR: DTM	INSPECTION DATE: January 10, 2005	REVISION:	
STREET LOCATION	ASSISTANT:			
North Bay Front Between Park Ave and Emerald Ave				

Subtotal		\$11,675
Contingency	20 %	\$2,335
Contractor OH & P	10 %	\$1,168
City Cost Index	10 %	\$1,168
GRAND TOTAL		\$16,345

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Emerald Ave and Garnet Ave	INSPECTOR: ASSISTANT:	QTM	INSPECTION DATE: DEC 17, 2004	REVISION:

Item Location	Description
1 0' East of Emerald Avenue	Reference point, centerline of lightpole
2 37' East of Emerald Avenue	Construction joint, sealant on both sides in good condition
3 125' East of Emerald Avenue	Pullbox, landside cracks, waterside cracks through previous repair
4 154' East of Emerald Avenue	Construction joint, sealant waterside in good condition, landside cracked and split
5 223' East of Emerald Avenue	Top of cap cracked, spill repair 4 SQ FT
6 255' East of Emerald Avenue	Mooring anchor insert. Reference point centerline of lightpole at Garnet Avenue



North Bay Front, 37' East of Emerald



North Bay Front, 37' East of Emerald



North Bay Front, 125' East of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1715 NW 10th Ave Suite 200 Miami, FL 33136
STREET LOCATION North Bay Front Between Emerald Ave and Garnet Ave	INSPECTOR ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004	REVISION:



North Bay Front, 125' East of Emerald



North Bay Front, 125' East of Emerald



North Bay Front, 154' East of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Emerald Ave and Garnet Ave	INSPECTOR: ASSISTANT:	GJM	INSPECTION DATE: DEC 17, 2004	REVISION:



North Bay Front, 223' East of Emerald



North Bay Front, 223' East of Emerald



North Bay Front, 154' East of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1150941-0001 404.733.4144
STREET LOCATION North Bay Front Between Emerald Ave and Garnet Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004	REVISION:



North Bay Front, 223' East of Emerald



North Bay Front, 255' East of Emerald

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 995-7072 14010-308 BEACH, CA	
STREET LOCATION North Bay Front Between Emerald Ave and Garnet Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004		REVISION:	

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
3	125' East of Emerald Avenue, crack injection	6	LF					\$70.00	\$420.00
4	154' East of Emerald Avenue, sealant repair	3	LF					\$25.00	\$75.00
5	223' East of Emerald Avenue, spall repair	4	SF					\$70.00	\$280.00
6	255' East of Emerald Avenue, mooring anchor	1	EA					\$25.00	\$25.00

Subtotal				\$800.00
Contingency	20 %			\$160.00
Contractor OH & P	10 %			\$80.00
City Cost Index	10 %			\$80.00
GRAND TOTAL				\$1,120.00

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Garnet Ave and Pearl Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004	REVISION:

Item	Location	Description
1	0' East of Garnet Avenue	Reference point, centerline of lightpole at Garnet Avenue
2	17' East of Garnet Avenue	Waterside, mooring anchor
3	17' East of Garnet Avenue	Construction joint, sealant good on both sides
4	17' East of Garnet Avenue	Waterside, crack through previous spall.
5	43' East of Garnet Avenue	Waterside, mooring anchor, 3 each
6	121' East of Garnet Avenue	Pullbox, crack repair through previous spalls
7	121' East of Garnet Avenue	Pullbox, access cover is accessible to general public through the loss of closure bolts
8	134' East of Garnet Avenue	Construction joint, sealant good on both sides
9	187' East of Garnet Avenue	Waterside, crack at bottom of cap, 36" long
10	224' East of Garnet Avenue	Waterside, mooring anchor insert.
11	230' East of Garnet Avenue	Waterside, crack at bottom of cap, 60" long
12	237' East of Garnet Avenue	Waterside, mooring anchor at centerline of Pearl Avenue lightpole
13	237' East of Garnet Avenue	Reference point, centerline of lightpole at Pearl Avenue

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 Cash & Associates Engineers & Architects 1700 West 10th Suite 100 San Diego, CA 92101
STREET LOCATION North Bay Front Between Garnet Ave and Pearl Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004	REVISION:



17 feet East of Garnet



17 feet East of Garnet



17 feet East of Garnet

ACTIVITY

Balboa Island Bulkhead Inspection

CASH & ASSOCIATES
Engineering and Architecture

STREET LOCATION

North Bay Front
Between Garnet Ave and Pearl Ave

INSPECTOR
ASSISTANT:

CTM

INSPECTION DATE: DEC 17, 2004

REVISION:



CASH & ASSOCIATES
1110201-1429
11/10/04 ERM 16



43 feet East of Garnet



121 feet East of Garnet



121 feet East of Garnet



121 feet East of Garnet



134 feet East of Garnet



134 feet East of Garnet

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			REVISION:
	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004	
STREET LOCATION North Bay Front Between Garnet Ave and Pearl Ave				



187 feet East of Garnet



224 feet East of Garnet



230 feet East of Garnet



237 feet East of Garnet

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Garnet Ave and Pearl Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004	REVISION:



Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
2	17' East of Garnet Avenue, mooring anchor	1	EA					\$25.00	\$25
4	17' East of Garnet Avenue, crack injection	3	LF					\$70.00	\$210
5	43' East of Garnet Avenue, mooring anchor	3	EA					\$25.00	\$75
6	121' East of Garnet Avenue, crack injection	6	LF					\$70.00	\$420
7	121' East of Garnet Avenue, pullbox bolts	4	EA					\$25.00	\$100
9	187' East of Garnet Avenue, crack injection	3	LF					\$70.00	\$210
10	224' East of Garnet Avenue, mooring anchor	1	EA					\$25.00	\$25
11	230' East of Garnet Avenue, crack injection	5	LF					\$70.00	\$350
12	237' East of Garnet Avenue, mooring anchor	1	EA					\$25.00	\$25

Subtotal			\$1,440
Contingency	20 %		\$288
Contractor OH & P	10 %		\$144
City Cost Index	10 %		\$144
GRAND TOTAL			\$2,016

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Pearl Ave and Agate Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004	REVISION:

Item Location	Description
1 17' East of Pearl Avenue	Construction joint, sealant in good shape both water and landsides
2 40' East of Pearl Avenue	Waterside, crack at bottom of cap 60" long
3 110' East of Pearl Avenue	Pullbox, waterside west and landside west corners are cracked 12" long
4 90' West of Agate Avenue	Landside, spall on lower step 24" long x 5" x 5"
5 105' West of Agate Avenue	Construction joint, sealant in good shape both water and landside
6 22' West of Agate Avenue	Waterside, crack at bottom of cap 18" long, rust present
7 12' West of Agate Avenue	Waterside, mooring anchor insert, rust present
8 2' West of Agate Avenue	Waterside, mooring anchor insert, rust present
9 General Notes	Shrinkage cracks at 10' o.c. nothing serious, seawall is straight and in good condition



North Bay Front, 40' East of Pearl



North Bay Front, 110' East of Pearl



North Bay Front, 90' West of Agate

ACTIVITY

Balboa Island Bulkhead Inspection

CASH & ASSOCIATES
Engineering and Architecture

STREET LOCATION

North Bay Front
Between Pearl Ave and Agate Ave

INSPECTOR
ASSISTANT:

QTM

INSPECTION DATE: DEC 17, 2004

REVISION:



2004 & 2005
LICENSE # 1013
REVISED 8-0-04



North Bay Front, 22' West of Agate



North Bay Front, 12' West of Agate



North Bay Front, 12' West of Agate



North Bay Front, 2' West of Agate



North Bay Front, 2' West of Agate

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES INSPECTION & ARCHITECTURE (714) 996-7272 10070101 BALBOA ISLAND CA	
STREET LOCATION North Bay Front Between Pearl Ave and Agate Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004		REVISION:	

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
2	40' East of Pearl Avenue, crack injection	5	LF					\$70.00	\$350
3	110' East of Pearl Avenue, crack injection	6	LF					\$70.00	\$420
4	90' West of Agate Avenue, crack injection	2	LF					\$70.00	\$140
6	22' West of Agate Avenue, crack injection	2	LF					\$70.00	\$140
7	12' West of Agate Avenue, mooring anchor	1	EA					\$25.00	\$25
8	2' West of Agate Avenue, mooring anchor	1	EA					\$25.00	\$25

Subtotal			\$1,100
Contingency	20 %		\$220
Contractor OH & P	10 %		\$110
City Cost Index	10 %		\$110
GRAND TOTAL			\$1,540

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 DOCK & MARINE INSPECTION & REPAIRS (415) 435-3875 www.cash-ca.com
	STREET LOCATION North Bay Front Between Agate Ave and Collins Ave	INSPECTOR: CTM	INSPECTION DATE: DEC 17, 2004	

Item	Location	Description
1	13' East of Agate Avenue	Waterside, mooring anchor, rust present
2	13' East of Agate Avenue	Construction joint, sealant in good shape land side and water side
3	13' East of Agate Avenue	Landside, spall at sidewalk 2" x 3" x 1"
4	32' West of Collins Avenue	Construction joint, sealant cracked and split on waterside, sealant missing on landside and top
5	8' West of Collins Avenue	Spall repair 60" long at top x 6" x 9"; Spall repair at bottom 48" long x 3" x 7"
6	At Collins Avenue	Mooring anchor insert, rust present



North Bay Front, 13' East of Agate



North Bay Front, 13' East of Agate



North Bay Front, 13' East of Agate

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1114 8th St. S.E. SEASIDE, CA 94133
STREET LOCATION North Bay Front Between Agate Ave and Collins Ave	INSPECTOR/L ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004	



North Bay Front, 32' West of Collins



North Bay Front, 32' West of Collins



North Bay Front, 8' West of Collins



North Bay Front, 8' West of Collins



North Bay Front, at Collins

North Bay Front Between Agate Ave and Collins Ave

INSPECTION REPORT

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE [714] 955-2213 10000 10th Ave., LA	
STREET LOCATION North Bay Front Between Agate Ave and Collins Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004	REVISION:		

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	13' East of Agate Avenue, mooring anchor	1	EA					\$25.00	\$25
3	13' East of Agate Avenue, spall repair	0.25	SF					\$70.00	\$18
4	32' West of Collins Avenue, sealant repair	6	LF					\$25.00	\$150
5	8' West of Collins Avenue, spall repair, steps	20	SF					\$70.00	\$1,400
6	At Collins Avenue, mooring anchor	1	EA					\$25.00	\$25

Subtotal		\$1,618
Contingency	20 %	\$324
Contractor OH & P	10 %	\$162
City Cost Index	10 %	\$162
GRAND TOTAL		\$2,265

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
	INSPECTOR: ASSISTANT	CTM	INSPECTION DATE: DEC 17, 2004	
STREET LOCATION North Bay Front Between Collins Ave and Ruby Ave				

Item	Location	Description
1	14' East of Collins Avenue	Waterside, mooring anchor insert, rust present
2	50' East of Collins Avenue	Landside, transverse shrinkage crack across cap
3	85' East of Collins Avenue	Construction joint, sealant cracked and split on waterside, sealant missing on landside and top
4	110' East of Collins Avenue	Pullbox, landside spill through previous repair 30" long x 6" x 5"
5	81' West of Ruby Avenue	Landside, spall at lower step 2" long
6	78' West of Ruby Avenue	Waterside, crack at bottom of cap, 24" long
7	75' West of Ruby Avenue	Waterside, crack at bottom of cap, 60" long
8	66' West of Ruby Avenue	Landside, large shrinkage cracks
9	55' West of Ruby Avenue	Waterside, large shrinkage cracks
10	54' West of Ruby Avenue	Waterside crack 72" long, location of previous repair
11	28' West of Ruby Avenue	Waterside, crack at bottom of cap, 72" long
12	19' West of Ruby Avenue	Construction joint, sealant in good condition land side and water side
13	19' West of Ruby Avenue	Waterside, crack at bottom of cap 30" x 3"
14	7' West of Ruby Avenue	Waterside, crack at bottom of cap 36" long



North Bay Front, 14' East of Collins



North Bay Front, 50' East of Collins



North Bay Front, 50' East of Collins

ACTIVITY

Balboa Island Bulkhead Inspection

CASH & ASSOCIATES
Engineering and Architecture

STREET LOCATION

North Bay Front
Between Collins Ave and Ruby Ave

INSPECTOR:
ASSISTANT:

CTM

INSPECTION DATE: DEC 17, 2004

REVISION:

CA

CASH & ASSOCIATES
ENGINEERING & ARCHITECTURE
(714) 841-8877
www.cash-ca.com



North Bay Front, 85' East of Collins



North Bay Front, 85' East of Collins



North Bay Front, 110' East of Collins

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Collins Ave and Ruby Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 17, 2004	REVISION:



North Bay Front, 110' East of Collins



North Bay Front, 110' East of Collins



North Bay Front, 81' West of Ruby
North Bay Front, 138' East of Collins



North Bay Front, 76' West of Ruby
North Bay Front, 141' East of Collins



North Bay Front, 75' West of Ruby
North Bay Front, 144' East of Collins



North Bay Front, 66' West of Ruby
North Bay Front, 153' East of Collins

ACTIVITY

Balboa Island Bulkhead Inspection

CASH & ASSOCIATES
Engineering and Architecture

STREET LOCATION

North Bay Front
Between Collins Ave and Ruby Ave

INSPECTOR:
ASSISTANT:

CTM

INSPECTION DATE: DEC 17, 2004

REVISION:

CA

CLARK A. CASH
ARCHITECT
1400 NW 10th Ave
Tallahassee, FL 32304
(904) 486-1111



North Bay Front, 55' West of Ruby
North Bay Front, 164' East of Collins



North Bay Front, 55' West of Ruby
North Bay Front, 164' East of Collins



North Bay Front, 28' West of Ruby
North Bay Front, 191' East of Collins



North Bay Front, 19' West of Ruby
North Bay Front, 200' East of Collins



North Bay Front, 7' West of Ruby
North Bay Front, 212' East of Collins

North Bay Front Between Collins Ave and Ruby Ave

INSPECTION REPORT

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture		 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 800-2072 HUNTINGTON BEACH, CA	
STREET LOCATION		INSPECTOR:	CTM	INSPECTION DATE:	DEC 17, 2004
North Bay Front Between Collins Ave and Ruby Ave		ASSISTANT:		REVISION:	

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	14' East of Collins Avenue, mooring anchor	1	EA					\$25.00	\$25
2	50' East of Collins Avenue, crack injection	3	LF					\$70.00	\$210
3	85' East of Collins Avenue, sealant repair	6	LF					\$25.00	\$150
4	110' East of Collins Avenue, spall repair	2	SF					\$70.00	\$140
5	81' West of Ruby Avenue, spall repair	2	SF					\$70.00	\$140
6	78' West of Ruby Avenue, crack injection	2	LF					\$70.00	\$140
7	75' West of Ruby Avenue, crack injection	5	LF					\$70.00	\$350
8	66' West of Ruby Avenue, crack injection	10	LF					\$70.00	\$700
9	55' West of Ruby Avenue, crack injection	6	LF					\$70.00	\$420
10	54' West of Ruby Avenue, crack repair	7	LF					\$70.00	\$490
11	28' West of Ruby Avenue, crack injection	6	LF					\$70.00	\$420
13	19' West of Ruby Avenue, crack injection	3	LF					\$70.00	\$210
14	7' West of Ruby Avenue, crack injection	3	LF					\$70.00	\$210

Subtotal				\$3,605
Contingency	20 %			\$721
Contractor OH & P	10 %			\$361
City Cost Index	10 %			\$361
GRAND TOTAL				\$5,047

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture		 JULIA A. CASH, P.E. 1111000 - 0000 08-2004 04-06-10
STREET LOCATION North Bay Front Between Ruby Ave and Diamond Ave		INSPECTOR: CTM	INSPECTION DATE: DEC 20, 2004	

Item	Location	Description
1	At Ruby Avenue lightpole	Waterside, mooring anchor insert, rust present
2	At Ruby Avenue lightpole	Waterside, 84" long crack at bottom of cap
3	17' East of Ruby Avenue	Waterside, crack at middle of cap 84" long
4	22' East of Ruby Avenue	Waterside, spill and crack landside lower steep 36" long
5	28' East of Ruby Avenue	Waterside, 60" long crack with rust present
6	65' East of Ruby Avenue	Waterside, spill 6" long x 2" high x 2" deep
7	97' East of Ruby Avenue	Construction joint, sealant in good condition both sides
8	111' East of Ruby Avenue	Electrical pull box spill, land and water side 25" long x 3" high x 3" deep
9	134' East of Ruby Avenue	Waterside, crack bottom of cap 24" long
10	215' East of Ruby Avenue at Diamond Avenue	Construction joint, waterside sealant needs repair



North Bay Front, at Ruby



North Bay Front, at Ruby



North Bay Front, at Ruby

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Ruby Ave and Diamond Ave	INSPECTOR: ASSISTANT:	QTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 17' East of Ruby



North Bay Front, 17' East of Ruby



North Bay Front, 22' East of Ruby



North Bay Front, 28' East of Ruby



North Bay Front, 65' East of Ruby



North Bay Front, 65' East of Ruby

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Ruby Ave and Diamond Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 97' East of Ruby



North Bay Front, 97' East of Ruby



North Bay Front, 111' East of Ruby



North Bay Front, 111' East of Ruby



North Bay Front, 134' East of Ruby



North Bay Front, 215' East of Ruby

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Ruby Ave and Diamond Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 215' East of Ruby

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture			
Balboa Island Bulkhead Inspection					
STREET LOCATION		INSPECTOR:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:
North Bay Front Between Ruby Ave and Diamond Ave		ASSISTANT:			



Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	At Ruby Avenue lightpole, mooring anchor	1	EA					\$25.00	\$25
2	At Ruby Avenue lightpole, crack injection	7	LF					\$70.00	\$490
3	17' East of Ruby Avenue, crack injection	7	LF					\$70.00	\$490
4	22' East of Ruby Avenue, spall repair	7	SF					\$70.00	\$490
5	28' East of Ruby Avenue, crack injection	5	LF					\$70.00	\$350
6	65' East of Ruby Avenue, spall repair	0.5	SF					\$70.00	\$35
8	111' East of Ruby Avenue, spall repair	3	SF					\$70.00	\$210
9	134' East of Ruby Avenue, crack injection	2	LF					\$70.00	\$140
10	215' East of Ruby Avenue, sealant repair	6	LF					\$25.00	\$150

Subtotal		\$2,380
Contingency	20 %	\$476
Contractor OH & P	10 %	\$238
City Cost Index	10 %	\$238
GRAND TOTAL		\$3,332

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Diamond Ave and Sapphire Ave	INSPECTOR ASSISTANT	CTM	INSPECTION DATE: DEC 28, 2004	REVISION:

Item	Location	Description
1	15' East of Diamond Avenue	Waterside, crack at bottom of cap, 60" long
2	28' East of Diamond Avenue	Waterside, crack at middle of cap, 36" long
3	38' East of Diamond Avenue	Waterside, crack at bottom of cap, 72" long
4	62' East of Diamond Avenue	Waterside, crack at bottom of cap, 60" long
5	102' East of Diamond Avenue	Landside, spill 48" long x 5" high x 6" deep
6	108' East of Diamond Avenue	Construction joint, sealant cracked and split land and water side
7	112' East of Diamond Avenue	Pullbox, small spill 12"x1"x1/2" at southwest corner of pull box cover
8	132' East of Diamond Avenue	Waterside, crack at bottom of cap 72" long
9	144' East of Diamond Avenue	Waterside, crack at bottom of cap 36" long
10	156' East of Diamond Avenue	Waterside crack at bottom of cap, 72" long
11	167' East of Diamond Avenue	Waterside, crack at bottom of cap, 72" long
12	202' East of Diamond Avenue	Construction joint, sealant needs repair on landside
13	202' East of Diamond Avenue	Spill top of cap 6" long x 8" high x 1/2" deep



North Bay Front, 15' East of Diamond



North Bay Front, 28' East of Diamond



North Bay Front, 38' East of Diamond

ACTIVITY

Balboa Island Bulkhead Inspection

CASH & ASSOCIATES
Engineering and Architecture

STREET LOCATION

North Bay Front
Between Diamond Ave and Sapphire Ave

INSPECTOR:
ASSISTANT:

CTM

INSPECTION DATE: DEC 20, 2004

REVISION:



2004 & 2005
REGISTERED
PROFESSIONAL ENGINEERS
(114) 981-4227
4470000 800-12



North Bay Front, 62' East of Diamond



North Bay Front, 102' East of Diamond



North Bay Front, 108' East of Diamond



North Bay Front, 108' East of Diamond



North Bay Front, 112' East of Diamond



North Bay Front, 132' East of Diamond

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE TEL: 949-435-1229 www.cashassoc.com	
STREET LOCATION North Bay Front Between Diamond Ave and Sapphire Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004		REVISION:



North Bay Front, 144' East of Diamond



North Bay Front, 166' East of Diamond



North Bay Front, 167' East of Diamond



North Bay Front, 202' East of Diamond



North Bay Front, 202' East of Diamond

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION		INSPECTION DATE: DEC 28, 2004			
North Bay Front		INSPECTOR:		REVISION:	
Between Diamond Ave and Sapphire Ave		ASSISTANT:			



Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	15' East of Diamond Avenue, crack injection	5	LF					\$70.00	\$350
2	28' East of Diamond Avenue, crack injection	3	LF					\$70.00	\$210
3	38' East of Diamond Avenue, crack injection	6	LF					\$70.00	\$420
4	62' East of Diamond Avenue, crack injection	5	LF					\$70.00	\$350
5	102' East of Diamond Avenue, spall repair	2	SF					\$70.00	\$140
6	108' East of Diamond Avenue, sealant repair	6	LF					\$25.00	\$150
7	112' East of Diamond Avenue, spall repair	1	SF					\$70.00	\$70
8	132' East of Diamond Avenue, crack injection	6	LF					\$70.00	\$420
9	144' East of Diamond Avenue, crack injection	3	LF					\$70.00	\$210
10	156' East of Diamond Avenue, crack injection	6	LF					\$70.00	\$420
11	167' East of Diamond Avenue, crack injection	6	LF					\$70.00	\$420
12	202' East of Diamond Avenue, sealant repair	6	LF					\$70.00	\$420
13	202' East of Diamond Avenue, spall repair	1	SF					\$70.00	\$70

Subtotal		\$3,650
Contingency	20 %	\$730
Contractor OH & P	10 %	\$365
City Cost Index	10 %	\$365
GRAND TOTAL		\$5,110

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture	
Balboa Island Bulkhead Inspection			
STREET LOCATION		INSPECTOR:	INSPECTION DATE: DEC 20, 2004
North Bay Front Between Sapphire Ave and Coral Ave		CTM	REVISION:
		ASSISTANT:	



Item	Location	Description
1	7' East of Sapphire Avenue	Waterside, spall at bottom of cap, 72" long
2	34' East of Sapphire Avenue	Waterside, crack at bottom of cap 36" long
3	52' East of Sapphire Avenue	Waterside, spall along cap, 60" long and 24" high
4	90' East of Sapphire Avenue	Construction Joint, sealant on land and water side in good condition
5	105' East of Sapphire Avenue	Pullbox, top cap spalled land and water side 24" long x 8" high x 6" deep
6	125' East of Sapphire Avenue	Waterside, crack at bottom of cap 60" long (adjacent to pier)
7	135' East of Sapphire Avenue	Waterside, crack at bottom of cap 60" long (adjacent to pier)
8	148' East of Sapphire Avenue	Waterside, crack at bottom of cap, 72" long
9	158' East of Sapphire Avenue	Waterside, spall at bottom of cap, 60" long x 12" high
10	206' East of Sapphire Avenue	Waterside, spall 48" long x 12" x 1"
11	206' East of Sapphire Avenue	Construction joint, waterside sealant cracked and split, top and landside missing sealant



North Bay Front, 7' East of Sapphire



North Bay Front, 52' East of Sapphire



North Bay Front, 90' East of Sapphire

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES 1715 JEFFERSON AVE SUITE 100 SAN ANTONIO, TX 78201
STREET LOCATION North Bay Front Between Sapphire Ave and Coral Ave	INSPECTOR: CTM	INSPECTION DATE: DEC 20, 2004	REVISION:	



North Bay Front, 90' East of Sapphire



North Bay Front, 105' East of Sapphire



North Bay Front, 105' East of Sapphire



North Bay Front, 105' East of Sapphire



North Bay Front, 105' East of Sapphire



North Bay Front, 125' East of Sapphire

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Sapphire Ave and Coral Ave	INSPECTOR: ASSISTANT	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 135' East of Sapphire



North Bay Front, 148' East of Sapphire



North Bay Front, 158' East of Sapphire



North Bay Front, 206' East of Sapphire



North Bay Front, 206' East of Sapphire

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture					 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714)804-2072 HUNTINGTON BEACH, CA		
STREET LOCATION		INSPECTOR:		CTM	INSPECTION DATE: DEC 20, 2004		REVISION:		
North Bay Front Between Sapphire Ave and Coral Ave		ASSISTANT:							
Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	7' East of Sapphire Avenue, crack injection	6	LF					\$70.00	\$420
2	34' East of Sapphire Avenue, crack injection	3	LF					\$70.00	\$210
3	52' East of Sapphire Avenue, spall repair	10	SF					\$70.00	\$700
5	105' East of Sapphire Avenue, spall repair	4	SF					\$70.00	\$280
6	125' East of Sapphire Avenue, crack injection	5	LF					\$70.00	\$350
7	135' East of Sapphire Avenue, crack injection	5	LF					\$70.00	\$350
8	148' East of Sapphire Avenue, crack injection	6	LF					\$70.00	\$420
9	158' East of Sapphire Avenue, spall repair	5	SF					\$70.00	\$350
10	206' East of Sapphire Avenue, spall repair	4	SF					\$70.00	\$280
11	206' East of Sapphire Avenue, sealant repair	6	LF					\$25.00	\$150
Subtotal								\$3,510	
Contingency		20 %						\$702	
Contractor OH & P		10 %						\$351	
City Cost Index		10 %						\$351	
GRAND TOTAL									\$4,914

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES 1111111111111111 1111111111111111
	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	
STREET LOCATION North Bay Front Between Coral Ave and Apolena Ave				

Item	Location	Description
1	8' East of Coral Avenue	Waterside, crack at bottom of cap, 60" long
2	47' East of Coral Avenue	Construction joint, waterside sealant split and cracked, landside and top sealant missing
3	58' East of Coral Avenue	Waterside, crack at bottom of cap 48" long
4	108' East of Coral Avenue	Pullbox spall both sides of box, 24" x 9" x 6"
5	116' East of Coral Avenue	Waterside, crack at bottom of cap 96" long
6	162' East of Coral Avenue	Construction joint, waterside sealant split and cracked, landside and top sealant missing
7	172' East of Coral Avenue	Top of cap spalled 48" long x 2' wide x 3" deep
8	187' East of Coral Avenue	Waterside top corner of cap spalled and previously repaired, spalling 168" long x 24" high x 12" deep
9	196' East of Coral Avenue	Landside, spall, 48" long x 12" high x 12" deep
10	202' East of Coral Avenue	Waterside, spall 48" long at top of cap
11	207' East of Coral Avenue	Landside, spall at top of cap, 48" long x 18" wide, 9" deep
12	213' East of Coral Avenue	Waterside, crack at bottom of cap 48" long



North Bay Front, 8' East of Coral



North Bay Front, 47' East of Coral



North Bay Front, 47' East of Coral

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 Cash & Associates 17111-101 San Diego, CA 92161
STREET LOCATION North Bay Front Between Coral Ave and Apollonia Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 58' East of Coral



North Bay Front, 108' East of Coral



North Bay Front, 108' East of Coral



North Bay Front, 116' East of Coral



North Bay Front, 162' East of Coral



North Bay Front, 162' East of Coral

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 2004 & 2007-2013 HOLDING & PARTIAL 17-1880-2013 LICENSE NO. 00000000
STREET LOCATION North Bay Front Between Coral Ave and Apolena Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 172' East of Coral



North Bay Front, 172' East of Coral



North Bay Front, 187' East of Coral



North Bay Front, 187' East of Coral



North Bay Front, 187' East of Coral



North Bay Front, 187' East of Coral

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Coral Ave and Apolena Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 196' East of Coral



North Bay Front, 202' East of Coral



North Bay Front, 202' East of Coral



North Bay Front, 207' East of Coral



North Bay Front, 213' East of Coral

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION		INSPECTOR:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:
North Bay Front Between Coral Ave and Apolena Ave		ASSISTANT:			



Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	8' East of Coral Avenue, crack injection	5	LF					\$70.00	\$350
2	47' East of Coral Avenue, sealant repair	6	LF					\$40.00	\$240
3	58' East of Coral Avenue, crack injection	4	LF					\$70.00	\$280
4	108' East of Coral Avenue, spall repair	6	SF					\$70.00	\$420
5	116' East of Coral Avenue, crack injection	8	LF					\$70.00	\$560
6	162' East of Coral Avenue, sealant repair	6	LF					\$40.00	\$240
7	172' East of Coral Avenue, spall repair	8	SF					\$70.00	\$560
8	187' East of Coral Avenue, Spall repair	24	SF					\$70.00	\$1,680
9	196' East of Coral Avenue, spall repair	4	SF					\$70.00	\$280
10	202' East of Coral Avenue, Spall repair	4	SF					\$70.00	\$280
11	207' East of Coral Avenue, spall repair	6	SF					\$70.00	\$420
12	213 East of Coral Avenue, crack injection	4	LF					\$70.00	\$280

Subtotal		\$5,590
Contingency	20 %	\$1,118
Contractor OH & P	10 %	\$559
City Cost Index	10 %	\$559
GRAND TOTAL		\$7,826

ACTIVITY	CASH & ASSOCIATES Engineering and Architecture		
STREET LOCATION	INSPECTOR:	QTM	INSPECTION DATE: DEC 20, 2004
North Bay Front Between Apolena Ave and Amethyst Ave	ASSISTANT:		REVISION:



Item	Location	Description
1	13' East of Apolena Avenue	Top of cap spalled 60" x 24" x 6"
2	26' East of Apolena Avenue	Waterside, crack at bottom of cap 72" long
3	32' East of Apolena Avenue	Waterside, crack at bottom of cap 72" long
4	38' East of Apolena Avenue	Waterside, crack at bottom of cap 72" long
5	60' East of Apolena Avenue	Construction joint, waterside sealant cracked and split, landside and top missing sealant
6	94' East of Apolena Avenue	Waterside and top of cap spalled 24" long x 12" high x 2" deep
7	109' East of Apolena Avenue	Pull box, spalls both sides 24" long x 8" high x 3" deep
8	176' East of Apolena Avenue	Construction joint, waterside sealant cracked and split, landside and top missing sealant
9	181' East of Apolena Avenue	Landside, at top of cap crack, 36" long
10	186' East of Apolena Avenue	Landside face, spall 48" long x 24" high x 3" deep
11	186' East of Apolena Avenue	Waterside at top of cap, spall 36" long x 12" high x 6" deep
12	200' - 216' East of Apolena Avenue	Top cap spalled 180" long x 24" wide x 12" deep



North Bay Front, 13' East of Apolena



North Bay Front, 13' East of Apolena



North Bay Front, 26' East of Apolena

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1711000-0010 SAN DIEGO, CALIF. 92108
STREET LOCATION North Bay Front Between Apolena Ave and Amethyst Ave	INSPECTOR: CTM	INSPECTION DATE: DEC 20, 2004	REVISION:	



North Bay Front, 32' East of Apolena



North Bay Front, 38' East of Apolena



North Bay Front, 60' East of Apolena



North Bay Front, 60' East of Apolena



North Bay Front, 94' East of Apolena



North Bay Front, 109' East of Apolena

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES 114100-0018 04/01/00 8:00 PM
STREET LOCATION North Bay Front Between Apolena Ave and Amethyst Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 109' East of Apolena



North Bay Front, 176' East of Apolena



North Bay Front, 176' East of Apolena



North Bay Front, 181' East of Apolena



North Bay Front, 181' East of Apolena



North Bay Front, 186' East of Apolena

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Apolena Ave and Amethyst Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 186' East of Apolena



North Bay Front, 203' East of Apolena



North Bay Front, 203' East of Apolena



North Bay Front, 203' East of Apolena

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
	 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 950-1272 JALINGTON BRIDGE, CA			
STREET LOCATION North Bay Front Between Apolena Ave and Amethyst Ave	INSPECTOR:	CTM	INSPECTION DATE: DEC 20, 2004	
	ASSISTANT:		REVISION:	

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	13' East of Apolena Avenue, spall repair	12	SF					\$70.00	\$840
2	26' East of Apolena Avenue, crack injection	6	LF					\$70.00	\$420
3	32' East of Apolena Avenue, crack injection	6	LF					\$70.00	\$420
4	38' East of Apolena Avenue, crack injection	6	LF					\$70.00	\$420
5	60' East of Apolena Avenue, sealant repair	6	LF					\$25.00	\$150
6	94' East of Apolena Avenue, spall repair	3	SF					\$70.00	\$210
7	109' East of Apolena Avenue, spall repair	4	SF					\$70.00	\$280
8	176' East of Apolena Avenue, sealant repair	6	LF					\$70.00	\$420
9	181' East of Apolena Avenue, crack injection	3	LF					\$70.00	\$210
10	186' East of Apolena Avenue, spall repair	8	SF					\$70.00	\$560
11	186' East of Apolena Avenue, spall repair	3	SF					\$70.00	\$210
12	200' - 218' East of Apolena Avenue, spall repair	30	SF					\$70.00	\$2,100

Subtotal			\$6,240
Contingency	20 %		\$1,248
Contractor OH & P	10 %		\$624
City Cost Index	10 %		\$624
GRAND TOTAL			\$8,736

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture				
STREET LOCATION North Bay Front Between Amethyst Ave and Onyx Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:	CASH & ASSOCIATES 10000 15th Ave, Suite 100 San Diego, CA 92161 (619) 584-1234 Fax: (619) 584-1235

Item	Location	Description
1	5' East of Amethyst Avenue	Top of cap, crack, 3' long
2	11' East of Amethyst Avenue	Top of cap, crack, 3' long
3	74' East of Amethyst Avenue	Construction joint, waterside sealant cracked and split, landside and top sealant missing
4	110' East of Amethyst Avenue	Pull box, spall 24" long x 3" high x 9" deep
5	190' East of Amethyst Avenue	Construction joint, waterside sealant cracked and split, landside and top sealant missing
6	195' East of Amethyst Avenue	Waterside, spall at bottom of cap 72" long x 12" high x 12" deep



North Bay Front, 5' East of Amethyst



North Bay Front, 11' East of Amethyst



North Bay Front, 74' East of Amethyst

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 969-3333 4401 North Balboa, Suite 111
STREET LOCATION North Bay Front Between Amethyst Ave and Onyx Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 74' East of Amethyst



North Bay Front, 110' East of Amethyst



North Bay Front, 110' East of Amethyst



North Bay Front, 190' East of Amethyst



North Bay Front, 190' East of Amethyst



North Bay Front, 195' East of Amethyst

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 566-4072 4111 CASHMAN RD. SUITE 200	
STREET LOCATION North Bay Front Between Amethyst Ave and Onyx Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:		

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	5' East of Amethyst Avenue, spall repair	6	SF					\$70.00	\$420
2	11' East of Amethyst Avenue, spall repair	6	SF					\$70.00	\$420
3	74' East of Amethyst Avenue, sealant repair	6	LF					\$25.00	\$150
4	110' East of Amethyst Avenue, spall repair	4	SF					\$70.00	\$280
5	190' East of Amethyst Avenue, sealant repair	6	LF					\$25.00	\$150
6	195' East of Amethyst Avenue, spall repair	6	SF					\$70.00	\$420

Subtotal		\$1,840
Contingency	20 %	\$368
Contractor OH & P	10 %	\$184
City Cost Index	10 %	\$184
GRAND TOTAL		\$2,576

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture	
STREET/LOCATION North Bay Front Between Onyx Ave and Marine Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004 REVISION:



Item	Location	Description
1	5' East of Onyx Avenue	Waterside, crack lower half of cap 36" long
2	32' East of Onyx Avenue	Waterside, crack at bottom of cap 144" long
3	42' East of Onyx Avenue	Waterside, crack at bottom of cap, 24" long
4	53' East of Onyx Avenue	Waterside, spall at bottom of cap 60" long x 12" high x 6" deep
5	62' East of Onyx Avenue	Waterside, crack at bottom of cap, 60" long
6	74' East of Onyx Avenue	Waterside, spall at bottom of cap, 60" long x 12" high x 6" deep
7	87' East of Onyx Avenue	Construction joint, waterside sealant cracked and split, landside and top sealant missing
8	106' East of Onyx Avenue	Pull box, landside spall 24" long x 6" high x 4" deep
9	122' East of Onyx Avenue	Waterside, crack at bottom of cap, 36" long



North Bay Front, 5' East of Onyx



North Bay Front, 32' East of Onyx



North Bay Front, 42' East of Onyx

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Onyx Ave and Marine Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISIONS:



North Bay Front, 53' East of Onyx



North Bay Front, 62' East of Onyx



North Bay Front, 74' East of Onyx



North Bay Front, 87' East of Onyx



North Bay Front, 87' East of Onyx



North Bay Front, 109' East of Onyx

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES 1000 N. MILPITAS AVE. SUITE 100 SAN JOSE, CA 95128 (408) 951-1111
STREET LOCATION North Bay Front Between Onyx Ave and Marine Ave	INSPECTOR ASSISTANT	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 122' East of Onyx

ACTIVITY Batboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES 1111 PCH-3000 San Diego, CA 92101
STREET LOCATION North Bay Front Between Marine Ave and Grand Canal West	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:

Item	Location	Description
1	61' East of Marine Avenue	Waterside, spall at bottom of cap, 36" long
2	95' East of Marine Avenue	Waterside, spall at top of cap, 24" square x 2" deep
3	166' East of Marine Avenue	Waterside, cracked above pile, longitudinal crack 60" long
4	173' East of Marine Avenue	Waterside, crack with rust at center of cap, 36" long



North Bay Front, 61' East of Marine



North Bay Front, 95' East of Marine



North Bay Front, 166' East of Marine

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION North Bay Front Between Marine Ave and Grand Canal West	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:



North Bay Front, 173' East of Marine



North Bay Front, 166' East of Marine

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1714/2893-2012 NOTED TO: 08/20/12	
STREET LOCATION North Bay Front Between Marine Ave and Grand Canal West		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004	REVISION:		

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	61' East of Marine Avenue, crack injection	3	LF					\$70.00	\$210
2	95' East of Marine Avenue, spall repair	4	SF					\$70.00	\$280
3	166' East of Marine Avenue, crack injection	5	LF					\$70.00	\$350
4	173' East of Marine Avenue, crack injection	3	LF					\$70.00	\$210

Subtotal			\$1,050
Contingency	20 %		\$210
Contractor OH & P	10 %		\$105
City Cost Index	10 %		\$105
GRAND TOTAL			\$1,470

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture		REVISION:
	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005	
STREET LOCATION South Bay Front Between Park Ave and Emerald Ave			



Item	Location	Description
1	86' West of Emerald Avenue	Landside, cracking at lower step 72"
2	95' West of Emerald Avenue	Pullbox, cracked on landside, 30", waterside repaired and in good shape
3	144' West of Emerald Avenue	Waterside, vertical crack through cap 30" long
4	153' West of Emerald Avenue	Waterside, vertical crack at panel joints
5	160' West of Emerald Avenue	Waterside, vertical crack through previous repair
6	170' West of Emerald Avenue	Landside, crack through previous repair
7	195' West of Emerald Avenue	Landside, transverse crack through cap at lightpole
8	212' West of Emerald Avenue	Landside, transverse crack through cap
9	263' West of Emerald Avenue	Waterside, vertical crack through previous repair
10	280' West of Emerald Avenue	Landside, transverse crack through cap at previous repair
11	309' West of Emerald Avenue	Landside, transverse crack through cap at previous repair
12	327' West of Emerald Avenue	Waterside, vertical crack through cap 30" long
13	340' West of Emerald Avenue	Waterside, crack at bottom of cap
14	354' West of Emerald Avenue	Waterside, spall at bottom of cap 24" long x 12" high x 1" deep
15	354' West of Emerald Avenue	Waterside, vertical crack through previous repair
16	354' West of Emerald Avenue	Waterside, panel joint opened up
17	379' West of Emerald Avenue	Construction joint, at bottom of previous repair pulling away
18	408' West of Emerald Avenue	Landside, transverse crack through lower step
19	416' West of Emerald Avenue	Waterside, vertical crack through cap 30" long
20	420' West of Emerald Avenue	Pullbox, cracked on both sides
21	445' West of Emerald Avenue	Construction joint spall at bottom of cap 48" long x 16" high x 6" deep
22	492' West of Emerald Avenue	Construction joint, sealant landside and waterside in good condition
23	492' West of Emerald Avenue	Spall and cracked on west side of construction joint

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2006	REVISION:	



South Bay Front, 86' West of Emerald



South Bay Front, 95' West of Emerald



South Bay Front, 95' West of Emerald


ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005	REVISION:	



South Bay Front, 101' West of Emerald



South Bay Front, 144' West of Emerald



South Bay Front, 153' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 1001 N. Milpitas Blvd. Suite 100 Milpitas, CA 95035 (415) 951-1234 www.cash-engineers.com
STREET LOCATION South Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005	REVISION:	



South Bay Front, 153' West of Emerald



South Bay Front, 160' West of Emerald



South Bay Front, 170' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 11111111111111111111 11111111111111111111
STREET LOCATION South Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005	REVISION:	



South Bay Front, 172' West of Emerald



South Bay Front, 195' West of Emerald



South Bay Front, 212' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005	REVISION:	



South Bay Front, 263' West of Emerald



South Bay Front, 280' West of Emerald



South Bay Front, 300' West of Emerald



South Bay Front, 309' West of Emerald



South Bay Front, 327' West of Emerald



South Bay Front, 340' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2025	REVISION:	



South Bay Front, 352' West of Emerald



South Bay Front, 352' West of Emerald



South Bay Front, 354' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES 114900-0000 114900-0000
STREET LOCATION South Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005	REVISION:	



South Bay Front, 378' West of Emerald



South Bay Front, 375' West of Emerald



South Bay Front, 379' West of Emerald



South Bay Front, 408' West of Emerald



South Bay Front, 416' West of Emerald



South Bay Front, 420' West of Emerald

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Park Ave and Emerald Ave	INSPECTOR: CTM ASSISTANT:	INSPECTION DATE: January 10, 2005	REVISION:	



South Bay Front, 420' West of Emerald



South Bay Front, 420' West of Emerald



South Bay Front, 445' West of Emerald



South Bay Front, 492' West of Emerald



South Bay Front, 492' West of Emerald

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1714-1567-2072 HOUSTON, TEXAS, U.S.A.			
STREET LOCATION		INSPECTOR: CTM ASSISTANT:		INSPECTION DATE: January 10, 2005		REVISION:			
South Bay Front Between Park Ave and Emerald Ave									
Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	86' West of Emerald Avenue, crack injection	6	LF					\$70.00	\$420
2	95' West of Emerald Avenue, crack injection	3	LF					\$70.00	\$210
3	144' West of Emerald Avenue, crack injection	3	LF					\$70.00	\$210
4	153' West of Emerald Avenue, crack injection	6	LF					\$70.00	\$420
5	160' West of Emerald Avenue, crack injection	6	LF					\$70.00	\$420
6	170' West of Emerald Avenue, crack injection	6	LF					\$70.00	\$420
7	195' West of Emerald Avenue, crack injection	3	LF					\$70.00	\$210
8	212' West of Emerald Avenue, crack injection	6	LF					\$70.00	\$420
9	263' West of Emerald Avenue, crack injection	3	LF					\$70.00	\$210
10	280' West of Emerald Avenue, crack injection	4	LF					\$70.00	\$280
11	309' West of Emerald Avenue, crack injection	4	LF					\$70.00	\$280
12	327' West of Emerald Avenue, crack injection	3	LF					\$70.00	\$210
13	340' West of Emerald Avenue, crack injection	6	LF					\$70.00	\$420
14	354' West of Emerald Avenue, spall repair	2	SF					\$70.00	\$140
15	354' West of Emerald Avenue, crack injection	6	LF					\$70.00	\$420
18	408' West of Emerald Avenue, crack injection	5	LF					\$70.00	\$350
19	416' West of Emerald Avenue, crack injection	3	LF					\$70.00	\$210
20	420' West of Emerald Avenue, crack injection	6	LF					\$70.00	\$420
21	445' West of Emerald Avenue, crack injection	6	LF					\$70.00	\$420
23	492' West of Emerald Avenue, spall repair	2	SF					\$70.00	\$140
Subtotal								\$6,230	
Contingency		20 %						\$1,246	
Contractor OH & P		10 %						\$623	
City Cost Index		10 %						\$623	
GRAND TOTAL								\$8,722	

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 Cash & Associates 11111 1st St San Diego, CA 92161
STREET LOCATION South Bay Front Between Emerald Ave and Garnet Ave	INSPECTOR: ASSISTANT:	GTM	INSPECTION DATE	

Item	Location	Description
1	66' West of Garnet Avenue	Landside, transverse crack through cap
2	67' West of Garnet Avenue	Waterside, crack over pile 60" long
3	101' West of Garnet Avenue	Construction joint, sealant waterside and landside cracked and split
4	113' West of Garnet Avenue	Waterside, 72" crack over pile, spall 12" long x 12" wide x 4" high on west side of pile bottom of cap
5	115' West of Garnet Avenue	Pullbox, spall on waterside and landside
6	125' West of Garnet Avenue	Waterside, crack 60" long over pile
7	148' West of Garnet Avenue	Waterside, crack 60" long over pile
8	159' West of Garnet Avenue	Waterside, crack at bottom of cap 96" long
9	172' West of Garnet Avenue	Waterside, crack at bottom of cap 120" long
10	185' West of Garnet Avenue	Waterside, cross crack 24" long x 12" high
11	194' West of Garnet Avenue	Waterside, crack 36" long over pile
12	201' West of Garnet Avenue	Landside, crack at top of walk going to waterside 24" long
13	213' West of Garnet Avenue	Construction joint, sealant in good shape
14	213' West of Garnet Avenue	Landside, longitudinal crack to east of construction joint 72" long lower step
15	220' West of Garnet Avenue	(Reference centerline of Emerald Avenue)



South Bay Front, 68' West of Garnet



South Bay Front, 67' West of Garnet



South Bay Front, 101' West of Garnet

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (949) 441-1234 100 NORTH BROADWAY
STREET LOCATION South Bay Front Between Emerald Ave and Garnet Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE:	REVISION:	



South Bay Front, 113' West of Garnet



South Bay Front, 115' West of Garnet



South Bay Front, 115' West of Garnet



South Bay Front, 125' West of Garnet



South Bay Front, 148' West of Garnet



South Bay Front, 159' West of Garnet

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1714 9th St. S.E. ALBUQUERQUE, NM 87102 (505) 263-1234	
STREET LOCATION South Bay Front Between Emerald Ave and Garnet Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE:	REVISION:		



South Bay Front, 172' West of Garnet



South Bay Front, 185' West of Garnet



South Bay Front, 194' West of Garnet



South Bay Front, 201' West of Garnet



South Bay Front, 213' West of Garnet

ACTIVITY

Balboa Island Bulkhead Inspection

CASH & ASSOCIATES
Engineering and Architecture



CASH & ASSOCIATES
ENGINEERING & ARCHITECTURE
(714) 985-2073
CORPUS CHRISTI, TX

STREET LOCATION

South Bay Front
Between Emerald Ave and Garnet Ave

INSPECTOR:
ASSISTANT:

CTM

INSPECTION DATE:

REVISION:

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	66' West of Garnet Avenue, crack injection	6	LF					\$70	\$420.00
2	67' West of Garnet Avenue, crack injection	5	LF					\$70	\$350.00
3	101' West of Garnet Avenue, sealant repair	6	LF					\$25	\$150.00
4	113' West of Garnet Avenue, crack injection	8	LF					\$70	\$560.00
5	115' West of Garnet Avenue, spall repair	6	SF					\$70	\$420.00
6	125' West of Garnet Avenue, crack injection	5	LF					\$70	\$350.00
7	148' West of Garnet Avenue, crack injection	5	LF					\$70	\$350.00
8	159' West of Garnet Avenue, crack injection	8	LF					\$70	\$560.00
9	172' West of Garnet Avenue, crack injection	10	LF					\$70	\$700.00
10	185' West of Garnet Avenue, crack injection	4	LF					\$70	\$280.00
11	194' West of Garnet Avenue, crack injection	3	LF					\$70	\$210.00
12	201' West of Garnet Avenue, crack injection	2	LF					\$70	\$140.00
14	213' West of Garnet Avenue, crack injection	6	LF					\$70	\$420.00

Subtotal
Contingency
Contractor OH & P
City Cost Index

20 %
10 %
10 %

\$4,910
\$982
\$491
\$491

GRAND TOTAL

\$6,874

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture		 2900 N. ALHAMBRA SUITE 200 (714) 365-8575 CASH@CASH-CA.COM
STREET LOCATION South Bay Front Between Garnet Ave and Pearl Ave		INSPECTOR ASSISTANT	CTM INSPECTION DATE: DEC. 21, 2004	

Item	Location	Description
1	17' East of Garnet Avenue	Construction joint, waterside and landside sealant in good shape
2	17' East of Garnet Avenue	Waterside, minor cracking
3	51' East of Garnet Avenue	Waterside, transverse crack through cap
4	84' East of Garnet Avenue	Waterside, transverse crack through cap
5	85' East of Garnet Avenue	Waterside, transverse crack through cap
6	115' east of Garnet Avenue	Pull box, in good shape, no spalling
7	134' East of Garnet Avenue	Construction joint, waterside sealant cracked and split, landside and top missing sealant
8	221' East of Garnet Avenue	Waterside spall at bottom of cap 108" long x 18" tall x 6" deep



South Bay Front, 17' East of Garnet



South Bay Front, 17' East of Garnet



South Bay Front, 51' East of Garnet

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Garnet Ave and Pearl Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:



South Bay Front, 51' East of Garnet



South Bay Front, 84' East of Garnet



South Bay Front, 64' East of Garnet



South Bay Front, 85' East of Garnet



South Bay Front, 115' East of Garnet



South Bay Front, 134' East of Garnet

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES ENGINEERING AND ARCHITECTURE			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1700 S. 10TH ST. ANAHEIM, CA 92805
STREET LOCATION South Bay Front Between Garnet Ave and Pearl Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:



South Bay Front, 134' East of Garnet



South Bay Front, 221' East of Garnet

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 895-1072 SANTA ANA, CALIF. 92701			
STREET LOCATION		INSPECTOR:		CTM		INSPECTION DATE: DEC 21, 2004		REVISION:	
South Bay Front Between Garnet Ave and Pearl Ave		ASSISTANT:							

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
2	17' East of Garnet Avenue, crack injection	1	LF					\$70.00	\$70
3	51' East of Garnet Avenue, crack injection	6	LF					\$70.00	\$420
4	64' East of Garnet Avenue, crack injection	6	LF					\$70.00	\$420
5	85' East of Garnet Avenue, crack injection	6	LF					\$70.00	\$420
7	134' East of Garnet Avenue, sealant repair	6	LF					\$25.00	\$150
8	221' East of Garnet Avenue, crack injection	9	LF					\$70.00	\$630

Subtotal		\$2,110
Contingency	20 %	\$422
Contractor OH & P	10 %	\$211
City Cost Index	10 %	\$211
GRAND TOTAL		\$2,954

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture		
STREET LOCATION South Bay Front Between Pearl Ave and Agate Ave	INSPECTOR: CTM	INSPECTION DATE: DEC 21, 2004	REVISION:
			

Item Location	Description
1 23' East of Pearl Avenue	Construction joint, waterside sealant cracked, landside sealant in good shape
2 33' East of Pearl Avenue	Waterside, spall at bottom of cap 96" long x 18" tall x 3" deep
3 45' East of Pearl Avenue	Landside, spall at lower step 48" long x 6" high x 4" deep
4 92' East of Pearl Avenue	Waterside spall at top of cap 2" long x 2" high x 4" deep
5 112' East of Pearl Avenue	Pullbox, spall 30" long x 7" high x 5" deep
6 141' East of Pearl Avenue	Construction joint, waterside sealant cracked, landside sealant in good shape
7 Note	Transverse cracks at 7' - 12' on center along cap



South Bay Front, 23' East of Pearl



South Bay Front, 23' East of Pearl



South Bay Front, 33' East of Pearl

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Pearl Ave and Agate Ave	INSPECTOR: CTM	INSPECTION DATE: DEC 21, 2004	REVISION:	



South Bay Front, 45' East of Pearl



South Bay Front, 92' East of Pearl



South Bay Front, 112' East of Pearl



South Bay Front, 141' East of Pearl



South Bay Front, 141' East of Pearl

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture			
Balboa Island Bulkhead Inspection					
STREET LOCATION		INSPECTOR:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:
South Bay Front Between Pearl Ave and Agate Ave		ASSISTANT:			



Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	23' East of Pearl Avenue, sealant repair	3	LF					\$25.00	\$75
2	33' East of Pearl Avenue, crack injection	8	LF					\$70.00	\$560
3	45' East of Pearl Avenue, spall repair	4	SF					\$70.00	\$280
4	92' East of Pearl Avenue, spall repair	6	SF					\$70.00	\$420
5	112' East of Pearl Avenue, spall repair	3	SF					\$70.00	\$210
6	141' East of Pearl Avenue, sealant repair	3	LF					\$25.00	\$75
7	Note, transverse cracks at 7' o.c. shrinkage cracks	60	LF					\$70.00	\$4,200

Subtotal			\$5,820
Contingency	20 %		\$1,164
Contractor OH & P	10 %		\$582
City Cost Index	10 %		\$582
GRAND TOTAL			\$8,148

ACTIVITY	CASH & ASSOCIATES Engineering and Architecture		
Balboa Island Bulkhead Inspection	INSPECTOR:	CTM	INSPECTION DATE: DEC 21, 2004
STREET LOCATION	ASSISTANT:		REVISION:
South Bay Front Between Agate Ave and Opal Ave			



Item	Location	Description
1	34' East of Agate Avenue	Construction joint, waterside obstructed by "electrical room", landside missing sealant
2	110' East of Agate Avenue	Pull box, in good condition
3	116' East of Agate Avenue	Construction joint, landside and top missing sealant, waterside cracked and needs repair
4	116' East of Agate Avenue	Waterside, spill at bottom of cap 36" long
5	79' East of Agate Avenue	Previously repaired spill, cracked 60" long x 6" high x 2" deep, bottom half of cap
6	209' East of Agate Avenue	Waterside, bottom of cap spalled 72" long x 8" high



South Bay Front, 34' East of Agate



South Bay Front, 79' East of Agate



South Bay Front, 110' East of Agate

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1700 19th Street San Francisco, CA 94133
STREET LOCATION South Bay Front Between Agate Ave and Opal Ave	INSPECTOR: ASSISTANT:	GTM	INSPECTION DATE: DEC 21, 2004	



South Bay Front, 116' East of Agate



South Bay Front, 116' East of Agate



South Bay Front, 116' East of Agate



South Bay Front, 209' East of Agate

South Bay Front Between Agate Ave and Opal Ave

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (314) 925-1072 4400 N. 10TH ST. SUITE 200, ST. LOUIS, MO 63107	
STREET LOCATION		INSPECTOR: CTM		INSPECTION DATE: DEC 21, 2004		REVISION:	
South Bay Front Between Agate Ave and Opal Ave		ASSISTANT:					

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	34' East of Agate Avenue, sealant repair	3	LF					\$25.00	\$75
3	116' East of Agate Avenue, sealant repair	3	LF					\$25.00	\$75
4	116' East of Agate Avenue, crack injection	6	LF					\$70.00	\$420
5	79' East of Agate Avenue, crack repair	5	LF					\$70.00	\$350
6	209' East of Agate Avenue, crack injection	6	LF					\$70.00	\$420

Subtotal		\$1,340
Contingency	20 %	\$268
Contractor OH & P	10 %	\$134
City Cost Index	10 %	\$134
GRAND TOTAL		\$1,876

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture	
STREET LOCATION South Bay Front Between Opal Ave and Topaz Ave		INSPECTOR: ASSISTANT:	CTM INSPECTION DATE: DEC 21, 2004
		REVISION:	



Item	Location	Description
1	3' East of Opal Avenue	Waterside, spall at bottom of pier support, 18" long x 12" high x 4" deep
2	17' East of Opal Avenue	Construction joint, landside sealant and top in good shape, waterside sealant cracked and split
3	17' East of Opal Avenue	Waterside, crack at bottom of cap 36" long
4	27' East of Opal Avenue	Waterside, crack at bottom of cap 60" long
5	51' East of Opal Avenue	Waterside, crack at bottom of cap 168" long
6	63' East of Opal Avenue	Waterside, crack at bottom of cap, 108 long
7	74' East of Opal Avenue	Waterside, crack at bottom of cap, 48" long
8	86' East of Opal Avenue	Waterside, crack at bottom of cap 24" long, light spalling
9	108' East of Opal Avenue	Waterside, crack at bottom of cap, 24" long light spalling
10	116' East of Opal Avenue	Pullbox, spalling at landside and waterside 24" long x 3" wide x 3" deep
11	132' East of Opal Avenue	Construction joint, sealant landside and top missing; waterside sealant cracked and split



South Bay Front, 3' East of Opal



South Bay Front, 17' East of Opal



South Bay Front, 27' East of Opal

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 114985-0312 March 2004
STREET LOCATION South Bay Front Between Opal Ave and Topaz Ave	INSPECTOR: ASSISTANT	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:



South Bay Front, 51' East of Opal



South Bay Front, 63' East of Opal



South Bay Front, 74' East of Opal



South Bay Front, 98' East of Opal



South Bay Front, 108' East of Opal



South Bay Front, 116' East of Opal

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 11101841-1000 JANUARY 2004	
STREET LOCATION South Bay Front Between Opal Ave and Topaz Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004		REVISION:



South Bay Front, 132' East of Opal



South Bay Front, 132' East of Opal

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 955-2072 HAYWARD, CALIF., U.S.A.	
STREET LOCATION		INSPECTOR: CTM		INSPECTION DATE: DEC 21, 2004		REVISION:	
Balboa Island Bulkhead Inspection		ASSISTANT:					
South Bay Front Between Opal Ave and Topaz Ave							

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	3' East of Opal Avenue, spill repair	2	SF				\$70.00		\$140
2	17' East of Opal Avenue, sealant repair	3	LF				\$25.00		\$75
3	17' East of Opal Avenue, crack injection	3	LF				\$70.00		\$210
4	27' East of Opal Avenue, crack injection	5	LF				\$70.00		\$350
5	51' East of Opal Avenue, crack injection	13	LF				\$70.00		\$910
6	63' East of Opal Avenue, crack injection	9	LF				\$70.00		\$630
7	74' East of Opal Avenue, crack injection	4	LF				\$70.00		\$280
8	96' East of Opal Avenue, crack injection	2	LF				\$70.00		\$140
9	108' East of Opal Avenue, crack injection	2	LF				\$70.00		\$140
10	116' East of Opal Avenue, spill repair	6	LF				\$70.00		\$420
11	132' East of Opal Avenue, sealant repair	6	LF				\$25.00		\$150

Subtotal		\$3,445
Contingency	20 %	\$689
Contractor OH & P	10 %	\$345
City Cost Index	10 %	\$345
GRAND TOTAL		\$4,823

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture	
STREET LOCATION South Bay Front Between Topaz Ave and Turquoise Ave		INSPECTOR: ASSISTANT:	CTM
		INSPECTION DATE: DEC 21, 2004	
		REVISION:	



Item Location

- 1 22' East of Topaz Avenue
- 2 68' East of Topaz Avenue
- 3 115' East of Topaz Avenue
- 4 115' East of Topaz Avenue
- 5 139' East of Topaz Avenue
- 6 173' East of Topaz Avenue
- 7 General comments

Description

Construction joint, waterside sealant cracked and split, landside and top sealant missing
 Top of cap, spalled at previous repair location 66" long x 10" high x 12" deep
 Pullbox, waterside, previous crack repair, spalling "hollow sounding" 24" long x 3" high x 1" deep
 Pullbox, area in line with the seawall spalling adjacent to box 12" long x 2" high x 1" deep
 Construction joint, waterside sealant cracked and split, landside and top sealant in good shape
 Waterside, spall at bottom of cap 48" long x 12" high x 2" deep
 Shrinkage cracks at 120" on center transverse through cap, typical



South Bay Front, 22' East of Topaz



South Bay Front, 22' East of Topaz



South Bay Front, 68' East of Topaz

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Topaz Ave and Turquoise Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:



South Bay Front, 68' East of Topaz



South Bay Front, 115' East of Topaz



South Bay Front, 139' East of Topaz



South Bay Front, 139' East of Topaz



South Bay Front, 173' East of Topaz

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture									
Balboa Island Bulkhead Inspection											
STREET LOCATION		INSPECTOR:		CTM		INSPECTION DATE: DEC 21, 2004		REVISION:			
South Bay Front		ASSISTANT:									
Between Topaz Ave and Turquoise Ave											

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	22' East of Topaz Avenue, sealant repair	6	LF					\$25.00	\$150
2	68' East of Topaz Avenue, spall repair	6	SF					\$70.00	\$420
3	115' East of Topaz Avenue, spall repair	6	SF					\$70.00	\$420
4	115' East of Topaz Avenue, spall repair	3	SF					\$70.00	\$210
5	139' East of Topaz Avenue, sealant repair	3	LF					\$25.00	\$75
6	173' East of Topaz Avenue, crack injection	4	LF					\$70.00	\$280
7	General, transverse cracks, minor, optional	130	LF					\$70.00	\$9,100



Subtotal		\$10,655
Contingency	20 %	\$2,131
Contractor OH & P	10 %	\$1,066
City Cost Index	10 %	\$1,066
GRAND TOTAL		\$14,917

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture		 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1714 18th St, Suite 100 San Francisco, CA 94133	
STREET LOCATION South Bay Front Between Turquoise Ave and Collins Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:

Item	Location	Description
1	8' East of Turquoise Avenue	Storm drain junction box, severe spalling
2	13' East of Turquoise Avenue	Construction joint, sealant waterside and landside cracked and split
3	60' East of Turquoise Avenue	Waterside, longitudinal crack through top of cap 60" long x 6" down from top
4	118' East of Turquoise Avenue	Construction joint, sealant waterside and landside cracked and split
5	124' East of Turquoise Avenue	Pullbox, cracking around box, previous repairs appear to be in good shape
6	214' East of Turquoise Avenue	Pullbox, spall on waterside only, 48" long x 7" high x 7" deep
7	235' East of Turquoise Avenue	Construction joint, sealant waterside and landside cracked and split
8	322' East of Turquoise Avenue	Waterside, lightpole at Collins Avenue, spalled at top of cap, landside spall behind plaque



South Bay Front, 8' East of Turquoise



South Bay Front, 13' East of Turquoise



South Bay Front, 118' East of Turquoise

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES, ENGINEERING & ARCHITECTURE 204/840-2219 204/840-2218
STREET LOCATION South Bay Front Between Turquoise Ave and Collins Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:



South Bay Front, 60' East of Turquoise



South Bay Front, 60' East of Turquoise



South Bay Front, 118' East of Turquoise



South Bay Front, 118' East of Turquoise



South Bay Front, 124' East of Turquoise



South Bay Front, 124' East of Turquoise

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 852-2100 11111 Main St., Suite 100
STREET LOCATION South Bay Front Between Turquoise Ave and Collins Ave	INSPECTOR: ASSISTANT	CTM	INSPECTION DATE: DEC 21, 2004	



South Bay Front, 124' East of Turquoise



South Bay Front, 214' East of Turquoise



South Bay Front, 214' East of Turquoise



South Bay Front, 235' East of Turquoise



South Bay Front, 235' East of Turquoise



South Bay Front, 322' East of Turquoise

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (314) 883-2632 40560701.10/04.11			
STREET LOCATION South Bay Front Between Turquoise Ave and Collins Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004		REVISION:			
Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	8' East of Turquoise Avenue, spall repair	10	SF					\$70.00	\$700
2	13' East of Turquoise Avenue, sealant repair	6	LF					\$25.00	\$150
3	60' East of Turquoise Avenue, crack injection	6	LF					\$70.00	\$420
4	118' East of Turquoise Avenue, sealant repair	6	LF					\$25.00	\$150
5	124' East of Turquoise Avenue, crack injection	3	LF					\$70.00	\$210
6	214' East of Turquoise Avenue, spall repair	3	SF					\$70.00	\$210
7	235' East of Turquoise Avenue, sealant repair	6	LF					\$25.00	\$150
8	322' East of Turquoise Avenue, spall repair	6	SF					\$70.00	\$420

Subtotal		\$2,410
Contingency	20 %	\$482
Contractor OH & P	10 %	\$241
City Cost Index	10 %	\$241
GRAND TOTAL		\$3,374

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture		 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1110 4th Street, Suite 200 San Francisco, CA 94107 (415) 441-1111	
STREET LOCATION South Bay Front Between Collins Ave and Ruby Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:

Item	Location	Description
1	29' East of Collins Avenue	Construction joint, sealant in good shape all around
2	29' East of Collins Avenue	Landside, spall at top of cap 14" long x 3" high x 2" deep
3	110' East of Collins Avenue	Pullbox, waterside spall 36" x 6" x 3", landside spall 24" long x 8" high x 7" deep
4	146' East of Collins Avenue	Construction joint, landside and top missing sealant, waterside sealant cracked and split
5	219' East of Collins Avenue	Waterside, Ruby Avenue lightpole, spall and "hollow sounding" 24" long x 5" high x 3" deep



South Bay Front, 29' East of Collins



South Bay Front, 29' East of Collins



South Bay Front, 110' East of Collins

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1714 NEW RITE AUSTIN, TEXAS 78701
STREET LOCATION South Bay Front Between Collins Ave and Ruby Ave	INSPECTOR ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:



South Bay Front, 110' East of Collins



South Bay Front, 146' East of Collins



South Bay Front, 146' East of Collins



South Bay Front, 219' East of Collins

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES INTERIOR & ARCHITECTURE 2714 38th St. #202 SAN FRANCISCO, CA 94114			
STREET LOCATION South Bay Front Between Collins Ave and Ruby Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004		REVISION:			
Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
2	29' East of Collins Avenue, crack injection	4	LF					\$70.00	\$280
3	110' East of Collins Avenue, spall repair	6	SF					\$70.00	\$420
4	146' East of Collins Avenue, sealant repair	6	LF					\$25.00	\$150
5	219' East of Collins Avenue, spall repair	6	SF					\$70.00	\$420

Subtotal		\$1,270
Contingency	10 %	\$127
Contractor OH & P	10 %	\$127
City Cost Index	10 %	\$127
GRAND TOTAL		\$1,651

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 2001-4-21000233 2001-4-21000233 714-608-4011 10/10/04 8:45:10
STREET LOCATION South Bay Front Between Ruby Ave and Diamond Ave	INSPECTOR: ASSISTANT:	QTM	INSPECTION DATE: DEC 21, 2004	REVISION:

Item Location	Description
1 43' East of Ruby Avenue	Construction joint, landside and top missing sealant, waterside sealant cracked and split
2 110' East of Ruby Avenue	Pullbox, spall on landside and waterside 24" long x 6" high x 6" deep
3 160' East of Ruby Avenue	Construction joint, landside and top missing sealant, waterside sealant cracked and split
4 219' East of Ruby Avenue	Waterside, lightpole: spall at top of cap 24" long x 5" high x 3" deep over previous repair



South Bay Front, 43' East of Ruby



South Bay Front, 43' East of Ruby



South Bay Front, 110' East of Ruby

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES INSURANCE & ARCHITECTURE (310) 555-2072 11111 WILSON BLVD. #401 LA	
STREET LOCATION South Bay Front Between Ruby Ave and Diamond Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004		REVISION:	

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	43' East of Ruby Avenue, sealant repair	6	LF					\$25.00	\$150
2	110' East of Ruby Avenue, spall repair	4	SF					\$70.00	\$280
3	160' East of Ruby Avenue, sealant repair	6	LF					\$25.00	\$150
4	219' East of Ruby Avenue, spall repair	3	SF					\$70.00	\$210

Subtotal				\$790
Contingency	20 %			\$158
Contractor OH & P	10 %			\$79
City Cost Index	10 %			\$79
GRAND TOTAL				\$1,106

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture		 CASH & ASSOCIATES 10000 BALBOA AVENUE SUITE 100 BALBOA BEACH, CA 92008-3827 (619) 435-1212	
STREET LOCATION South Bay Front Between Diamond Ave and Sapphire Ave		INSPECTOR: ASSISTANT	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:

Item	Location	Description
1	57' East of Diamond Avenue	Construction joint, waterside sealant obscured by pier, landside sealant cracked
2	109' East of Diamond Avenue	Pulldown, waterside spill 24" long x 5" high x 3" wide landside "hollow sound"
3	173' East of Diamond Avenue	Construction joint, top and landside sealant in good shape, waterside sealant missing



South Bay Front 57' East of Diamond



South Bay Front 110' East of Diamond



South Bay Front 110' East of Diamond



South Bay Front 173' East of Diamond



South Bay Front 173' East of Diamond

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 17743550-2029 HUNTINGTON BEACH, CA			
STREET LOCATION South Bay Front Between Diamond Ave and Sapphire Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:				
Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	57' East of Diamond Avenue, sealant repair	3	LF					\$25.00	\$75
2	109' East of Diamond Avenue, spill repair	3	SF					\$70.00	\$210
3	173' East of Diamond Avenue, sealant repair	3	LF					\$25.00	\$75

Subtotal			\$360
Contingency	20 %		\$72
Contractor OH & P	10 %		\$36
City Cost Index	10 %		\$36
GRAND TOTAL			\$504

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture		 Over 40 years of experience Serving the community with integrity and excellence	
STREET LOCATION South Bay Front Between Sapphire Ave and Coral Ave		INSPECTOR ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:

Item	Location	Description
1	16' East of Sapphire Avenue	Waterside, spall at bottom of cap 48" long x 7" tall x 4" deep
2	71' East of Sapphire Avenue	Construction joint, landside sealant in good condition, waterside sealant cracked and split
3	110' East of Sapphire Avenue	Pullbox, spalled on landside (30" long x 5" high x 6" wide) and waterside (30" long x 12" high x 9" wide)
4	188' East of Sapphire Avenue	Construction joint, landside sealant missing, waterside sealant cracked and split
5	210' East of Sapphire Avenue	Waterside, spall at bottom of cap 36" long x 6" high x 1" deep
6	206' East of Sapphire Avenue	Waterside, spall at bottom of cap over previous repair, 18" long x 6" high x 1/2" deep
7	General comments	Shrinkage cracks at 10' on center, transverse through cap, typical



South Bay Front, 16' East of Sapphire



South Bay Front, 71' East of Sapphire



South Bay Front, 71' East of Sapphire

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1700 S. KALANAN AVE. HONOLULU, HI 96815
STREET LOCATION South Bay Front Between Sapphire Ave and Coral Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	



South Bay Front, 110' East of Sapphire



South Bay Front, 116' East of Sapphire



South Bay Front, 188' East of Sapphire



South Bay Front, 188' East of Sapphire



South Bay Front, 206' East of Sapphire



South Bay Front, 210' East of Sapphire

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Sapphire Ave and Coral Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:



Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	16' East of Sapphire Avenue, crack injection	4	LF					\$70.00	\$280
2	71' East of Sapphire Avenue, sealant repair	4	LF					\$25.00	\$100
3	110' East of Sapphire Avenue, spall repair	4	SF					\$70.00	\$280
4	188' East of Sapphire Avenue, sealant repair	6	LF					\$25.00	\$150
5	210' East of Sapphire Avenue, crack injection	3	LF					\$70.00	\$210
6	206' East of Sapphire Avenue, crack injection	2	LF					\$70.00	\$140
7	General, transverse cracks at 10' o.c. minor	130	LF					\$70.00	\$9,100

Subtotal				\$10,260
Contingency	20 %			\$2,052
Contractor OH & P	10 %			\$1,026
City Cost Index	10 %			\$1,026
GRAND TOTAL				\$14,364

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Coral Ave and Apolena Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	

Item	Location	Description
1	91' East of Coral Avenue	Construction joint, waterside sealant is cracked and split, landside sealant is missing
2	116' East of Coral Avenue	Pullbox, spall and landside and waterside at top of cap, 24" long x 5" high x 6" wide
3	207' East of Coral Avenue	Construction joint, waterside sealant is cracked and split, landside sealant is missing
4	General comments	Shrinkage cracks at 10'-20' on center transverse through cap, typical

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 JOHN A. CASH/CA/CT 1113885 - 1877 10/10/2008 8:00-10
STREET LOCATION South Bay Front Between Coral Ave and Apolena Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:



South Bay Front, 91' East of Coral



South Bay Front, 91' East of Coral



South Bay Front, 116' East of Coral



South Bay Front, 116' East of Coral



South Bay Front, 207' East of Coral



South Bay Front, 207' East of Coral

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Apolena Ave and Amethyst Ave	INSPECTOR: ASSISTANT	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:

Item	Location	Description
1	44' East of Apolena Avenue	Waterside, crack at bottom of cap 132" long
2	56' East of Apolena Avenue	Waterside, crack at bottom of cap 36" long
3	76' East of Apolena Avenue	Waterside, crack at bottom of cap 48" long
4	100' East of Apolena Avenue	Construction joint, waterside sealant split, landside and top sealant missing
5	110' East of Apolena Avenue	Pullbox, waterside and landside spall 30" long x 7" high x 6" wide
6	216' East of Apolena Avenue	Construction joint, waterside sealant split, landside and top sealant missing
7	General comments	Shrinkage cracks at 10'-20' on center transverse through cap, top 12" of cap typical



South Bay Front, 44' East of Apolena



South Bay Front, 44' East of Apolena



South Bay Front, 56' East of Apolena

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 Cash & Associates 114 West 10th St San Diego, CA 92101
STREET LOCATION South Bay Front Between Apolena Ave and Amethyst Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:



South Bay Front, 76' East of Apolena



South Bay Front, 100' East of Apolena



South Bay Front, 100' East of Apolena



South Bay Front, 110' East of Apolena



South Bay Front, 110' East of Apolena



South Bay Front, 216' East of Apolena

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 17001 E. 15TH AVE SUITE 200 DENVER, CO 80202
STREET LOCATION South Bay Front Between Apolena Ave and Amethyst Ave	INSPECTOR: ASSISTANT:	CDM	INSPECTION DATE: DEC 21, 2004	REVISION:



South Bay Front, 216' East of Apolena

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION		INSPECTION DATE: DEC 21, 2004			
South Bay Front		INSPECTOR: CTM		REVISION:	
Between Apolena Ave and Amethyst Ave		ASSISTANT:			



Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	44' East of Apolena Avenue, crack injection	11	LF					\$70.00	\$770
2	56' East of Apolena Avenue, crack injection	3	LF					\$70.00	\$210
3	76' East of Apolena Avenue, crack injection	4	LF					\$70.00	\$280
4	100' East of Apolena Avenue, sealant repair	6	LF					\$25.00	\$150
5	110' East of Apolena Avenue, spall repair	4	SF					\$70.00	\$280
6	216' East of Apolena Avenue, sealant repair	6	LF					\$25.00	\$150
7	General, transverse shrinkage cracks, minor	80	LF					\$70.00	\$5,600

Subtotal			\$7,440
Contingency	20 %		\$1,488
Contractor OH & P	10 %		\$744
City Cost Index	10 %		\$744
GRAND TOTAL			\$10,416

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Amethyst Ave and Onyx Ave	INSPECTOR: ASSISTANT:	GTM	INSPECTION DATE: DEC 21, 2004	REVISION:

Item Location

Item Location	Description
1 31' East of Amethyst Avenue	Waterside, crack at bottom of cap, 6" long
2 46' East of Amethyst Avenue	Waterside, crack at bottom of cap, 36" long
3 111' East of Amethyst Avenue	Pullbox, spall on waterside 36" long x 6" high x 4" wide, spall on landside 24" long x 6" high x 4" wide
4 111' East of Amethyst Avenue	Construction joint, waterside sealant split and cracked, landside and top sealant missing
5 198' East of Amethyst Avenue	Waterside, crack at bottom of cap 108" long
6 218' East of Amethyst Avenue	Waterside, crack at bottom of cap, 48" long



South Bay Front, 31' East of Amethyst



South Bay Front, 46' East of Amethyst



South Bay Front, 111' East of Amethyst

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 2400 N. WINDYBUSH HAWAII, HI 96706 (808) 941-1234 www.cash-hi.com
STREET LOCATION South Bay Front Between Amethyst Ave and Onyx Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	



South Bay Front, 111' East of Amethyst



South Bay Front, 198' East of Amethyst



South Bay Front, 218' East of Amethyst

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (174)181-2072 ANYTOWN TEXAS, TX	
STREET LOCATION		INSPECTOR: CTM		INSPECTION DATE: DEC 21, 2004		REVISION:	
Balboa Island Bulkhead Inspection		ASSISTANT:					
South Bay Front							
Between Amethyst Ave and Onyx Ave							

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	31' East of Amethyst Avenue, crack injection	6	LF					\$70.00	\$420
2	46' East of Amethyst Avenue, crack injection	3	LF					\$70.00	\$210
3	111' East of Amethyst Avenue, spall repair	5	SF					\$70.00	\$350
4	111' East of Amethyst Avenue, sealant repair	6	LF					\$25.00	\$150
5	198' East of Amethyst Avenue, crack injection	9	LF					\$70.00	\$630
6	218' East of Amethyst Avenue, crack injection	4	LF					\$70.00	\$280

Subtotal				\$2,040
Contingency	20 %			\$408
Contractor OH & P	10 %			\$204
City Cost Index	10 %			\$204
GRAND TOTAL				\$2,856

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Onyx Ave and Marine Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC-21, 2004	REVISION:



Item	Location	Description
1	10' East of Onyx Avenue	Construction joint, waterside sealant cracked and split, landside and top sealant missing
2	21' East of Onyx Avenue	Waterside, crack at bottom of cap 48" long
3	109' east of Onyx Avenue	Pullbox in good condition
4	116' East of Onyx Avenue	Waterside, crack at bottom of cap 72" long
5	126' East of Onyx Avenue	Construction joint, waterside sealant plyable in good shape, landside sealant missing
6	General comments	Shrinkage cracks at 10'-20' on center transverse through cap, top 12" of cap typical



South Bay Front, 10' East of Onyx



South Bay Front, 10' East of Onyx



South Bay Front, 21' East of Onyx

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES 1714 E. 10th St. Suite 100 San Diego, CA 92101 (619) 584-8877 www.cashandassociates.com
STREET LOCATION South Bay Front Between Onyx Ave and Mainne Ave	INSPECTOR: ASSISTANT	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:



South Bay Front, 109' East of Onyx



South Bay Front, 109' East of Onyx



South Bay Front, 116' East of Onyx



South Bay Front, 126' East of Onyx



South Bay Front, 126' East of Onyx

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1714 9855-2072 N. SHERIDAN BLVD., CA	
STREET LOCATION South Bay Front Between Onyx Ave and Marine Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:		

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	10' East of Onyx Avenue, sealant repair	6	LF					\$25.00	\$150
2	21' East of Onyx Avenue, crack injection	4	LF					\$70.00	\$280
4	116' East of Onyx Avenue, crack injection	6	LF					\$70.00	\$420
5	126' East of Onyx Avenue, sealant repair	6	LF					\$25.00	\$150
6	General, transverse cracking through cap, minor	80	LF					\$70.00	\$5,600

Subtotal			\$6,600
Contingency	20 %		\$1,320
Contractor OH & P	10 %		\$660
City Cost Index	10 %		\$660
GRAND TOTAL			\$9,240

ACTIVITY: Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 Cash & Associates 11400 Judd Rd. San Diego, CA 92121
STREET LOCATION: South Bay Front Between Marine Ave and Grand Canal West	INSPECTOR: ASSISTANT:	GTM	INSPECTION DATE: DEC 21, 2004	REVISION:

Item	Location	Description
1	24' East of Marine Avenue	Construction joint, waterside sealant cracked and split, landside sealant missing
2	58' East of Marine Avenue	Waterside, crack at bottom of cap 48" long x 9" high x 3" deep
3	83' East of Marine Avenue	Waterside, crack at bottom of cap 48" long x 9" high x 3" deep
4	109' East of Marine Avenue	Pullbox, previous repairs to waterside and landside spalls are "hollow" 24" long x 6" high x 7" wide
5	116' East of Marine Avenue	Waterside, crack at bottom of cap, 36" long
6	130' East of Marine Avenue	Waterside, spalled at bottom of cap 156" long x 12" high x 12" deep
7	General comments	Shrinkage cracks at 10'-20' on center transverse through cap, top 12" of cap typical



South Bay Front, 24' East of Marine



South Bay Front, 24' East of Marine



South Bay Front, 58' East of Marine

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Marine Ave and Grand Canal West	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:



South Bay Front, 83' East of Marine



South Bay Front, 109' East of Marine



South Bay Front, 109' East of Marine



South Bay Front, 116' East of Marine



South Bay Front, 130' East of Marine



South Bay Front, 130' East of Marine

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 11400-10200 SAN DIEGO, CA 92121
STREET LOCATION South Bay Front Between Marine Ave and Grand Canal West	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	



South Bay Front, 130' East of Marine

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 850-2072 4010 KINGS BLVD., #404, LA	
STREET LOCATION South Bay Front Between Marine Ave and Grand Canal West		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 21, 2004	REVISION:		

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	24' East of Marine Avenue, sealant repair	6	LF					\$25.00	\$150
2	58' East of Marine Avenue, crack injection	4	LF					\$70.00	\$280
3	83' East of Marine Avenue, crack injection	4	LF					\$70.00	\$280
4	109' East of Marine Avenue, spall repair	6	LF					\$70.00	\$420
5	116' East of Marine Avenue, crack injection	3	LF					\$70.00	\$210
6	130' East of Marine Avenue, spall repair	13	SF					\$70.00	\$910
7	General, shrinkage cracks, minor	80	LF					\$70.00	\$5,600

Subtotal			\$7,850
Contingency	20 %		\$1,570
Contractor OH & P	10 %		\$785
City Cost Index	10 %		\$785
GRAND TOTAL			\$10,990

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture		 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 895-7013 100 N. COLTON BLVD., SUITE 100
STREET LOCATION South Bay Front Between Grand Canal and Abalone Ave		INSPECTOR: ASSISTANT:	CTM INSPECTION DATE: Dec 27, 2004 REVISION:	

Item	Location	Description
1	Corner	Waterside, cracking on face of cap
2	11' East of Grand Canal East	Waterside, spall at bottom of cap, 48" long x 5" high
3	11' East of Grand Canal East	Construction joint, sealant waterside and landside cracked and split
4	24' East of Grand Canal East	Waterside, cracking of surface of cap, 2'-3' on center
5	103' East of Grand Canal East	Pullbox, landside cracking of top of cap, 36" long
6	138' East of Grand Canal East	Waterside, cracking through cap 12" below top of cap, 30" long vertical crack through cap 12" long
7	187' East of Grand Canal East	Construction joint, sealant waterside and landside cracked and split

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 11160 - 12TH SAN DIEGO, CALIF. 92121
STREET LOCATION South Bay Front Between Grand Canal and Abalone Ave	INSPECTOR: ASSISTANT	CTM	INSPECTION DATE: Dec 27, 2004	REVISION:



South Bay Front, 3' East of Grand Canal



South Bay Front, 11' East of Grand Canal



South Bay Front, 11' East of Grand Canal



South Bay Front, 24' East of Grand Canal



South Bay Front, 103' East of Grand Canal



South Bay Front, 103' East of Grand Canal

CASH & ASSOCIATES  CASH & ASSOCIATES INSPECTION & MAINTENANCE (714) 951-1010 www.cashinspections.com	
Project Name: _____	Inspector: _____
Address: _____	City: _____ State: _____ Zip: _____
Between Grand Canal and Abalone Ave	South Bay Front



South Bay Front, 103' East of Grand Canal




South Bay Front, 138' East of Grand Canal



South Bay Front, 187' East of Grand Canal



South Bay Front, 187' East of Grand Canal

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture				
STREET LOCATION South Bay Front Between Abalone Ave and Crystal Ave	INSPECTOR ASSISTANT	CTM	INSPECTION DATE Dec 27, 2004	REVISION:	

Item	Location	Description
1	30' East of Abalone Avenue	Crack through cap, 12" high x 1/4" wide
2	54' East of Abalone Avenue	Crack through cap, 12" high x 1/4" wide
3	64' East of Abalone Avenue	Crack through cap, 12" high x 1/4" wide
4	74' East of Abalone Avenue	Crack through cap, 12" high x 1/4" wide
5	93' East of Abalone Avenue	Construction Joint, sealant split and cracked both sides
6	102' East of Abalone Avenue	Previously repaired crack though cap still moving, cracked
7	110' East of Abalone Avenue	Pullbox, cracked though cap top 12" at east end of pullbox and horizontally through cap
8	152' East of Abalone Avenue	Crack through cap, 12" high x 1/4" wide
9	159' East of Abalone Avenue	Crack through cap, 12" high x 1/4" wide
10	183' East of Abalone Avenue	Crack through cap, 12" high x 1/16" wide
11	190' East of Abalone Avenue	Crack through cap, 12" high x 1/16" wide
12	199' East of Abalone Avenue	Crack through cap, 12" high x 1/8" wide
13	201' East of Abalone Avenue	Construction joint, sealant split and cracked both sides
14	201' East of Abalone Avenue	Waterside, spall 18" long x 7" high x 7" deep



South Bay Front, 30' East of Abalone



South Bay Front, 30' East of Abalone



South Bay Front, 54' East of Abalone

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES, INC. 1141111-1111 1111111-1111
	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: Dec 27, 2004	
STREET LOCATION South Bay Front Between Abalone Ave and Crystal Ave				



South Bay Front, 64' East of Abalone



South Bay Front, 74' East of Abalone



South Bay Front, 74' East of Abalone



South Bay Front, 93' East of Abalone



South Bay Front, 93' East of Abalone



South Bay Front, 102' East of Abalone

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 2004 S. PUEBLO AVE SAN ANTONIO, TEXAS 78204 (214) 594-1000 FAX (214) 594-1001
STREET LOCATION South Bay Front Between Abalone Ave and Crystal Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: Dec 27, 2004	REVISION:



South Bay Front, 102' East of Abalone



South Bay Front, 110' East of Abalone



South Bay Front, 110' East of Abalone

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Abalone Ave and Crystal Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: Dec 27, 2004	REVISION:



South Bay Front, 110' East of Abalone



South Bay Front, 110' East of Abalone



South Bay Front, 152' East of Abalone

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Abalone Ave and Crystal Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: Dec 27, 2004	REVISION:



South Bay Front, 152' East of Abalone



South Bay Front, 159' East of Abalone



South Bay Front, 159' East of Abalone

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 11111111-1111 11111111-1111
STREET LOCATION South Bay Front Between Abalone Ave and Crystal Ave	INSPECTOR: ASSISTANT:	QTM	INSPECTION DATE: Dec 27, 2004	REVISION:



South Bay Front, 175' East of Abalone



South Bay Front, 175' East of Abalone



South Bay Front, 183' East of Abalone

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 2741805-3010 BALBOA ISLAND, HI	
STREET LOCATION South Bay Front Between Abalone Ave and Crystal Ave	INSPECTOR: ASSISTANT:	GTM	INSPECTION DATE: Dec 27, 2004		REVISION:



South Bay Front, 183' East of Abalone



South Bay Front, 190' East of Abalone



South Bay Front, 190' East of Abalone

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture				CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 995-2072 NEWPORT BEACH, CA			
STREET LOCATION		INSPECTOR:		CTM	INSPECTION DATE: Dec 27, 2004		REVISION:		
South Bay Front Between Abalone Ave and Crystal Ave		ASSISTANT:							
Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	30' East of Abalone Avenue, crack injection	3	LF					\$70.00	\$210
2	54' East of Abalone Avenue, crack injection	3	LF					\$70.00	\$210
3	64' East of Abalone Avenue, crack injection	3	LF					\$70.00	\$210
4	74' East of Abalone Avenue, crack injection	3	LF					\$70.00	\$210
5	93' East of Abalone Avenue, sealant repair	6	LF					\$25.00	\$150
6	102' East of Abalone Avenue, crack injection	6	LF					\$70.00	\$420
7	110' East of Abalone Avenue, crack injection	5	LF					\$70.00	\$350
8	152' East of Abalone Avenue, crack injection	3	LF					\$70.00	\$210
9	159' East of Abalone Avenue, crack injection	3	LF					\$70.00	\$210
10	183' East of Abalone Avenue, crack injection	3	LF					\$70.00	\$210
11	190' East of Abalone Avenue, crack injection	3	LF					\$70.00	\$210
12	199' East of Abalone Avenue, crack injection	3	LF					\$70.00	\$210
13	201' East of Abalone Avenue, sealant repair	6	LF					\$25.00	\$150
14	201' East of Abalone Avenue, spall repair	2	SF					\$70.00	\$140

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 JOHN A. CASH, P.E. 11112001-1411 1000 10th Street, Suite 100
STREET LOCATION South Bay Front Between Crystal Ave and Jade Ave	INSPECTOR: ASSISTANT	GTM	INSPECTION DATE: Dec 27, 2004	REVISION:

Item	Location	Description
1	20' East of Crystal Avenue	Crack through cap at 2'-5" on center, top 12" of cap
2	23' East of Crystal Avenue	Crack through cap at 2'-5" on center, top 12" of cap
3	25' East of Crystal Avenue	Crack through cap at 2'-5" on center, top 12" of cap
4	30' East of Crystal Avenue	Waterside, spall repair loose at lower edges, 48" long x 7" high
5	94' East of Crystal Avenue	Waterside, crack at bottom of cap 30" long
6	106' East of Crystal Avenue	Construction joint, sealant on waterside and landside cracked and split
7	110' East of Crystal Avenue	Pullbox, landside horizontal crack 12" down from top 36" long
8	116' - 190' East of Crystal Avenue	Crack through cap @ 2'-5" o.c., top 12" of cap
9	195' East of Crystal Avenue	Waterside, crack at bottom of cap, 96" long
10	220' East of Crystal Avenue (at Jade Avenue)	Waterside, crack at bottom of wall, 60" long



South Bay Front, 20' East of Crystal



South Bay Front, 20' East of Crystal



South Bay Front, 30' East of Crystal

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			STREET LOCATION South Bay Front Between Crystal Ave and Jade Ave
INSPECTOR: CTM	INSPECTION DATE: Dec 27, 2004	REVISION:		
 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1111 10th St, Suite 100 San Francisco, CA 94103				



South Bay Front, 94' East of Crystal



South Bay Front, 106' East of Crystal



South Bay Front, 106' East of Crystal



South Bay Front, 110' East of Crystal



South Bay Front, 110' East of Crystal



South Bay Front, 110' East of Crystal

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Crystal Ave and Jade Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: Dec 27, 2004	



South Bay Front, 195' East of Crystal



South Bay Front, 220' East of Crystal

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture				 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1214 JONES BLVD. SAN ANTONIO, TEXAS 78201-2424	
STREET LOCATION South Bay Front Between Crystal Ave and Jade Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: Dec 27, 2004		REVISION:	

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
1	Transverse cracks at 5' o.c., shrinkage cracks	130	LF					\$70.00	\$9,100
4	30' East of Crystal Avenue, crack injection	4	LF					\$70.00	\$280
5	94' East of Crystal Avenue, crack injection	3	LF					\$70.00	\$210
6	106' East of Crystal Avenue, sealant repair	6	LF					\$25.00	\$150
7	110' East of Crystal Avenue, crack injection	3	LF					\$70.00	\$210
9	195' East of Crystal Avenue, crack injection	8	LF					\$70.00	\$560
10	220' East of Crystal Avenue, crack injection	5	LF					\$70.00	\$350

Subtotal				\$10,860
Contingency	10 %			\$1,086
Contractor OH & P	10 %			\$1,086
City Cost Index	10 %			\$1,086
GRAND TOTAL				\$14,118

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 895-1072 1141 NORTH BAY AVE., CA
STREET LOCATION South Bay Front Between Jade Ave and East Bay Front	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: Dec 27, 2004	
REVISION:				

Item Location	Description
1 4' East of Jade Avenue	Construction joint, waterside cracked and split
2 11' East of Jade Avenue	Waterside, crack at bottom of cap 180" long
3 37' East of Jade Avenue	Waterside, crack at bottom of cap 96" long
4 51' East of Jade Avenue	Waterside, spall at bottom of cap 72" long x 12" high x 6" long
5 61' East of Jade Avenue	Waterside, crack at bottom of cap 72" long
6 71' East of Jade Avenue	Waterside, crack at bottom of cap 72" long
7 84' East of Jade Avenue	Waterside, crack at bottom of cap 48" long
8 96' East of Jade Avenue	Waterside, crack at bottom of cap 120" long
9 119' East of Jade Avenue	Construction joint, waterside cracked and split
10 119' East of Jade Avenue	Waterside, crack at bottom of cap 12" long
11 132' East of Jade Avenue	Waterside, crack at bottom of cap 72" long
12 177' East of Jade Avenue	Waterside, crack at bottom of cap 60" long
13 187' East of Jade Avenue	Waterside, crack at bottom of cap 36" long
14 212' East of Jade Avenue	Waterside, crack at bottom of cap 60" long
15 235' East of Jade Avenue	Construction joint, sealant split and cracked on waterside, landside in good condition
16 235' East of Jade Avenue	Landside, 72" long crack at lower step
17 235' East of Jade Avenue	Waterside, previously repaired crack and spall appears to be holding, condition questionable Concrete is pushed out of plain of wall and could pose future problem

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION South Bay Front Between Jade Ave and East Bay Front	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: Dec 27, 2004	REVISION:



South Bay Front, 4' East of Jade



South Bay Front, 4' East of Jade



South Bay Front 11' East of Jade



South Bay Front, 37' East of Jade



South Bay Front, 51' East of Jade



South Bay Front, 61' East of Jade

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1111 10th Ave, Suite 200 San Francisco, CA 94133 (415) 440-1010
STREET LOCATION South Bay Front Between Jade Ave and East Bay Front	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: Dec 27, 2004	REVISION:



South Bay Front, 71' East of Jade



South Bay Front, 96' East of Jade



South Bay Front, 119' East of Jade



South Bay Front, 119' East of Jade



South Bay Front, 132' East of Jade



South Bay Front, 152' East of Jade

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1111 10th Street, Suite 200 San Francisco, CA 94103 Tel: 415.774.1111 Fax: 415.774.1112
STREET LOCATION South Bay Front Between Jade Ave and East Bay Front	INSPECTOR: GTM	INSPECTION DATE: Dec 27, 2004	REVISION:	



South Bay Front, 177' East of Jade



South Bay Front, 187' East of Jade



South Bay Front, 212' East of Jade



South Bay Front, 235' East of Jade



South Bay Front, 235' East of Jade



South Bay Front, 235' East of Jade

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 936-2022 100 WILSON BLVD, SUITE 200
STREET LOCATION South Bay Front Between Jade Ave and East Bay Front	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: Dec 27, 2004	REVISION:



South Bay Front, 235' East of Jade

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture		
	 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 992-2002 HUNTINGTON BEACH, CA		
STREET LOCATION Grand Canal West Between North Bay Front and Balboa Ave	INSPECTOR:	CTM	INSPECTION DATE: January 21, 2005
	ASSISTANT:		REVISION:

Item	Location	Description
1	0' North of Balboa	Reference point, centerline of Balboa Avenue
2	15' North of Balboa Avenue	Waterside, crack on face of pile
3	41' North of Balboa Avenue	Construction joint at top of cap only, sealant cracked and split
4	47' North of Balboa Avenue	Construction joint at lower step only, sealant cracked and split
5	70' North of Balboa Avenue	Waterside, crack on sides of pile
6	81' North of Balboa Avenue	Waterside, crack on south side of pile
7	103' North of Balboa Avenue	Waterside, crack on face and south side of pile
8	114' North of Balboa Avenue	Waterside, crack on face of pile
9	235' North of Balboa Avenue	Waterside, crack on face of pile
10	235' North of Balboa Avenue	Construction joint, sealant split and crack
11	290' North of Balboa Avenue	Waterside, crack on face and sides of pile
12	329' North of Balboa Avenue	Waterside, 60" long crack at bottom of cap
13	356' North of Balboa Avenue	Waterside, crack and spalled face of pile
14	362' North of Balboa Avenue	Waterside, crack at midline of cap, 96" long
15	400' North of Balboa Avenue	Waterside, crack on face of pile
16	412' North of Balboa Avenue	Waterside, crack on sides of pile
17	422' North of Balboa Avenue	Waterside, crack on south side of pile
18	435' North of Balboa Avenue	Construction joint, sealant split and cracked on land side, waterside obscured by dock
19	444' North of Balboa Avenue	Waterside, crack on sides of pile
20	467' North of Balboa Avenue	Waterside, crack on sides of pile
21	478' North of Balboa Avenue	Waterside, crack on sides of pile
22	490' North of Balboa Avenue	Waterside, crack on north side of pile
24	500' North of Balboa Avenue	Waterside, crack on face and sides of pile
25	500' North of Balboa Avenue	Waterside, wall spall, 2 square feet
26	511' North of Balboa Avenue	Waterside, crack on face and sides of pile
27	534' North of Balboa Avenue	Waterside, crack on face and sides of pile
28	545' North of Balboa Avenue	Waterside, crack on south side of pile
29	556' North of Balboa Avenue	Waterside, crack on sides of pile
30	567' North of Balboa Avenue	Waterside, crack on sides of pile
31	567' North of Balboa Avenue	Waterside, crack at middle of cap, 60" long
32	578' North of Balboa Avenue	Waterside, spall at mudline of pile
33	578' North of Balboa Avenue	Waterside, crack at middle of cap, 96" long
34	589' North of Balboa Avenue	Waterside, crack on face and sides of pile, obscured by rocks
35	597' North of Balboa Avenue	Construction joint, sealant split and crack

Continued onto next page

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 2000 N. 41ST STREET SUITE 100 LOS ANGELES, CA 90018 (310) 440-4272 FAX (310) 440-4273	
STREET LOCATION Grand Canal West Between North Bay Front and Balboa Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005		REVISION:

Reference point, outside corner of cap at North Bay Front
 Waterside, underside of cap has spalls, cracks and loose material
 Top of cap "hollow spalled" sounds. Little of no signs of spalling, high potential for problems

36 801' North of Balboa Avenue
 37 general note
 38 Address 0' - 120'



15' North of Balboa Avenue



41' North of Balboa Avenue



41' North of Balboa Avenue

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE CTA 0000-0000 000000 0000 00
STREET LOCATION Grand Canal West Between North Bay Front and Balboa Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005	REVISION:



47' North of Balboa Avenue



70' North of Balboa Avenue



81' North of Balboa Avenue

ACTIVITY

Balboa Island Bulkhead Inspection

CASH & ASSOCIATES
Engineering and Architecture

STREET LOCATION

Grand Canal West
Between North Bay Front and Balboa Ave

INSPECTOR:
ASSISTANT:

CTM

INSPECTION DATE: January 21, 2005

REVISION:



CASH & ASSOCIATES
ENGINEERING & ARCHITECTURE
11111111-1111
ALBUQUERQUE, NM 87106



103' North of Balboa Avenue



114' North of Balboa Avenue



235' North of Balboa Avenue



235' North of Balboa Avenue



290' North of Balboa Avenue



325' North of Balboa Avenue

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 JAMES A. CASH, P.E. License # 17446-0001 License # 17446-0002
STREET LOCATION Grand Canal West Between North Bay Front and Balboa Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005 REVISION:	



356' North of Balboa Avenue



362' North of Balboa Avenue



400' North of Balboa Avenue



412' North of Balboa Avenue



422' North of Balboa Avenue



435' North of Balboa Avenue

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between North Bay Front and Balboa Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005	REVISION:



444' North of Balboa Avenue



457' North of Balboa Avenue



476' North of Balboa Avenue



490' North of Balboa Avenue



500' North of Balboa Avenue



511' North of Balboa Avenue

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between North Bay Front and Balboa Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005	REVISION



534' North of Balboa Avenue



545' North of Balboa Avenue



556' North of Balboa Avenue



567' North of Balboa Avenue



578' North of Balboa Avenue



589' North of Balboa Avenue

ACTIVITY: Balboa Island Bulkhead Inspection	CASH & ASSOCIATES ENGINEERING AND ARCHITECTURE			
STREET LOCATION: Grand Canal West Between North Bay Front and Balboa Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005	REVISION:



597' North of Balboa Avenue



597' North of Balboa Avenue

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture		 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 954-2077 IRVINE, CALIF. 92614	
STREET LOCATION Grand Canal West Between North Bay Front and Balboa Ave		INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005	REVISION:

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
2	15' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
3	41' North of Balboa Avenue, sealant repair	2	SF					\$70.00	\$140
4	47' North of Balboa Avenue, sealant repair	3	SF					\$70.00	\$210
5	70' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
6	81' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
7	103' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
8	114' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
9	235' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
10	235' North of Balboa Avenue, sealant repair	7	LF					\$25.00	\$175
11	290' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
12	329' North of Balboa Avenue, crack injection	5	LF					\$70.00	\$350
13	356' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
14	362' North of Balboa Avenue, crack injection	8	LF					\$70.00	\$560
15	400' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
16	412' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
17	422' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
18	435' North of Balboa Avenue, sealant repair	7	LF					\$25.00	\$175
19	444' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
20	467' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
21	478' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
22	490' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
24	500' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
25	500' North of Balboa Avenue, spall repair	2	SF					\$70.00	\$140
26	511' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
27	534' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
28	545' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
29	556' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
30	567' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
31	567' North of Balboa Avenue, crack injection	5	LF					\$70.00	\$350
32	578' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
33	578' North of Balboa Avenue, crack injection	8	LF					\$70.00	\$560
34	589' North of Balboa Avenue, shotcrete repair	6	SF					\$70.00	\$420
35	597' North of Balboa Avenue, sealant repair	7	LF					\$25.00	\$175
37	general note	200	SF					\$70.00	\$14,000

Continued onto next page

ACTIVITY Balboa Island Bulkhead Inspection		CASH & ASSOCIATES Engineering and Architecture		 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 299-2077 10110-330 BALBOA, CA
STREET LOCATION Grand Canal West Between North Bay Front and Balboa Ave		INSPECTOR: ASSISTANT:	CTM INSPECTION DATE: January 21, 2005 REVISION:	
38 Address 0' - 120'		120	SF	\$70.00
				\$8,400

Subtotal		\$34,895
Contingency	20 %	\$6,979
Contractor OH & P	10 %	\$3,490
City Cost Index	10 %	\$3,490
GRAND TOTAL		\$48,853

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture		
	 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 956-7079 HUNTINGTON BEACH, CA		
STREET LOCATION Grand Canal West Between Balboa Ave and Park Ave	INSPECTOR: CTM	INSPECTION DATE: January 21, 2005	REVISION:
	ASSISTANT:		

Item	Location	Description
1	0' North of Park Avenue	Reference point, face of bridge
2	36' North of Park Avenue	Waterside, vertical crack on south side of construction joint
3	36' North of Park Avenue	Waterside, crack on north side of pile
4	37' - 43' North of Park Avenue	Waterside, crack at bottom of cap
5	47' North of Park Avenue	Waterside, vertical crack on cap above pile 24" long
6	70' North of Park Avenue	Waterside, crack on sides of pile
7	81' North of Park Avenue	Waterside, hole on underside of cap north side of pile
8	97' North of Park Avenue	Waterside, change in quality under cap, spalls, cracks, and loose material under cap.
9	103' North of Park Avenue	Waterside, spalled face of pile
10	114' North of Park Avenue	Waterside, crack on sides of pile
11	136' North of Park Avenue	Waterside, crack on face and sides of pile
12	158' North of Park Avenue	Waterside, crack on face and sides of pile
13	169' North of Park Avenue	Waterside, crack on north side of pile
14	192' North of Park Avenue	Construction joint, sealant cracked and split
15	203' North of Park Avenue	Waterside, cracked pile
16	214' North of Park Avenue	Waterside, spalled south side of pile
17	225' North of Park Avenue	Waterside, cracked face and sides of pile
18	236' North of Park Avenue	Waterside, crack on north side of pile
19	247' North of Park Avenue	Waterside, crack on sides of pile
20	258' North of Park Avenue	Waterside, crack on face and north side of pile
21	269' North of Park Avenue	Waterside, crack on face and sides of pile
22	280' North of Park Avenue	Waterside, spalled face of pile
23	291' North of Park Avenue	Waterside, crack on sides of pile
24	300' North of Park Avenue	Construction joint, sealant cracked and split
25	302' North of Park Avenue	Waterside, crack on face of pile
26	313' North of Park Avenue	Waterside, crack on sides of pile
27	346' North of Park Avenue	Waterside, crack on south side of pile
28	369' North of Park Avenue	Waterside, crack on north side of pile
29	380' North of Park Avenue	Waterside, crack on face and sides of pile
30	391' North of Park Avenue	Waterside, crack on face of pile
31	399' North of Park Avenue	Construction joint, sealant cracked and split
32	413' North of Park Avenue	Waterside, crack on face of pile
33	424' North of Park Avenue	Waterside, crack on north side of pile
34	446' North of Park Avenue	Waterside, crack on face of pile
35	453' North of Park Avenue	Reference point, centerline of Balboa Avenue
36	0' - 400' North of Park Avenue	Landside, top of cap has a "Hollow" sound, significant potential for spalling

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between Balboa Ave and Park Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005	REVISION:



36 feet North of Park



47 feet North of Park



70 feet North of Park



81 feet North of Park



103 feet North of Park



114 feet North of Park

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between Balboa Ave and Park Ave	INSPECTOR: ASS-STANT:	CTM	INSPECTION DATE: January 21, 2005	REVISION:



136 feet North of Park



158 feet North of Park



169 feet North of Park



192 feet North of Park



192 feet North of Park



203 feet North of Park

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between Balboa Ave and Park Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005	REVISION:



214 feet North of Park



225 feet North of Park



236 feet North of Park



247 feet North of Park



258 feet North of Park



269 feet North of Park

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between Balboa Ave and Park Ave	INSPECTOR: ASSISTANT:	DTM	INSPECTION DATE: January 21, 2005	REVISION:



280 feet North of Park



291 feet North of Park



302 feet North of Park



313 feet North of Park



346 feet North of Park



369 feet North of Park

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			CA CASH & ASSOCIATES ENGINEERING & ARCHITECTURE (714) 409-4200 WWW.CASH-CA.COM
STREET LOCATION Grand Canal West Between Balboa Ave and Park Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005	REVISION:



389 feet North of Park



391 feet North of Park



380 feet North of Park



424 feet North of Park



413 feet North of Park



399 feet North of Park

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between Balboa Ave and Park Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005	REVISION:



453 feet North of Park

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 5714 89th - 2072 HUNTING BEACH, CA
STREET LOCATION Grand Canal West Between Balboa Ave and Park Ave	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: January 21, 2005	REVISION:

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
2	36' North of Park Avenue, crack injection	3	LF					\$70.00	\$210
3	36' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
4	37' - 43' North of Park Avenue, crack injection	6	LF					\$70.00	\$420
5	47' North of Park Avenue, crack injection	2	LF					\$70.00	\$140
6	70' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
7	81' North of Park Avenue, spall repair	1	SF					\$70.00	\$70
8	97' North of Park Avenue, spall repair	200	SF					\$70.00	\$14,000
9	103' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
10	114' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
11	136' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
12	158' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
13	169' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
14	192' North of Park Avenue, sealant repair	7	LF					\$25.00	\$175
15	203' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
16	214' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
17	225' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
18	236' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
19	247' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
20	258' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
21	269' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
22	280' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
23	291' North of Park Avenue, shotcrete repair	6	SF					\$70.00	\$420
24	300' North of Park Avenue, sealant repair	7	LF					\$25.00	\$175
25	302' North of Park Avenue	6	SF					\$70.00	\$420
26	313' North of Park Avenue	6	SF					\$70.00	\$420
27	346' North of Park Avenue	6	SF					\$70.00	\$420
28	369' North of Park Avenue	6	SF					\$70.00	\$420
29	380' North of Park Avenue	6	SF					\$70.00	\$420
30	391' North of Park Avenue	6	SF					\$70.00	\$420
31	399' North of Park Avenue, sealant repair	7	LF					\$25.00	\$175
32	413' North of Park Avenue	6	SF					\$70.00	\$420
33	424' North of Park Avenue	6	SF					\$70.00	\$420
34	446' North of Park Avenue	6	SF					\$70.00	\$420
36	0' - 400' North of Park Avenue	300	SF					\$70.00	\$21,000

Continued onto next page

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between Balboa Ave and Park Ave	INSPECTOR: ASSISTANT	CTM	INSPECTION DATE: January 21, 2005	REVISION:

CASH & ASSOCIATES
 PROFESSIONAL ARCHITECTS
 (714) 895-2072
 KUNIMOTO BRIDGE, LA

Subtotal		\$46,865
Contingency	20 %	\$9,373
Contractor OH & P	10 %	\$4,687
City Cost Index	10 %	\$4,687
GRAND TOTAL		\$65,611

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture		
	 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 1714804-2072 HAWTHORNE, BLVD. CA		
STREET LOCATION Grand Canal West Between Park Ave and South Bay Front	INSPECTOR:	CTM	INSPECTION DATE: DEC 20, 2004 & December 21, 2004 & January 21, 2005
	ASSISTANT:		REVISION:

Item	Location	Description
1	0' North of South Bay Front	Reference point, outside corner of bulkhead cap
2	23' North of South Bay Front	Waterside, cracked on south side of pile, bottom of shotcrete exposed
3	34' North of South Bay Front	Waterside, cracked on face of pile, bottom of shotcrete exposed
4	34'-46' North of South Bay Front	Waterside, crack under cap, crack in section 144"
5	46' North of South Bay Front	Waterside, cracked on south side of pile, bottom of shotcrete exposed
6	57' North of South Bay Front	Waterside, cracked face and sides of pile, bottom of shotcrete exposed
7	68' North of South Bay Front	Waterside, cracked sides of pile, bottom of shotcrete exposed
8	79' North of South Bay Front	Waterside, cracked on north side of pile, bottom of shotcrete exposed
9	79' - 90' North of South Bay Front	Waterside, crack under cap, crack in section 132"
10	90' North of South Bay Front	Waterside, cracked face and sides of pile, bottom of shotcrete exposed
11	101' North of South Bay Front	Waterside, pile in good shape, bottom of shotcrete exposed, CCJ
12	101' - 112' North of South Bay Front	Waterside, holes at underside of cap
13	112' North of South Bay Front	Waterside, cracked face of pile, bottom of shotcrete exposed
14	123' North of South Bay Front	Waterside, cracked face of pile
15	134' North of South Bay Front	Waterside, no damage
16	144' North of South Bay Front	Waterside, cracked face of pile
17	144' North of South Bay Front	Waterside, cracked face of pile
18	156' North of South Bay Front	Construction joint, waterside sealant cracked and split
19	178' North of South Bay Front	Waterside, cracked face of pile, south side of pile at mudline, spalled
20	189' North of South Bay Front	Waterside, cracked face of pile
21	189' North of South Bay Front	Waterside, cracked face of pile
22	200' North of South Bay Front	Construction joint, waterside sealant cracked and split
23	200' - 211' North of South Bay Front	Waterside, spall at mudline of pile
24	211' North of South Bay Front	Waterside, holes at underside of cap.
25	211' - 222' North of South Bay Front	Waterside, spall at cap and mudline of pile
26	222' North of South Bay Front	Waterside, holes at underside of cap.
27	231' North of South Bay Front	Waterside, cracked and spalled pile
28	233' North of South Bay Front	Construction joint, waterside sealant cracked and split
29	244' North of South Bay Front	Waterside, cracked face and sides of pile
30	255' North of South Bay Front	Waterside, cracked face of pile
31	266' North of South Bay Front	Waterside, cracked face of pile
32	277' North of South Bay Front	Waterside, cracked face and sides of pile
33	321' North of South Bay Front	Construction joint, waterside sealant cracked and split
34	321' North of South Bay Front	Crack control joint, sealant in good shape. Waterside, cracked at top of pile

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
	STREET LOCATION Grand Canal West Between Park Ave and South Bay Front	INSPECTOR: ASSISTANT:	CTM	
				REVISION:

35 332' - 343' North of South Bay Front	Waterside, Underside of cap cracked and spalled
36 343' North of South Bay Front	Waterside, cracked face and sides of pile
37 354' - 365' North of South Bay Front	Waterside, Underside of cap cracked and spalled
38 365' North of South Bay Front	Construction joint, waterside sealant cracked and split
39 376' North of South Bay Front	Waterside, cracked face of pile
40 387' - 398' North of South Bay Front	Waterside, crack at bottom of cap 96" long
41 398' North of South Bay Front	Waterside, cracked face of pile
42 408' North of South Bay Front	Construction joint, waterside sealant cracked and split
43 408' North of South Bay Front	Waterside, spall at south side of pile
44 433' North of South Bay Front	Waterside, diagonal crack at bridge abutment, 96"



23 feet North of South Bay Front



34 feet North of South Bay Front



46 feet North of South Bay Front

ACTIVITY

Balboa Island Bulkhead Inspection

CASH & ASSOCIATES
ENGINEERING AND ARCHITECTURE

STREET LOCATION

Grand Canal West
Between Park Ave and South Bay Front

INSPECTOR:
ASSISTANT:

CTM

INSPECTION DATE: DEC 20, 2004 &
December 21, 2004 & January 21, 2005

REVISION:



DATE: 8-20-2004
PROJECT: 04-01
SHEET: 001 OF 01



57 feet North of South Bay Front



68 feet North of South Bay Front



79 feet North of South Bay Front



90 feet North of South Bay Front



101 feet North of South Bay Front



112 feet North of South Bay Front

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between Park Ave and South Bay Front	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004 & December 21, 2004 & January 21, 2005	REVISION:



123 feet North of South Bay Front



144 feet North of South Bay Front



156 feet North of South Bay Front



178 feet North of South Bay Front



189 feet North of South Bay Front



200 feet North of South Bay Front

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between Park Ave and South Bay Front	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004 & December 21, 2004 & January 21, 2005	REVISION:



231 feet North of South Bay Front



222 feet North of South Bay Front



211 feet North of South Bay Front



255 feet North of South Bay Front



244 feet North of South Bay Front



233 feet North of South Bay Front

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between Park Ave and South Bay Front	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004 & December 21, 2004 & January 21, 2005	REVISION



266 feet North of South Bay Front



277 feet North of South Bay Front



321 feet North of South Bay Front



332 feet North of South Bay Front



343 feet North of South Bay Front



354 feet North of South Bay Front

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal West Between Park Ave and South Bay Front	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004 & December 21, 2004 & January 21, 2005	REVISION:



365 feet North of South Bay Front



376 feet North of South Bay Front



387 feet North of South Bay Front



398 feet North of South Bay Front



408 feet North of South Bay Front



408 feet North of South Bay Front

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			 CASH & ASSOCIATES ENGINEERING & ARCHITECTURE 11100-100th Ave San Diego, CA 92120
STREET LOCATION Grand Canal West Between Park Ave and South Bay Front	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: DEC 20, 2004 & December 21, 2004 & January 21, 2005	



433 feet North of South Bay Front

ACTIVITY

Balboa Island Bulkhead Inspection

CASH & ASSOCIATES
Engineering and Architecture

STREET LOCATION

Grand Canal West

Between Park Ave and South Bay Front

INSPECTOR:
ASSISTANT:

CTM

INSPECTION DATE: DEC 20, 2004 &
December 21, 2004 & January 21, 2005

REVISION:

CASH & ASSOCIATES
INCORPORATED
(11-1895-7072)
ANNISTON, ALABAMA 35611

Item	Description	QUANTITY		MATERIAL COST		LABOR COST		ENGINEERING ESTIMATE	
		Number	Unit	Unit Cost	Total	Unit Cost	Total	Unit Cost	Total
2	23' North of South Bay Front, shotcrete repair	8	SF					\$70.00	\$560
3	34' North of South Bay Front, shotcrete repair	8	SF					\$70.00	\$560
4	34'-46' North of South Bay Front, crack injection	12	LF					\$70.00	\$840
5	46' North of South Bay Front, shotcrete repair	8	SF					\$70.00	\$560
6	57' North of South Bay Front, shotcrete repair	8	SF					\$70.00	\$560
7	68' North of South Bay Front, shotcrete repair	8	SF					\$70.00	\$560
8	79' North of South Bay Front, shotcrete repair	8	SF					\$70.00	\$560
9	79' - 90' North of South Bay Front, crack injection	11	LF					\$70.00	\$770
10	90' North of South Bay Front, shotcrete repair	8	SF					\$70.00	\$560
12	101' - 112' North of South Bay Front, spall repair	5	SF					\$70.00	\$350
13	112' North of South Bay Front, shotcrete repair	8	SF					\$70.00	\$560
14	123' North of South Bay Front, shotcrete repair	8	SF					\$70.00	\$560
16	144' North of South Bay Front, shotcrete repair	8	SF					\$70.00	\$560
17	144' North of South Bay Front, sealant repair	7	LF					\$25.00	\$175
18	156' North of South Bay Front, shotcrete repair	6	SF					\$70.00	\$420
19	178' North of South Bay Front, shotcrete repair	6	SF					\$70.00	\$420
20	189' North of South Bay Front, shotcrete repair	6	SF					\$70.00	\$420
21	189' North of South Bay Front, sealant repair	7	LF					\$25.00	\$175
22	200' North of South Bay Front, shotcrete repair	6	SF					\$70.00	\$420
23	200' - 211' North of South Bay Front, spall repair	5	SF					\$70.00	\$350
24	211' North of South Bay Front, shotcrete repair	6	SF					\$70.00	\$420
25	211' - 222' North of South Bay Front, spall repair	5	SF					\$70.00	\$350
26	222' North of South Bay Front, shotcrete repair	6	SF					\$70.00	\$420
27	231' North of South Bay Front, sealant repair	7	LF					\$25.00	\$175
28	233' North of South Bay Front, shotcrete repair	6	SF					\$70.00	\$420
29	244' North of South Bay Front, shotcrete repair	6	SF					\$70.00	\$420
30	255' North of South Bay Front, shotcrete repair	6	SF					\$70.00	\$420
31	266' North of South Bay Front, shotcrete repair	6	SF					\$70.00	\$420
32	277' North of South Bay Front, sealant repair	7	LF					\$70.00	\$490
34	321' North of South Bay Front, shotcrete repair	6	SF					\$25.00	\$150
35	332' - 343' North of South Bay Front, spall repair	5	SF					\$70.00	\$350
36	343' North of South Bay Front, shotcrete repair	6	SF					\$70.00	\$420
37	354' - 365' North of South Bay Front, spall repair	5	SF					\$70.00	\$350
38	365' North of South Bay Front, sealant repair	7	LF					\$25.00	\$175

Continued onto next page

ACTIVITY		CASH & ASSOCIATES Engineering and Architecture			
Balboa Island Bulkhead Inspection					
STREET LOCATION		INSPECTOR:	CTM	INSPECTION DATE: DEC 20, 2004 & December 21, 2004 & January 21, 2005	REVISION:
Grand Canal West Between Park Ave and South Bay Front		ASSISTANT:			
39	376' North of South Bay Front, shotcrete repair	6	SF		\$420
40	387' - 398' North of South Bay Front, crack inject.	11	LF		\$770
41	398' North of South Bay Front, shotcrete repair	6	SF		\$420
42	408' North of South Bay Front, sealant repair	7	LF		\$175
43	408' North of South Bay Front, shotcrete repair	6	SF		\$420
44	433' North of South Bay Front, crack injection	8	LF		\$560



Subtotal		\$17,685
Contingency	20 %	\$3,537
Contractor OH & P	10 %	\$1,769
City Cost Index	10 %	\$1,769
GRAND TOTAL		\$24,759

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture		
			
STREET LOCATION Grand Canal East Between South Bay Front and Park Ave	INSPECTOR: CTM	INSPECTION DATE: December 21, 2004	REVISION:
	ASSISTANT:		

Item	Location	Description
1	5' North of South Bay Front	Landside, hollow patch on top of cap, 24" long x 12" wide
2	7' North of South Bay Front	Waterside, spall 96" long, rebar exposed
3	41' North of South Bay Front	Waterside, crack at bottom of cap, 96" long
4	68' North of South Bay Front	Waterside, shotcrete cracked at pile
5	78' North of South Bay Front	Waterside, shotcrete cracked at pile
6	82'-92' North of South Bay Front	Landside, hollow patch on top of cap, 120" long x 12" wide
7	91' North of South Bay Front	Waterside, shotcrete cracked at pile
8	92'-103' North of South Bay Front	Landside, hollow patch on top of cap, 72" long x 12" wide
9	116' North of South Bay Front	Construction joint, sealant missing on landside, waterside sealant in good shape.
10	119' North of South Bay Front	Waterside, spall at bottom of cap 180" long x 6" x 12"
11	133' North of South Bay Front	Waterside, shotcrete at pile lost at base
12	133' North of South Bay Front	Waterside, crack at bottom of cap 120" long
13	145' North of South Bay Front	Construction joint, shotcrete over construction joint sealant missing
14	165' North of South Bay Front	Waterside, bottom of shotcrete exposed at mudline
15	189' North of South Bay Front	Waterside, shotcrete cracked and failing off of pile
16	190' North of South Bay Front	Construction joint, sealant cracked and split on both waterside and landside
17	217' North of South Bay Front	Waterside, shotcrete at wall spalled off
18	240' North of South Bay Front	Waterside, shotcrete at pile cracked and loss of shotcrete on wall
19	240' North of South Bay Front	Waterside, crack at bottom of cap, 120" long
20	234' North of South Bay Front	Construction joint, landside sealant cracked and split, waterside sealant obscured by dock
21	268' North of South Bay Front	Waterside, crack at bottom of cap, 48" long
22	279' North of South Bay Front	Construction joint, spalled at landside, sealant cracked and split both sides
23	323' North of South Bay Front	Construction joint, landside sealant cracked and split, waterside sealant obscured by dock
24	329' North of South Bay Front	Waterside, shotcrete over pile cracked and spalled
25	341' North of South Bay Front	Waterside, shotcrete over pile cracked and spalled
26	367' North of South Bay Front	Construction joint, sealant cracked and split on land and water side
27	372' North of South Bay Front	Waterside, shotcrete spalled at pile base
28	394' North of South Bay Front	Waterside, shotcrete spalled off at pile, entire length
29	394' North of South Bay Front	Waterside, crack at bottom of cap 48" long
30	411' North of South Bay Front	Construction joint, landside and top sealant in good shape, waterside sealant cracked and split
31	Bridge supports	Park Avenue bridge supports need thorough inspection, supports are cracked

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal East Between South Bay Front and Park Ave	INSPECTOR: (ASSISTANT)	QTM	INSPECTION DATE: December 21, 2004	REVISION



Grand Canal East, 5 ft N. of South Bay Front



Grand Canal East, 7 ft N. of South Bay Front



Grand Canal East, 41 ft N. of South Bay Front



Grand Canal East, 68 ft N. of South Bay Front



Grand Canal East, 68 ft N. of South Bay



Grand Canal East, 78 ft N. of South Bay Front

ACTIVITY Balboa Island Bulkhead Inspection	CASH & ASSOCIATES Engineering and Architecture			
STREET LOCATION Grand Canal East Between South Bay Front and Park Ave.	INSPECTOR: ASSISTANT:	CTM	INSPECTION DATE: December 21, 2004	REVISION:



Grand Canal East, 82 ft N. of South Bay Front



Grand Canal East, 91 ft N. of South Bay



Grand Canal East, 97 ft N. of South Bay Front



Grand Canal East, 116 ft N. of South Bay Front



Grand Canal East, 119 ft N. of South Bay



Grand Canal East, 119 ft N. of South Bay Front