



1. Trees must be of quality nursery stock, free from pests, disease and structural defect.
2. Complete backfill of pit with native soil, tamping in soil with feet or shovel handle to insure there are no air pockets.
3. Fill water basin and let seep twice. If drainage is concern, the perimeter of the pit can be dug deeper to divert excess water away from the root ball.
4. Center tree between the sidewalk and curb
5. Space trees 35' min. to 50' max.
6. Plant 50' min. from BCR on the approach to an intersection and 15' from the ECR on the exit side.
7. Plant 10' min. from edge of drive approach.
8. Provide 10' clearance from utility and sewer lines.
9. Plant 20' min. from street light and power poles.
10. Where there is no side walk, plant tree in the center of parkway.
11. Plant tree 3' from curb.

NOTE: For list of designated trees for specific streets please call Urban Forester (949)644-3083

**CITY OF NEWPORT BEACH**  
PUBLIC WORKS DEPARTMENT

APPROVED:

PUBLIC WORKS DIRECTOR

**24 INCH BOX TREE  
PLANTING DETAIL**

RCE NO. 36106  
Date: DEC. 2002  
Drawn by: M. WAGNER

Scale: N.T.S.  
FUSERS/PBW/Space/CAD/STB  
STD Details, 2002, Std

DRAWING NO. **STD-118-L-A**