



# CITY OF NEWPORT BEACH

## COMMUNITY DEVELOPMENT DEPARTMENT

### BUILDING DIVISION

100 Civic Center Drive | P.O. Box 1768 | Newport Beach, CA 926588915  
www.newportbeachca.gov | (949) 644-3200

## MASONRY WALL CHECKLIST

**This is to be used as a general checklist; it is not inclusive of all code requirements and inspection criteria.**

**Per California Building Code (CBC) Chapters 1, 17, 18, 21  
American Concrete Institute (ACI) 530.1 (masonry) and 318 (concrete)  
And applicable ASTM referenced standards**

### **FOOTING INSPECTION**

- Approved plans on site CBC 2101.3
- Location per approved plans CBC 107
- Slope setback maintained 5' to daylight CBC 1808.7
- Clean of foreign debris ACI 318 7.5.1(d)
- Size per approved plans: depth and width, key way if required.
- Stepped, if slope exceeds 1/10. CBC 1809.3
- Reinforcing steel per CBC 1907 and ACI 318
  - Minimum grade per plans (mill certification required for foreign rebar )
  - Properly sized and placement per plan ACI 318 7.5.1
  - Minimum clearances to earth maintained. 3" per ACI 318
  - Adequately secure from displacement ACI 318 7.5.1
  - Lap splice requirements maintained. Length, staggered splices, etc.
  - Minimum length of lap splices (30db in concrete, 40/48 db. in masonry)
  - Location, type, and installation of mechanical splices (manufacturer's data required)
  - Location, type of welded splices (certified welder required/deputy inspection and materials identification required per CBC 1704.3.1.3 and 1708.2)
  - Double dowels at jambs, wall ends and corners as required by plans and ACI 530
- Plumbing piping and electrical conduits Per ACI 318 6.3 and SEOR (structural engineer of record).
- If pipes or conduits run through stem/masonry wall then:
  - Sleeved with schedule 40 steel
  - Protect from concrete
  - $\geq 3$  diameter on center
  - Clearances to reinforcement minimum  $\frac{3}{4}$ "
- Structural Observation per plan and CBC 1710
- Soils engineer approval per plan and CBC 1803.5.11

### **MASONRY (LAYUP) Materials per ACI 530 and ASTM standards Execution per ACI 530.1**

- Rebar and footing clean of over pour and laitance per ACI 530.1 3.2
- Type of masonry per approved plans (density). No blemished, cracked or broken units per ASTM standard C 90
- Deputy inspection requirements of materials and layup-periodic for Level 1
- Strength testing (prisms) per CBC 1704.5 for Level 2

- Wall height per approved plans
- Head and bed joints solidly mortar filled, except beveled end of open-end units.
- Initial bed joint  $> \frac{1}{4}'' < \frac{3}{4}''$ . ACI 530.1 3.3B.1
- Bed and head joints  $\frac{3}{8}''$  thick +/-  $\frac{1}{8}''$  ACI 350.1 3.3.B
  - o Max mortar fin projection of  $\frac{1}{2}''$ . ACI 530.1 3.3B.1c
  - o Clean of foreign debris and mortar droppings per ACI 530.1
- Clean-outs required for grout pours  $> 5'$  ACI 530.1 3.2F
  - o At all cells with vertical reinforcing bars
  - o 3" minimum dimension ACI 530 3.2F.2
  - o Max 32" O.C. if solidly grouted
  - o Max 48" if partially grouted
- Max grout pour height per ACI 530 3.5 and table 7 (based on cell size/grout space)
- Anchor bolts  $> \frac{1}{4}''$  minimum grout surrounding per ACI 530 3.4D
- Plumb and line of masonry layup- within  $\frac{1}{4}''$  in 10' ( $\frac{1}{2}''$  max.) per ACI 530 3.3F

### **REINFORCING STEEL (in masonry wall) per ACI 530.1**

- Minimum grade per plan ( mill cert required )
- Properly sized per plans (special requirements for shear walls)
  - o Maximum size #11 (36mm)
  - o Minimum #4 at 2' o.c. each way in Seismic Design Category D
- Maximum reinforcement 6% of cell area without splice or 12% of cell area with splice
- Placed per plans and within tolerances (vertical rebar within  $\frac{1}{2}''$  sideways, 2" long way)
- Adequately secured from displacement ACI 530.1 3.4B.1 and 3.2E (no drop in bars)
- Lintel bars minimum 2' past openings each side ACI 530 1.17.3.2.3.1
- Double jamb bars at openings
- Vertical steel within 16" of wall openings  $> 16''$  and corners. Within 8" of joints and end of wall ACI 530 1.17.3.2.3.1
- Dowels embedded in concrete not bent more than 1 in 6. ACI 530.1 3.4B.8.6
- Minimum 40 db (40 bar diameters) lap slice, 48db for grade 60 rebar (typical)
- Minimum clearance to masonry maintained. ACI 530.1 3.4B
  - o  $\frac{1}{4}''$  for fine grout –  $\frac{1}{2}''$  for course grout.

### **PRE-GROUT INSPECTION**

- All grout per ASTM C476, 8-10" slump, mix design and psi per SEOR (structural engineer of record)
- Grout consolidation ***and reconsolidation*** per ACI 530.5E
- Maximum pour height per Approved plans and ACI 530
- Maximum lift height per ACI 530 3.5D
- Periodic deputy inspection of reinforcement (and materials) per CBC1704.5.1
- Special inspection requirements apply to all masonry per CBC 1704.5.1(all grouting requires continuous deputy inspection and periodic inspection of reinforcement)***
- Deputy(s) registered with the City of Newport Beach
- Verify permit description reflects actual work being performed.
- Minimum grout key of  $1 \frac{1}{2}''$  per ACI 530 3.5F
- Bed and head joints  $\frac{3}{8}''$  +/-  $\frac{1}{8}''$  and initial bed joints  $\frac{1}{4}''$  min. and  $\frac{3}{4}''$  max. per ACI
- Hot/cold weather precaution requirements in place per CBC 21

### **FINAL INSPECTION**

- Wall construction complete, wall capped
- Appropriate curing time for retaining wall prior to backfill (28 days typical)

- Wall height and length per approved plans
- All grout lifts signed off, all city agencies approved
- Final deputy inspector's report per CBC 1704
- Wall passes the visual acceptance criteria of ACI 530
- Smoke alarms per CBC 907
- Carbon Monoxide detectors per CBC 420