APPENDIX C

GEOTECHNICAL REPORT

REVISED PRELIMINARY GEOTECHNICAL INVESTIGATION REPORT

For

4302 Ford Road Newport Beach, California

Prepared For: Ford Road Holdings, LP

Prepared By:
Langan Engineering & Environmental Services
32 Executive Park, Suite 130
Irvine, California 92614

26 October 2017 Revised 13 December 2018 700048801



REVISED PRELIMINARY GEOTECHNICAL INVESTIGATION REPORT

For

4302 Ford Road Newport Beach, California

Prepared For: Ford Road Holdings, LP

Prepared By:

Langan Engineering & Environmental Services

32 Executive Park, Suite 130

Irvine, California 92614

Enrique Riutort, PE, GE Senior Project Engineer **GE# 2683**

Diane M. Fiorelli, PE, GE Principal/Vice President GE# 3042

26 October 2017 Revised 13 December 2018 700048801

LANGAN

No. GE 3042

CONTENTS

1.	Intro	oduction	. 1
2.	Proj	ect Description	.1
	2.1	Site Description	.1
	2.2	Proposed Construction	.1
3.	Geo	logic Review	. 2
	3.1	Regional Geology	. 2
	3.2	Site Geology	. 2
	3.3	Geologic Hazards	. 2
4.	Sub	surface Investigation & Laboratory Testing	.4
	4.1	Subsurface Investigation	.4
	4.2	Percolation Testing	.5
	4.3	Laboratory Testing	.5
5.		surface Conditions	
6.	Fou	ndation Evaluation and Recommendations	
	6.1	Shallow Foundations	
	6.2	Lateral Resistance	
	6.3	Seismic Design Parameters	
	6.4	Corrosion Considerations	
	6.5	Floor Slabs	
7.		manent below-grade Walls	
8.		struction Recommendations	
	8.1	Excavation and Grading	
	8.2	Site Drainage and Temporary Construction Dewatering	
	8.3	Fill Material and Compaction Criteria	
	8.4	Utility Support	
	8.5	Stormwater Infiltration	
	8.6	Temporary Excavation Support	
9.		ection of Neighboring Structures And Site Features	
10		uture Studies	
10		onstruction Documents and Quality Control	
11		wner and Contractor Obligations	
12		mitations	
13	3. R	eferences	14



FIGURES

7	Site '	•	40.	AI I	

- 2 Boring Location Plan
- 3A CGS Fault Activity Map of California
- 3B CGS Fault Activity Map of California Legend
- 4 City of Newport Beach Seismic Hazards Map
- 5 City of Newport Beach Coastal Hazards Map
- 6 City of Newport Beach Flood Hazards Map
- 7 Design Earth Pressures for Below-Grade Walls
- 8 Subsurface Cross Section A-A'
- 9 Subsurface Cross Section B-B'
- 10 Design Earth Pressures for Cantilever Shoring Wall

APPENDICES

- A EQSearch & USGS ANSS Results
- **B** Boring Logs
- C CPT Logs
- **D** Laboratory Test Results
- **E** Percolation Test Results

26 October 2017 Revised 13 December 2018 700048801 Page 1 of 13

1. INTRODUCTION

As requested by Hines (the Client), we have updated our preliminary geotechnical engineering investigation report for the proposed construction of a three-story building with a one-story below grade parking garage (the Project) at 4302 Ford Road in the city of Newport Beach, Orange County, California (the Site). The purpose of this updated report is to address changes in the design of the proposed Project, and update our geotechnical recommendations.

The recommendations provided herein are based on the 2016 California Building Code (2016 CBC), City of Newport Beach's Title 15 - Buildings and Construction Code, specifically Excavation and Grading Code (Chapter 15.10), and the updated preliminary plans of the Project titled, "Ford Road Residential, Newport Beach" dated 31 July 2018 prepared by MVE + Partners. Elevations referenced herein are with respect to Northern American Vertical Datum of 1988 (NAVD88), unless otherwise noted.

Environmental issues (such as potentially contaminated soil) are outside the scope of this study and should be addressed in a separate study, if applicable.

2. PROJECT DESCRIPTION

2.1 Site Description

The Site is an approximate 1 acre trapezoidal-shaped parcel located at the southeast corner of MacArthur Boulevard and Bonita Canyon Drive at 4302 Ford Road in the city of Newport Beach, California. The Site is bounded by MacArthur Boulevard to the west, Bonita Canyon Drive to the north, Bonita Canyon Sports Park to the south and an existing AT&T building to the east, as shown on Figure 1.

The central and western part of the Site is currently vegetated with ground cover, shrubs, and mature trees. The southern site limits run parallel with an existing concrete pedestrian jogging path, in addition to ascending upwards to the concrete jogging path with an approximate 2H:1V (horizontal:vertical) fill slope from el. 192 to approximate el. 200.

The eastern part of the Site slopes upward at approximately a 2H:1V fill slope that ascends from el. 192 to approximate el. 200 and existing AT&T employee only parking lot. The natural slope is vegetated with ground cover, shrubs, and cactus.

2.2 Proposed Construction

Based on proposed site plans and elevation sections provided by the Client on 30 November 2018, we understand the Project will consist of construction of a three-story above grade multi-family building built on top of a one-story below grade parking structure with mechanical, electrical, and plumbing rooms. Proposed construction footprint is approximately 16,600 square feet.

At the time of this updated preliminary geotechnical investigation report, column and wall loads have not been develop yet.



26 October 2017 Revised 13 December 2018 700048801 Page 2 of 13

3. GEOLOGIC REVIEW

3.1 Regional Geology

The Site is located within the Peninsular Ranges Geomorphic Province of Southern California. The Peninsular Ranges Geomorphic Province consists of a series of mountain ranges separated by northwest trending valleys subparallel to faults that branch from the San Andreas Fault.

Specifically, the Site is located on the western margin of the Los Angeles Basin, an extensive sediment-filled depression bound by the Santa Monica and San Gabriel Mountains to the north, the Pacific Ocean to the west, the Palos Verdes Peninsula to the southwest, San Jose Hills to the south, Santa Ana Mountains to the southeast, and the Puente and Chino Hills to the east. The structural history of the Los Angeles Basin includes extension and strike-slip faulting followed by oblique contraction via thrusting and strike-slip faulting.

3.2 Site Geology

According to the California Geological Survey (CGS), "Seismic Hazard Zone Report for the Tustin 7.5-Minute Quadrangle, Orange County, California (SHZR 012)", the site is underlain by Pleistocene marine deposits (Qvoma+aa). In general, the deposit consist of dense to very dense sand and silty sand with local looser fine sands and silty layers. Underlying the Pleistocene marine deposits is Capistrano Formation. In general the Capistrano formation consists of grey fine sandy siltstone with local clay layers.

3.3 Geologic Hazards

Our geologic hazard review was performed in general accordance with California Geological Survey (CGS) "Special Publication 117A, Guidelines for Evaluating and Mitigating Seismic Hazards in California", the 2006 City of Newport Beach (City) General Plan - Safety Element, 2015 County of Riverside (County) General Plan, Safety Element, and the 2016 edition of California Building Code (2016 CBC). The following subsections present the results of our review of geologic hazards as they pertain to the Site.

Regional Faulting – Recognized and mapped faults that are located within a 100 kilometer (km) radius of the Site based on the CGS "2010 Fault Activity Map of California" (Fault Activity Map) and "An Explanatory Text to Accompany the Fault Activity Map of California" (Explanatory Text) are shown on Figures 3A and 3B, respectively. Based on our review, the closest known currently established Holocene-age faults to the Site are the North Branch Fault, approximately 5.2 miles west of the Site, and an unnamed fault, approximately 13.4 miles west of the Site.

The Site is located in a seismically active area that has historically been affected by generally moderate to occasionally high levels of ground motion. Due to the Site's close proximity to several active faults, the proposed development will probably experience similar moderate to occasionally high ground shaking from these fault as well as ground shaking from other seismically active faults of the southern California region.

Regional Seismicity – A search of the CGS earthquake catalogue using the computer program EQSearch found that 64 earthquakes with magnitude 5.0 or greater have occurred within a 100-km radius of the Site between 1800 and 2017. In addition, a search of the USGS ANSS Comprehensive Earthquake Catalog, updated through 22 October 2017 using a web-based Earthquake Archive Search and URL builder tool, found that 25 earthquakes with magnitudes



26 October 2017 Revised 13 December 2018 700048801 Page 3 of 13

between 5.0 or greater have occurred within a 100-km radius of the Site between 1900 and 2017. Summaries of the EQSearch and USGS ANSS reported earthquakes are provided in Appendix A.

<u>Surface Rupture</u> – The Site is not within a mapped Alquist-Priolo Earthquake Fault Zones as defined by the Alquist-Priolo Earthquake Fault Zoning (AP) Act. Geologic review does not indicate the presence of active surface faulting within the Site.

<u>Liquefaction</u> – Liquefaction is a transformation of soil from a solid to a liquefied state during which saturated soil temporarily loses strength resulting from the buildup of excess pore water pressure, during earthquake-induced cyclic loading. Soil susceptible to liquefaction includes loose to medium dense sand and gravel, low-plasticity silt, and some low-plasticity clay deposits.

Based on the CGS, "Earthquake Zones of Required Investigation Tustin Quadrangle (SHZ Tustin 7.5 Minute Quadrangle)" (2001), – the site is not located within a currently established area that is susceptible to liquefaction. Based on the City of Newport Beach's "General Plan, Safety Element" (2006), the Site is not located within a currently established area that is susceptible to liquefaction. Refer to Figure 4.

<u>Lateral Spreading</u> – Lateral spreading is a phenomenon in which a surficial soil displaces along a shear zone that has formed within an underlying liquefied layer. The surficial blocks are transported downslope or in the direction of a free face, such as a slope, by earthquake and gravitational forces. The Site is not located within a currently established liquefaction hazard zone; therefore, lateral spreading is not anticipated. Refer to Figure 4.

<u>Seismic-Induced Ground Deformations</u> – Seismic-induced ground deformations include ground surface settlement and differential settlement resulting from liquefaction-induced ground deformation and cyclic densification of unsaturated sands and gravels due to earthquakes. The Site is not located within a liquefaction hazard zone and groundwater is about 50 feet below grade; therefore, liquefaction-induced ground deformations are not anticipated. The Site will be underlain by engineered fill overlying competent marine deposits; therefore, significant differential settlement due to cyclic densification is not anticipated.

<u>Landslides</u> – Based on the City's Safety Element, the Site is not located within an earthquake-induced landslide hazard zone or a landslide potential hazard zone. Refer to Figure 4.

<u>Historic High Groundwater</u> – Based on the City's Safety Element – Geology and Seismic Hazards Section and site-specific data, the historically highest groundwater is estimated to be about 50 feet below ground surface.

<u>Flood Mapping</u> - Based on City's Safety Element – Flood Hazard Section and related Exhibit S-5 Flood Hazards, the Site is not located within a currently established flood hazard area. Refer to Figure 6.

Based on Federal Emergency Management Agency's (FEMA) Flood Insurance Rate Map (FIRM) Number 06059C0288J, dated 3 December 2009, and revised to reflect 11 July 2014 Letter Of Map Revision, the Site is within a currently established 'Zone X; areas of 0.2% annual flood,



26 October 2017 Revised 13 December 2018 700048801 Page 4 of 13

areas of 1% annual change of flood with average depths of less than 1 foot or with drainage areas less than 1 square mile, and are protected by levees from 1% annual chance flood.

<u>Tsunami and Seiche</u> – A tsunami is a long high sea wave caused by an earthquake, submarine landslide, or other disturbance. A seiche is oscillation of surface water in an enclosed or semi-enclosed basin such as a lake, bay, or harbor. The Site is not located near a coastline and the Site is not within the immediate vicinity an enclosed body of water therefore; potential for a tsunami or seiche to affect the Site does not exist.

Expansive Soils – Expansive soils can result in differential movement of structures including slab heave and cracking, differential movement of foundations, and cracking of pavements and sidewalks. The 2016 CBC defines potentially expansive soils as soils with expansion indices (EI) greater than 20. Site-specific EI testing was not performed as part of our investigations, and should be performed upon completion of recommended grading if cohesive materials are encountered at the bottom of the proposed excavation.

Collapsible Soils – Collapsible soils, or soils susceptible to hydroconsolidation, are geologically young, unconsolidated, low-density, loose, dry soils commonly present in arid to semi-arid regions, such as Southern California. These soils generally occur within wind deposited sands or silts, alluvial fans, colluvial soils, stream banks, or residual mudflow soils. Collapsible soils have granular particles that are chemically cemented in place creating a porous structure. Once water is introduced, the porous structure collapses and the granular particles are rearranged. A rise in groundwater or increase in surface-water infiltration, combined with the weight of a structure, can cause rapid settlement, resulting in cracking of foundations and walls. Based on the reported Site geologic conditions and subsurface information reviewed for the Site, soils potentially susceptible to hydroconsolidation are not anticipated.

4. SUBSURFACE INVESTIGATION & LABORATORY TESTING

4.1 Subsurface Investigation

Our field investigation consisted of drilling 3 borings, identified as B-1 through B-3 and performing 2 cone penetrometer tests (CPTs). Borings B-1 and B-3 were drilled to 50 feet below ground surface (bgs). Boring B-2 was drilled to a depth of 70 feet bgs and CPT-1 and CPT-2 were advanced to depths of 70 feet bgs. Ground surface elevations at the boring and CPT locations have been inferred from elevations shown on the site survey with respect to NAVD88. Refer to Figure 2 for approximate boring and CPT locations.

In preparation for drilling, the boreholes and CPTs were located in the field by a Langan Engineer, DigAlert Underground Service Alert was contacted to markout known utilities within the public right-of-way, and a private utility locating subcontractor performed a subsurface utility check at the boring locations to check the locations for subsurface utilities or anomalies.

The borings were drilled on 5 and 6 October 2017 by 2R Drilling under the full-time observation of a Langan field engineer. A limited-access drill rig with an 8-inch outer diameter hollow stem auger was used to advance the boreholes.

Sampling using a 3-inch-outer-diameter split barrel California sampler lined with 2.42-inch-inner-diameter brass rings and a 2-inch outer diameter split-spoon sampler was performed at select depths. Soil materials were visually examined and classified in the field in accordance with the



26 October 2017 Revised 13 December 2018 700048801 Page 5 of 13

Unified Soil Classification System (USCS). A copy of the Boring Logs is provided in Appendix B. Upon completion of drilling and logging, the borings were backfilled with a bentonite grout mixture.

Two (2) CPTs, identified as LCPT-1 and LCPT-2 were performed on 5 October 2017 by Kehoe Testing and Engineering under full-time engineering observation of a Langan field engineer. The CPTs were advanced to approximately 70 feet below existing grade. CPT holes were backfilled with bentonite and patched with concrete upon completion.

The CPTs were performed in accordance with ASTM D5778 by hydraulically pushing a 1.4-inch-diameter cone-tipped probe into the ground. Electrical strain gauges within the cone continuously measured soil data for the entire depth advanced, including tip resistance at the cone tip and frictional resistance on the friction sleeve behind the cone. Copies of the CPT logs are provided in Appendix C.

4.2 Percolation Testing

Two (2) percolation tests were performed in borings at depths of approximately 10 feet below existing ground surface. The percolation tests were performed in general accordance with the methods presented in the "Technical Guidance Document", prepared by Santa Ana Regional Quality Control Board, dated 19 May 2011 (updated December 2013). Percolation test results are attached in Appendix E.

4.3 Laboratory Testing

Soil samples obtained from the geotechnical borings were visually examined in the field, and classifications were confirmed by re-examination in our Irvine, California office. The following tests were performed on select samples:

- Moisture Content and Density ASTM D2937
- Direct Shear ASTM D3080
- Consolidation ASTM D 2435
- Atterberg Limits ASTM D 4318
- Sieve Analysis Passing No. 200 ASTM D 422
- Sulfate Content DOT CA Test 417-B
- Electrical Resistivity DOT CA Test 532
- Chloride Content DOT CA Test 422
- Soil pH DOT CA 643

The laboratory test results are provided in Appendix D.

5. SUBSURFACE CONDITIONS

Based on our review of the geologic and subsurface information, and available information obtained to date, the Site has ascending fill slopes on the eastern and southern portion is generally underlain by Pleistocene marine terrace deposits. Our interpretation of the subsurface conditions based on borings, and laboratory test results is summarized below. Refer to Figures 8 and 9, and Boring Logs (Appendix B) and CPT Logs (Appendix C) for additional subsurface information.

• Fill (af) – The fill generally consisting of tan to brown, medium dense, silty fine to medium sands with trace amounts of clay.



- <u>Pleistocene marine terrace deposits (Qvoma+aa)</u> Marine terrace deposits generally consisting of tan to red-brown, medium dense to very dense, silty and clayey fine to medium sands with varying amounts of silt and clay; as well as grey/brown-red to black, stiff to hard, silty clay with varying amounts of fine sand.
- <u>Capistrano Formation (Tcs)</u> Underlying the Pleistocene marine deposits is Capistrano Formation. In general the formation consists of grey fine sandy siltstone with local clay layers. A interlayer of hard light grey siltstone was also encountered at boring location B-2 at an approximate depth of 66 to 71 feet below existing ground surface.
- <u>Groundwater</u> Groundwater was not observed within our borings or measured within the cone penetrometer test locations.

6. FOUNDATION EVALUATION AND RECOMMENDATIONS

The available boring data indicates that materials beneath the proposed building consist of Pleistocene marine terrace deposits which are generally suitable for support of the proposed development on shallow foundations (i.e. spread or strip footings).

6.1 Shallow Foundations

Shallow footings bearing on Pleistocene marine terrace deposits (Qvoma+aa) may be designed with an allowable bearing pressure of ranging from 3,000 to 4,000 pounds per square foot (psf) per for continuous and spread footings embedded a minimum depth of 24 inches below the lowest adjacent grade and having a minimum width of 12 inches. The recommended bearing pressures can be increased by up to 33 percent for temporary transient loading such as earthquake or wind.

Footing excavations should be performed using a backhoe bucket fitted with a smooth steel plate welded across the bucket teeth to minimize disturbance during excavation and to provide a smooth bearing surface.

The foundation bearing level excavation subgrade should be observed and approved by a qualified Geotechnical Engineer prior to steel or concrete placement.

Foundations should be constructed as soon as possible following subgrade approval. The contractor shall be responsible for maintaining the subgrade in its as approved condition (i.e. free of water, debris, etc.) until the footing is constructed.

Shallow foundations designed in accordance with the above parameters are anticipated to settle less than one (1) inch under static loading and less than one (1) inch under dynamic (cyclic) loading with differential settlements less than 0.5 inch over 50 feet.

6.2 Lateral Resistance

Foundations bearing on appropriately prepared subgrade at the basement level and first floor level can be designed to resist lateral sliding using a coefficient of friction equal to 0.35. If sliding resistance is deemed insufficient, shear keys can be introduced to provide supplemental sliding resistance. Should additional lateral resistance be required, we should be notified in



26 October 2017 Revised 13 December 2018 700048801 Page 7 of 13

order to perform additional analyses and develop supplemental recommendations to resist the intended loads.

6.3 Seismic Design Parameters

For design of the project in accordance with the seismic provisions of the 2016 California Building Code (2016 CBC), we recommend the following parameters be used:

- Mapped Spectral Accelerations S_s and S₁ of 1.630g and 0.594g, respectively.
- Site Class D
- Site Coefficients F_A and F_V of 1.0 and 1.5, respectively.
- Maximum Considered Earthquake (MCE) spectral response acceleration parameters at short periods, S_{MS}, and at one-second period, S_{M1}, of 1.630g and 0.891g, respectively.
- Design Earthquake (DE) spectral response acceleration parameters at short period, S_{DS}, and at one-second period, S_{D1}, of 1.086g and 0.594g, respectively.
- MCE Geometric Mean Peak Ground Acceleration PGA_m of 0.651g.

6.4 Corrosion Considerations

Chemical analyses performed on existing surficial material are summarized in the following table.

Boring ID (Depth)	Resistivity (ohm-cm)	рН	Sulfate (ppm)	Chloride (ppm)
B-1 @ 0-5'	2,400	8.1	1,111	73

Based on the minimum resistivity, pH, sulfate and chloride contents, the upper 5 feet of existing surface material are considered to be non-corrosive (Caltrans 2012) to concrete. The sulfate concentration, pH, and chloride concentrations indicate soils are moderately to severly corrosive to ferrous metals. Per American Concrete Institute's (ACI), Type II cement (minimum) can be used for concrete exposed non- corrosive soil. Additional corrosion testing should be performed on actual subgrade materials and recommendations prepared during grading as needed to mitigate concrete corrosion and protect ferrous pipes, structures, valves, and fittings to be installed underground at the Site. A copy of the corrosion test results is provided in Appendix C.

6.5 Floor Slabs

Expansive soils are not anticipated to impact the slabs or foundations; therefore, we preliminarily recommend the slab on grade located at parking level B1 slab can be designed using a modulus of subgrade reaction of 175 pounds per cubic inch (pci). Slab reinforcement should be designed by a Structural Engineer to include sufficient reinforcement for shrinkage at a minimum. Upon completion of the recommended grading, an evaluation of the expansion potential of the foundation-bearing materials should be made, at which time, final recommendations should be presented.

A moisture barrier consisting of 4 inches of clean sand with 6-mil polyethylene capillary break with joints lapped not less than 6 inches is recommended below the basement slab.



26 October 2017 Revised 13 December 2018 700048801 Page 8 of 13

If expansive soils are encountered within the foundation and/or slab areas, methods commonly used to reduce the effects of expansive soils include: controlling the moisture content of the soils through effective site grading and types of planting, moisture conditioning the soils prior to placement of surface finishes, use of impermeable barriers around foundations, confinement of expansive soils through the use of non-expansive soil caps and chemical stabilization. If isolated areas of clays are identified beneath the proposed slab, we recommend removal and replacement with sandier material.

7. PERMANENT BELOW-GRADE WALLS

Below-grade walls can be designed to resist soil and surcharge pressures using the parameters below and pressure distributions in Figure 7.

- Soil Unit Weight = 120 pounds per cubic foot (pcf)
- Friction Angle = 30 degrees
- At-rest Earth Pressure (restrained wall) = 55 psf / foot
- Active Earth Pressure (unrestrained wall) = 35 psf / foot
- Ultimate sliding resistance coefficient = 0.35
- The vertical distance between the proposed final grade and the proposed top of foundation is anticipated to be greater than 6 feet for the proposed development, and the design peak ground acceleration at the Site is greater than 0.6g; therefore, additional earth pressures caused by seismic ground shaking should be considered in design. Below-grade and site retaining walls should be designed for seismic loading conditions using the active earth pressure plus the seismic force increment of 20 psf / foot.
- Lateral loads from surcharges on the retaining wall backfill may be considered to impart surcharge to the restrained walls presuming a rectangular pressure distribution. Surcharge loading from adjacent foundations should be considered where the adjacent foundations are supported on soil above a 1H:1V theoretical influence line projecting upwards from the base of the below grade wall. Lateral loading from neighboring foundations need not be considered if these foundations bear below the abovementioned influence line.
- Surcharge loading should consider adjacent streets, vehicular traffic, and sidewalks.
 Where vehicular traffic will pass within 10 feet of below-grade walls, temporary traffic
 loads should be considered in the design of walls. Traffic loads such as a fire truck or
 car parked on the street beyond the sidewalk may be modeled by a minimum uniform
 pressure of 100 psf / foot applied on the upper 10 feet of the walls.

Because groundwater was not encountered, and historical information associated with adjacent structures indicates its depth to be substantially below the lowest proposed finished level, special provisions for waterproofing below-grade areas do not appear to be warranted at this time. As a minimum, we recommend damp-proofing (such as Grace Water Shield water barrier membrane or equivalent) be used in below-grade closed areas that may house equipment, finishes, or occupants that could be adversely impacted by moisture intrusion. A final choice regarding moisture or vapor protection and mitigation for enclosed below-grade areas should be made after reviewing environmental site conditions and below-grade space use and performance criteria. To avoid undesired vapor accumulation behind walls, prefabricated drainage panels (such as MiraDRAIN or equivalent) are recommended to be placed in uniformly



26 October 2017 Revised 13 December 2018 700048801 Page 9 of 13

spaced strips behind the walls; for typical 4-foot-wide drainage panel rolls, we recommend a 4-foot edge-to-edge spacing at this time. In addition, a perimeter foundation drain should be installed to collect and route any accumulated water to the site drainage system. Perimeter foundation drains could consist of perforated, Schedule 40 PVC, minimum 4-inch diameter, PVC pipe surrounded with clean gravel and completely encased in geosynthetic filter fabric.

The above values assume backfill materials will consist of compacted fill comprised of excavated on-site soils including silty sands and fine to coarse-grained sands. If conditions other than those covered herein are anticipated, the lateral earth pressures should be provided on an individual basis by the Geotechnical Engineer.

If trees with deep-rooted or widespread rooted systems or vegetation are to be planted within 30 feet of the below-grade walls, the client and the Geotechnical Engineer should consult with the Project Landscape Architect to discuss landscaping alternatives that will not impact the adjacent walls and foundations.

8. CONSTRUCTION RECOMMENDATIONS

8.1 Excavation and Grading

Before beginning excavation and grading, a meeting should be held at the Site with the Owner, City Inspector, excavation/grading Contractor, Civil Engineer, and Geotechnical Engineer to discuss the work schedule and geotechnical aspects of the grading.

All pavement, vegetation, and deleterious materials should be disposed of offsite before beginning grading operations.

Any foundation and abandoned utility remnants or construction debris associated with former site structures encountered within excavations should be fully removed, where practical, and any void spaces that may be created should be backfilled with approved compacted structural fill. If utility pipes are too deep to be removed economically in proposed pavement areas, they should be filled with cement and sand grout or equivalent material that will prevent future collapse of the pipe.

After completion of excavation, including removal of all below-grade remnants, stripping, grubbing, removal of asphalt, base course material, and the soil subgrade should be compacted in place by proofrolling with at least 6 passes of a vibratory roller compactor having a minimum static drum weight of 5 tons. Any areas exhibiting rutting or pumping should be removed and replaced with compacted engineered fill material.

Any soft, loose, or unsuitable soils identified by the Geotechnical Engineer during subgrade preparation should be removed and replaced with approved compacted fill.

Any environmentally unsuitable soils encountered during the excavation process should be removed and properly disposed of off-site in accordance with all state and local regulations.

Surface site elements, such as site pavers, planters, and walkways can be supported on subgrade soils comprised of compacted fill or native alluvial soils prepared in accordance with the recommendations provided herein.

8.2 Site Drainage and Temporary Construction Dewatering

Proper drainage should be maintained at all times. Ponding or trapping of water in localized areas can cause differing moisture levels in the subsurface soil. Drainage should be directed



26 October 2017 Revised 13 December 2018 700048801 Page 10 of 13

away from the tops of excavations. Erosion protection and drainage control measures should be implemented during periods of inclement weather. During rainfall events, backfill operations may need to be restricted to allow for proper moisture control during fill placement. Based on our subsurface investigation, groundwater was not encountered within the Site and a dewatering permit during construction is not anticipated. However, during periods of inclement weather water may become trapped at bottom of excavations and require dewatering. In this instance a dewatering permit may be necessary for storm water.

8.3 Fill Material and Compaction Criteria

Fill material (imported or reused) should be free of organic and other deleterious materials and should have a maximum particle size no greater than 3 inches. The on-site soils are suitable for use as compacted fill. All fills should be placed in accordance with the placement and compaction criteria discussed in this report. Imported fill should contain no more than 12 percent passing the #200 sieve by dry weight and have a plasticity index less than 7. Grain size distributions, corrosivity, maximum dry density, and optimum water content determinations should be made on representative samples of the proposed fill material.

All structural backfill and fill beneath building slabs and pavements should be placed in uniform lifts (maximum 8 inches thick before compaction) and compacted to a minimum of 95 percent of the maximum dry density at a moisture content within 2 to 3 percent of optimum moisture content, as determined by ASTM D1557 (Modified Proctor compaction).

Non-structural backfill should be placed in uniform lifts (maximum 8 inches thick before compaction) and compacted to at least 90 percent of its maximum dry density at a moisture content within 3 percent of optimum moisture content, as determined by the ASTM D1557 (Modified Proctor compaction).

Non-structural fill having less than 15 percent finer than #200 sieve should be compacted to at least 95 percent of its maximum dry density at a moisture content within 3 percent of optimum moisture content, as determined by the ASTM D1557 (Modified Proctor compaction).

8.4 Utility Support

Utilities can be supported on compacted fill or on approved native soils. The bedding material should extend at least 12 inches over the top of the utility unless otherwise required by the utility owner. Utility subgrade should be confirmed to be free of standing water, firm, and unyielding prior to placement of bedding material. Utility trenches above pipe bedding should be backfilled in accordance with the recommendations provided herein for fill compaction requirements using either previously excavated soil (if suitable), or with approved imported material. Utility trench backfill in non-structural areas should be compacted to a minimum of 90 percent of the maximum dry density and moisture conditioned to within 3 percent of the optimum moisture content, as determined by ASTM D1557 (Modified Proctor). Utility trench backfill within the building and pavement footprints should be compacted to a minimum of 95 percent of the maximum dry density and moisture conditioned to within 3 percent of the optimum moisture content, as determined by ASTM D1557 (Modified Proctor).

8.5 Stormwater Infiltration

Percolation test P-1 is comprised of clayey fine grained sands and percolation test P-2 is comprised of silty fine grained sands. Percolation test P-1 was performed in marine terrace



26 October 2017 Revised 13 December 2018 700048801 Page 11 of 13

deposits and percolation test P-2 was performed in the existing fill slope on the eastern site limits. The measured percolation rates from P-1 and P-2 are 0.06 and 0.6 inches per hour at test depths of 5 to 10 feet below ground surface and 7 to 10 feet below ground surface, respectively. The corrected infiltration rates are 0.1 and 2.3 inches per hour at test depths of 5 to 10 feet and 7 to 10 feet, respectively.

8.6 Temporary Excavation Support

Temporary excavations are anticipated for the proposed development. The alluvial soils can be classified as Cal/Osha Type C soils. Temporary excavations will be required to facilitate belowgrade excavation for the proposed development and will need to be constructed in accordance with Cal/OSHA requirements. Based on our evaluation of subsurface data, and conceptual site plans, we anticipate excavations to be up to 12 feet max. Temporary slopes may be excavated no steeper than 1.5H:1V (horizontal:vertical).

It is anticipated that a 1.5H:1V temporary slope may require encroachment permits on the southern limits of the Site. If areas where 1.5H:1V temporary slopes are deemed not feasible, we anticipate a cantilever shoring wall (up to 12 feet) could be used. See Figure 10 for design earth pressures

Cantilever Shoring Wall:

- The soil pressure distribution for excavation support is a function of the type of excavation support system and the any bracing used. For design, the shoring system should be designed using a triangular pressure distribution having a maximum pressure of 35H reducing to zero towards the top of the wall, where H is the height of the wall in feet. Cantilever shoring adjacent to public right-of-ways should be designed for at-rest conditions with a maximum pressure of 55H.
- The design earth pressure on the lagging can be 0.6 times the earth pressure or a maximum of 400 psf in accordance with California Department of Transportation (2011), "Trenching and Shoring Manual," Revision 1, August 2011.
- Surcharge loading due to adjacent structures, traffic and construction loading within a
 distance of 30 feet from the wall top should be designed as a constant load equal to 1/3
 the applied surcharge. Heavy concentrated construction surcharges (i.e. cranes,
 material storage, etc.) should be kept a minimum distance of 10 feet away from the
 wall.
- Passive resistance against soldier beams below the excavated level should be based on an equivalent fluid weight of 175 psf/foot beginning 3 feet below the lowest subgrade level in front of the soldier beams. This passive resistance includes a factor of safety of 2.0. A maximum of 3 times the width of the soldier beam can be considered as contributing to passive resistance. Care must be taken during construction so as not to excavate any soil providing lateral restraint to the shoring system's toe. To minimize vibration and avoid adversely impacting neighboring structures, we recommend placing soldier piles in predrilled and cleaned-out holes that are subsequently backfilled with grout or concrete.

9. PROTECTION OF NEIGHBORING STRUCTURES AND SITE FEATURES

All new construction work should be performed so as not to adversely impact or cause loss of support to structures, hardscape and landscape elements, paving, or utilities to remain. At a



26 October 2017 Revised 13 December 2018 700048801 Page 12 of 13

minimum, a preconstruction conditions documentation comprised of photographic and videographic documentation of accessible and visible areas of neighboring landscaped, and hardscaped areas including pavements and sidewalks should be considered before beginning construction at the Site.

10. FUTURE STUDIES

At this time, we recommend performing the following supplemental studies:

- 1. A confirmation design geotechnical investigation and evaluation should be performed to satisfy future project and city of Newport Beach requirements, including:
 - a. Review structural loading, and confirm or refine preliminary foundation recommendations including types, bearing capacities, and anticipated settlements.
 - b. Review final civil and grading plan, structural plans and loads, perform final foundation analyses, and develop final foundation and temporary excavation recommendations.

To maintain our continuity of responsibility on this project, we recommend the above work be performed by LANGAN.

10. CONSTRUCTION DOCUMENTS AND QUALITY CONTROL

Technical specifications and design drawings should incorporate Langan's recommendations. When authorized, Langan will assist the design team in preparing specification sections related to geotechnical issues such as earthwork, ground improvement, shallow foundations, and backfill. Langan should also, when authorized, review foundation drawings prepared by the Structural Engineer, as well as Contractor submittals relating to materials and construction procedures for geotechnical work.

Langan has investigated and interpreted the site subsurface conditions and developed the foundation design recommendations contained herein, and is therefore best suited to perform quality assurance observation and testing of geotechnical-related work during construction. This work requiring quality assurance confirmation includes, but is not limited to, earthwork, backfill, ground improvement, shallow and deep foundations, and excavation support. Recognizing that construction is essentially the completion of design, Langan's quality assurance observation and testing during construction is necessary to maintain our continuity of responsibility on this project.

11. OWNER AND CONTRACTOR OBLIGATIONS

The Contractor is responsible for construction quality control, which includes satisfactorily constructing the foundation system and any associated temporary works to achieve the design intent while not adversely impacting or causing loss of support to neighboring structures. Construction activities that can alter the existing ground conditions such as excavation, fill placement, foundation construction, ground improvement, etc. can also potentially induce stresses, vibrations, and movements in nearby structures and utilities, and disturb occupants of nearby structures. Contractors working at the Site must ensure that their activities will not adversely affect the performance of the structures and utilities, and will not disturb occupants of nearby structures. Contractors must also take all necessary measures to protect the existing



26 October 2017 Revised 13 December 2018 700048801 Page 13 of 13

structures during construction. By using this report, the Owner agrees that Langan will not be held responsible for any damage to adjacent structures.

12. LIMITATIONS

The conclusions and recommendations provided in this report are based on subsurface conditions inferred from a limited number of borings, as well as architectural information provided by the Client. Recommendations provided are dependent upon one another and no recommendation should be followed independent of the others.

Any proposed changes in structures or their locations should be brought to Langan's attention as soon as possible so that we can determine whether such changes affect our recommendations. Information on subsurface strata and groundwater levels shown on the logs represent conditions encountered only at the locations indicated and at the time of investigation. If different conditions are encountered during construction, they should immediately be brought to Langan's attention for evaluation, as they may affect our recommendations.

This report has been prepared to assist the Owner, Architect, and Structural Engineer in the design process and is only applicable to the design of the specific project identified. The information in this report cannot be utilized or depended on by engineers or contractors who are involved in evaluations or designs of facilities (including underpinning, grouting, stabilization, etc.) on adjacent properties which are beyond the limits of that which is the specific subject of this report.

Environmental issues (such as potentially contaminated soil) are outside the scope of this study and should be addressed in a separate study.

\\langan.com\\data\\R\\data8\\700048801\\Office Data\\Reports\\Geotechnica\\Updated Preliminary GIR 2018\\700048801 Updated Preliminary Geotechnical Investigation Report.docx



13. REFERENCES

Codes, Publications, Reports, and Maps

American Concrete Institute (ACI) Committee 318, (2014), Building Code Requirements for Structural Concrete and Commentary, ACI 318-08.

Blake, T.F., (2000), Version 3.00 EQSearch, A Computer Program for the Estimation of Peak Horizontal Acceleration from Southern California Historical Earthquake Catalogs, October 2013 catalogue update.

Coduto, Donald P. (2001), "Foundation Design, Principles and Practices," Second Edition.

California Building Standards Commission, (2016), California Building Code, California Code of Regulations, Title 24.

California Department of Conservation, Division of Mines and Geology, (Revised 1997), Fault Rupture Hazard Zones in California, Alquist-Priolo Special Study Zones Act of 1972, Special Publication 42, supplements 1 and 2 added 1999.

California Department of Transportation, (2012), Corrosion Guidelines.

California Geological Survey (CGS), (1973), Photographic Reconnaissance Map of Major Landslides, Orange County, California, Preliminary Report 15, Plate 2.

California Geological Survey (CGS), (2008), Guidelines for Evaluating and Mitigation Seismic Hazards in California, Special Publication 117A.

California Geological Survey (CGS), (2010), An Explanatory Text to Accompany the Fault Activity Map of California, Scale 1:750,000.

City of Newport Beach, (2006), Chapter 11 Safety Element.

City of Newport Beach, (2017), Title 15 Buildings and Construction, Chapter 15.10-Excavation and Grading Code.

Federal Emergency Management Agency (FEMA), (2009), Flood Insurance Rate Map (FIRM), Map Number 06059C0288J, dated 3 December 2009.

Fife, D.L., (1973), State of California, Department of Conservation, Division of Mines & Geology, Photographic Reconnaissance Map of Major Landslides, Orange County, California, Scale 1:48,000.

Lew, M. et al., (2010), Seismic Earth Pressures on Deep Building Basements, Structural Engineers Association of California (SEAOC) 2010 Convention Proceedings.

Morton, P.K. and Miller, R.V., (1973), State of California, Department of Conservation, Division of Mines & Geology, Geologic Map of Orange County, California, Scale 1:48,000



National Seismic Hazards Mapping Project, (2008), Probabilistic Seismic Hazard Analysis Interactive Seismic Hazard Deaggregation Model, website (http://eqint.cr.usgs.gov/deaggint/2008/).

Naval Facilities Engineering Command (1986), Soils Mechanics, Foundations, and Earth Structures, NAVFAC DM-7.

Santa Ana Regional Water Quality Control Board (SARWQCB), dated 19 May 2011, updated December 2013, "Technical Guidance Document".


Sitar, N., Mikola, R.G., Candia, G., (2012), Seismically Induced Lateral Earth Pressures on Retaining Structures and Basement Walls, Geotechnical Engineering State of the Art and Practice, Keynote Lectures from GeoCongress 2012, Geotechnical Special Publication No. 226, ASCE.


United States Geological Survey (USGS) (2004), Preliminary Geologic Map of the Santa Ana 30' x 60' Quadrangle, Southern California, version 2.0.




FIGURES









LEGEND:

Site Location

Fault Age

The age classifications are based on geologic evidence to determine the youngest faulted unit and the oldest unfaulted unit along each fault of fault seciton

Historic

Holocene

Late Quaternary

Quaternary

100 km

Pre Quaternary Faults

fault, certain

--- fault, approx. located

····· fault, concealed

thrust fault, certain

- → - thrust fault, approx. located

··· thrust fault, approx. located, queried

fault, certain, barball

·--t- fault, concealed, barball

- ¹ - fault, approx. located, barball

Quaternary Faults

— fault, certain

fault, approx. located

-?— fault, approx. located, queried

- 2 - fault, inferred, queried

····· fault, concealed

--?-- fault, concealed, queried

→ thrust fault, certain

--- thrust fault, approx. located

··· thrust fault, concealed

dextral fault, certain

--- dextral fault, approx. located

dextral fault, concealed

sinistral fault, certain

--- sinistral fault, approx. located

····· sinistral fault, concealed

— thrust fault, certain (2)

—— thrust fault, approx. located (2)

····· thrust fault, concealed (2)

fault, solid, barball

fault, dotted, barball

- dextral fault, solid, barball

fault, dotted, queried, ballbar

fault, dotted, queried, ballbar (2)

— fault, solid, dip

— fault, dashed, dip

····· fault, dotted, dip

- reverse fault, solid

---- reverse fault, dashed

···· reverse fault, dotted

Irvine, CA 92614
T: 949.255.8640 F: 949.255.8641 www.langan.com

NEW JERSEY NEW YORK VIRGINIA CALIFORNIA PENNSYLVANIA CONNECTICUT FLORIDA TEXAS OHIO WEST VIRGINIA ARIZONA WASHINGTON DC GEORGIA

Langan Engineering and Environmental Services. Inc


4302 FORD ROAD


NEWPORT BEACH


ORANGE **CALIFORNIA** COUNTY


CGS FAULT ACTIVITY MAP OF CALIFORNIA LEGEND

Project No.	Figure
700048801	
Revised Date	
DECEMBER 2018	2
Scale	3
NOT TO SCALE	
Drawn By	
BJS	









Symbols:

H = Height of Wall (feet)

psf= pounds per square foot

Po = At-Rest Earth Pressure (Restrained Walls)


Pa = Active Earth Pressure (Unrestrained Walls)


Pae = Earth Pressure Increment


qs = surcharge


Notes

- 1. Dynamic Pressure Increment should be added to the Active Earth Pressure and any applicable surcharges
- 2. Minimum surcharge shown is based on a fire truck or car parked 10 feet beyond the wall. If higher surcharge loads are anticipated (e.g., adjacent buildings, heavy construction equipment, etc.) The surcharge loading should be evaluated on a case by case basis.









- conditions when adjacent to public right-of-way. See Figure 7.
- 3. Active pressure below the excavation should be assumed to act over one pile diameter.
- 4. The recommended pressures do not include surcharges from adjacent structures. Surcharge from adjacent structures should be added to the above shoring pressures, as appropriate.
- 5. pcf denotes pounds per cubic foot; psf denotes pounds per square foot.

Project

ORANGE COUNTY

psf/ft= pounds per square foot per linear foot along the wall



FLORIDA NORTH
ABI ATHENS DO
ISTANBUL PANAM

Langan Engineering & Environmental Services, Inc.

4302 FORD ROAD

NEWPORT BEACH

CALIFORNIA

Figure Title **DESIGN EARTH PRESSURES FOR CANTILEVER SHORING WALL**

Project N 70004	Figure	No.
Date OCTOBE		
REVISED DECEMB		10
Scale AS SI		10
Drawn By		
DV		

APPENDIX A EQSEARCH & USGS ANSS RESULTS



Table A.1 – USGS ANSS Comprehensive Catalog Search Results

Date ^{1,3}	Latitude ^{1,3}	Longitude ^{1,3}	Approximate Magnitude (Magnitude Type) 1,2,3		Approximate Distance from Project Site ^{1,3} (km)
3/29/2014	33.9325	-117.91583	5.1	(M _w)	34
7/29/2008	33.9485	-117.76633	5.44	(M _w)	37
3/20/1994	34.231	-118.475	5.24	(M_L)	88
1/17/1994	34.275	-118.493	5.89	(M_L)	93
1/17/1994	34.213	-118.537	6.7	(M_L)	90
6/28/1991	34.27	-117.993	5.8	(M_L)	72
2/28/1990	34.144	-117.697	5.51	(M _L)	59
12/3/1988	34.151	-118.13	5.02	(M∟)	63
10/4/1987	34.074	-118.098	5.25	(M _L)	54
10/1/1987	34.061	-118.079	5.9	(M_L)	52
7/13/1986	32.971	-117.874	5.45	(M∟)	73
1/1/1979	33.9165	-118.68717	5.21	(M_L)	83
9/12/1970	34.2548333	-117.53433	5.22	(M _L)	76
9/23/1963	33.7036667	-116.93817	5.29	(M _w)	86
12/26/1951	32.9161667	-118.30517	5.75	(M _L)	89
11/14/1941	33.7906667	-118.26367	5.12	(M _L)	41
5/31/1938	33.6993333	-117.51117	5.23	(M _w)	33
3/11/1933	33.6238333	-118.00117	5.29	(M_h)	13
3/11/1933	33.7666667	-117.985	5.02	(M_h)	19
3/11/1933	33.6308333	-117.9995	6.4	(M_h)	13
4/21/1918	33.647	-117.433	6.7	(M_{w})	40

Notes:

- 1. Earthquake Catalog search results obtained from USGS ANSS Comprehensive Catalog on 12 December 2018.
- Refer to USGS ANSS Comprehensive Catalog and USGS Earthquake Hazards Program for additional information on magnitude types.
- 3. Earthquake Catalog search results include earthquake events within 100 km of the Project Site with magnitudes of 5.0 or greater since 1900.



700048801_4302 Ford Road

******** EQSEARCH * Version 3.00 * *******

ESTIMATION OF PEAK ACCELERATION FROM CALIFORNIA EARTHQUAKE CATALOGS

JOB NUMBER: 700048801

DATE: 10-24-2017

JOB NAME: 4302 Ford Road

EARTHQUAKE-CATALOG-FILE NAME: C:\Program Files (x86)\EQSEARCH\February 2016

Update\ALLQUAKE.DAT

MAGNITUDE RANGE:

MINIMUM MAGNITUDE: 5.00 MAXIMUM MAGNITUDE: 9.00

SITE COORDINATES:

SITE LATITUDE: 33.6290 SITE LONGITUDE: 117.8610

SEARCH DATES:

START DATE: 1800 END DATE: 2017

SEARCH RADIUS:

62.6 mi 100.7 km

ATTENUATION RELATION: 14) Campbell & Bozorgnia (1997 Rev.) - Alluvium UNCERTAINTY (M=Median, S=Sigma): S Number of Sigmas: 1.0

ASSUMED SOURCE TYPE: SS [SS=Strike-slip, DS=Reverse-slip, BT=Blind-thrust]

SCOND: 0 Depth Source: A Basement Depth: 5.00 km Campbell SSR: 0 Campbell SHR: 0

COMPUTE PEAK HORIZONTAL ACCELERATION

MINIMUM DEPTH VALUE (km): 3.0

EARTHQUAKE SEARCH RESULTS

Page 1

Page	_								
FILE	:	LONG.	 DATE 	TIME (UTC) H M Sec		 QUAKE MAG.		SITE MM INT.	APPROX. DISTANCE mi [km]
DMG	33.5750 33.6170 33.6830 33.7000 33.7500 33.7500 33.7500 33.7500 33.7500 33.7500 33.7830 33.6990 33.9325 33.9325 33.9325 33.9325 33.9530 34.0000 34.0000 34.0000 34.0000 34.1000 34.1000 34.1000 34.2000 34.2000 34.2000 34.2000 34.2000 34.2000 34.2000 34.2000 34.2000 34.2700	117.9830 118.0170 118.0500 118.0670 118.0670 118.0830 118.0830 118.0830 118.0830 118.0830 118.76000 117.5110 117.5110 117.7610 117.7610 117.4000 117.4000 117.4000 117.4000 117.4000 118.2670 118.0790 118.2500 118.3000 117.4000 117.2000 117.2000 117.2000 117.3000 117.3000 117.3000 117.3000 117.3000 117.3000 117.5400	03/11/1933 04/22/1918 05/31/1938 03/29/2014 07/29/2008 11/14/1941 12/25/1903 05/13/1910 05/13/1910 05/15/1910 07/11/1856 09/23/1827 03/26/1860 07/11/1855 09/03/1905 02/28/1990 07/16/1920 08/28/1899 12/19/1880 07/23/1923 06/28/1991 08/04/1927 11/19/1918 07/13/1989 07/15/1905 07/22/1899 07/15/1905 07/22/1899 07/15/1905 07/12/1970 01/19/1989	518 4.0 19 150.0 658 3.0 51022.0 85457.0 131828.0 2 9 0.0 910 0.0 323 0.0 230 0.0 91017.6 2115 0.0 83455.4 040942.3 184215.7 84136.3 1745 0.0 620 0.0 1547 0.0 757 0.0 1425 0.0 1425 0.0 1425 0.0 1425 0.0 10 0 0.0 105938.2 0 0 0.0 105938.2 0 0 0.0 105938.2 0 0 0.0 14354.5 1224 0.0 234336.6 18 8 0.0 215 0.0 0 0 0.0 73026.0 144354.5 1224 0.0 2018 0.0 1347 8.2 2041 0.0 143053.0 65328.8	0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0	5.20 5.10 5.50 5.10 5.30 5.00 5.00 5.00 5.50 5.30 5.30 5.00 5.00 5.00 5.00 5.00 5.00 5.00 5.00 5.00 5.30 5.30 5.30 5.30 5.30 5.30 5.40 5.30 5.30 5.30 5.30 5.40 5.30 5.30 	0.149 0.123 0.136 0.085 0.085 0.083 0.069 0.069 0.070 0.048 0.069 0.070 0.031 0.077 0.031 0.077 0.031 0.023	X	6.1(9.9) 7.9(12.8) 9.0(14.5) 11.5(18.5) 12.8(20.6) 12.8(20.6) 15.2(24.5) 15.2(24.5) 15.2(24.5) 15.2(24.5) 15.2(24.5) 15.2(24.5) 15.2(24.5) 15.2(34.1) 20.7(33.3) 21.2(34.1) 23.1(37.2) 24.7(39.8) 26.8(43.2) 26.9(43.3) 26.9(43.3) 27.9(44.8) 32.3(52.0) 33.5(54.0) 34.0(54.7) 34.0(54.7) 34.0(54.7) 34.0(54.7) 35.3(56.8) 35.9(57.8) 36.5(58.7) 38.6(62.2) 39.5(63.5) 42.3(68.1) 43.4(69.9) 44.4(71.5) 44.7(72.0) 44.7(72.0) 45.4(73.1) 45.7(73.6) 47.5(76.4) 47.9(77.1) 48.3(77.7)

Page 2

700048801_4302 Ford Road DMG |34.3000|117.6000|07/30/1894| 512 0.0| 0.0| 6.00| 0.036 | V | 48.7(78.3) DMG |33.9500|118.6320|08/31/1930| 04036.0| 0.0| 5.20| 0.017 | IV | 49.5(79.6) DMG |33.7500|117.0000|04/21/1918|223225.0| 0.0| 6.80| 0.070 | VI | 50.2(80.7) DMG |33.7500|117.0000|06/06/1918|2232 0.0| 0.0| 5.00| 0.014 | IV | 50.2(80.7) DMG |34.3000|117.5000|07/22/1899|2032 0.0| 0.0| 6.50| 0.053 | VI | 50.7(81.6) DMG |33.8000|117.0000|12/25/1899|1225 0.0| 0.0| 6.40| 0.048 | VI | 50.8(81.8) PAS |33.9440|118.6810|01/01/1979|231438.9| 11.3| 5.00| 0.013 | III | 51.8(83.4) DMG |34.3700|117.6500|12/08/1812|15 0 0.0| 0.0| 7.00| 0.078 | VII | 52.6(84.6) DMG |33.7100|116.9250|09/23/1963|144152.6| 16.5| 5.00| 0.013 | III | 54.1(87.0) DMG |33.0000|117.3000|11/22/1800|2130 0.0| 0.0| 6.50| 0.048 | VI | 54.2(87.2)

EARTHQUAKE SEARCH RESULTS

Page 2

FILE CODE	LAT.	LONG.	 DATE 	TIME (UTC) H M Sec	! !	QUAKE	SITE ACC. g	SITE MM INT.	APPROX. DISTANCE mi [km]
GSP	34.2310	118.4750	03/20/1994	212012.3	13.0	5.30	0.016	IV	54.4(87.6)
GSP	34.2130	118.5370	01/17/1994	123055.4	18.0	6.70	0.055	VI	55.9(90.0)
DMG	34.3080	118.4540	02/09/1971	144346.7	6.2	5.20	0.014	III	57.9(93.1)
DMG	34.2000	117.1000	09/20/1907	154 0.0	0.0	6.00	0.028	V	58.8(94.6)
GSB	34.3010	118.5650	01/17/1994	204602.4	9.0	5.20	0.013	III	61.5(98.9)
DMG	33.9500	116.8500	09/28/1946	719 9.0	0.0	5.00	0.010	III	62.1(99.9)
GSP	34.3050	118.5790	01/29/1994	112036.0	1.0	5.10	0.011	III	62.2(100.1)
DMG	34.4110	118.4010	02/09/1971	14 244.0	8.0	5.80	0.021	IV	62.2(100.1)
DMG	34.4110	118.4010	02/09/1971	141028.0	8.0	5.30	0.014	III	62.2(100.1)
DMG	34.4110	118.4010	02/09/1971	14 041.8	8.4	6.40	0.037	V	62.2(100.1)
DMG	34.4110	118.4010	02/09/1971	14 1 8.0	8.0	5.80	0.021	IV	62.2(100.1)

-END OF SEARCH- 64 EARTHQUAKES FOUND WITHIN THE SPECIFIED SEARCH AREA.

TIME PERIOD OF SEARCH: 1800 TO 2017

LENGTH OF SEARCH TIME: 218 years

THE EARTHQUAKE CLOSEST TO THE SITE IS ABOUT 6.1 MILES (9.9 km) AWAY.

LARGEST EARTHQUAKE MAGNITUDE FOUND IN THE SEARCH RADIUS: 7.0

LARGEST EARTHQUAKE SITE ACCELERATION FROM THIS SEARCH: 0.411 q

COEFFICIENTS FOR GUTENBERG & RICHTER RECURRENCE RELATION:

a-value= 0.973 b-value= 0.345 beta-value= 0.794

TABLE OF MAGNITUDES AND EXCEEDANCES:

Earthquake	Number of Times	Cumulative
Magnitude	Exceeded	No. / Year
4.0	64	0.29358 Page 3

	7	00048801_4302	Ford Road
4.5	64	0.29358	
5.0	ĺ 64	0.29358	
5.5	22	0.10092	
6.0	15	0.06881	
6.5	j 6	0.02752	
7.0	j 2	0.00917	

APPENDIX B BORING LOGS



LA	NUF	1/V	Log	of Boring	9		B-1				Sheet	1	of	3
Project	4000 F . I.D I			Project N	0.		70004	2004						
Location	4302 Ford Road			Elevation	and Da	atum	70004	3801						
Drilling Compa	4302 Ford Road, Ne	wport Beach, CA		Date Sta	eto d		Approx	imate			et (NAVD 8 Finished	38)		
Drilling Compa	2R Drilling			Date Sta	ieu		10/6	5/17	ľ	Jale	rillistieu	10	/6/17	
Drilling Equipn	nent			Completion Depth Rock Depth										
Size and Type	Limited Access Rig			Niverban			51 Disturb	.5 ft ed		Un	ndisturbed	C	- Core	
Casing Diame	8" diameter Hollow S	Stem Auger	Casing Depth (ft)	Number			First		10	Co	ompletion	- 2	4 HR.	-
NA	-	Weight (lbs)	Drop (in)	Water Le			∇		-		<u>T</u>		<u>Ā</u>	-
Casing Diame Casing Hamm Sampler Sampler Hamr	-		- Diop (III)		Diciliali		eff							
Sampler Hami	3" O.D. Cal. Mod. & 2	Weight (lhs)	Drop (in) 30 inches	Field Eng	jineer									
	Automatic	140 lbs.	30 inches			D	aniel Ju Samp	udge le Data	a			_		
MATERIAL SYMBOL (tt)		Sample Description	1	Dept Scal		Туре	Recov. (in) Penetr.	sist /6in	N-Val (Blows		(Drilling	Rema Fluid, Dep	rKS th of Casing, esistance, et	,
200.0 2 XXXXX)			0	Ž	F	Pe Re	<u> </u>	10 20 3	0 40	Fluid Loss	, Drilling R	esistance, et	(c.)
MATERIAL MATERIAL (4) + 500°C				E	=	Н								
				F 1	=						Hand a	ugered	0 to 5 fee	t.
3	Tan-brown silty fin	ie to medium SAND, t	race clay (SM)	_ 2	=	1								
\$	dry. [FILL]	ie to mediam SAND, t	race clay, (SIVI),		<u>-</u> 4	H								
₫ \				3	=									
				- 4	=									
ZOT-10-05 DARLE DATE: GF2				<u> </u>	=	П								
' IXXXXXI	Medium dense, tar trace clay, (SM), di	n-brown, silty fine to m	edium SAND,	5	=		3							
	trace clay, (SW), ui	וא (רובב)		- 6	S-1	SPT	8 3	7 1	5 9					
\$ \\\\\				<u> </u>	+	╁	°	-	$ \cdot $					
192.5	5			F ′	=									
192.5	Marine Terrace De	posits (Qvoma+aa)		E 8	4									
NS50		, , , , , , , , , , , , , , , , , , ,		<u> </u>	=									
				<u> </u>	3									
	Medium dense, tar	n-brown, silty fine to m	edium SAND.	_ 10	+	╁	4	\dashv						
	(SM), dry.	, , , , , , , , , , , , , , , , , , ,	,	Ē 11	S-2	SPT	∞ .	14	20					
				- 11 -	1		14		28					
A A A A A A A A A A A A A A A A A A A				12	=======================================									
				13	=									
				ļ '3	=									
				- 14										
				- - 15	1									
90048	Dense, brown-red,	silty fine SAND, (SM)	, moist.		4		ω 9 ω	45						
Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z Z				16	S-3	SPT	& □ 16	15	31					
				- - 17				\exists						
				ļ ''	=									
				18										
NLANGAN COMIDALANKVDA ASKYOUGASSOTIENGINEEKING DA FAKEO I EGFINICALKS				- - 19	4									
JANG.				į, iš	=									
₹ 111				<u>_</u>		1					<u> </u>			



Log of Boring **B-1** Sheet 2 of 3 Project Project No. 4302 Ford Road 700048801 Location Elevation and Datum 4302 Ford Road, Newport Beach, CA Approximately 200 feet (NAVD 88) Sample Data Remarks Elev (ft) Depth N-Value (Blows/ft) Penetr. resist BL/6in Sample Description (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.) Scale 10 20 30 40 -180.0 20 Dense, tan, silty fine SAND, (SM), dry. SPT S-4 8 17 21 36 19 22 23 24 25 Dense, grey/brown-red, silty fine SAND, (SM), moist. 20 S-5 CR 50/5" 50/5" 26 //LANGAN.COM/DATA/IRV/DATA8/700048801/ENGINEERING DATA/GEOTECHNICAL/GINTLOGS/700048801-BORING LOGS - 2017-10-05 DRILL DATE.GPJ 27 28 29 30 Dense, grey/brown-red, silty fine SAND, (SM), moist. S-6 9 11 31 20 32 33 34 35 Dense, brown-red, silty fine SAND, (SM), moist. 16 S-7 9 CR 35 36 40 37 38 39 Medium dense, brown-red, silty fine SAND, trace coarse 3 sand, (SM), moist S-S 159.3 18 9 10 42 Capistrano Formation [Tcs] 43



Log of Boring **B-1** Sheet 3 of 3 Project Project No. 4302 Ford Road 700048801 Location Elevation and Datum 4302 Ford Road, Newport Beach, CA Approximately 200 feet (NAVD 88) Sample Data Remarks Elev (ft) Depth N-Value (Blows/ft) Penetr. resist BL/6in Number Sample Description (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.) Scale 10 20 30 40 155.0 Very stiff, grey/brown-red, fine sandy SILTSTONE, moist. S-9 CR 8 10/26/2017 2:01:14 PM ... Report: Log - LANGAN 17 46 24 48 49 50 Very stiff, grey/brown-red, fine sandy SILTSTONE, moist. SPT 3 S-10 18 6 148.5 NLANGAN, COMIDATANIRVIDATA81700048801/ENGINEERING DATA/GEOTECHNICAL/GINTLOGS/700048801-BORING LOGS - 2017-10-05 DRILL DATE.GPJ 52 End boring at 51.5 feet. No groundwater encountered. Boring backfilled with bentonite-grout mixture tremie style. 53 55 56 58 59 60 61 62 63 64 66 67 68 69

LA	NG/	1/V	Log	of Boring		B-2			Sheet	1	of	4
Project	4202 Ford Bood			Project No.		70004000	1					
Location	4302 Ford Road			Elevation and Da		70004880	1					
Drilling Compa	4302 Ford Road, Ne	wport Beach, CA		Date Started		Approxima	ately 1		et (NAVD a	88)		
	2R Drilling					10/5/17				10	0/5/17	
Drilling Equipm	nent Limited Access Rig			Completion Dept	h	71.5 ft		Rock	Depth		_	
Size and Type	of Bit	Stom Augor		Number of Samp	oles	Disturbed		Un	disturbed		Core	
Casing Diamet Casing Hamme Sampler Sampler Hamne	8" diameter Hollow S er (in)	Meili Augei	Casing Depth (ft)	Water Level (ft.)		First	14		mpletion		24 HR. √▼	
Casing Hamme	 er_	Weight (lbs)	Drop (in)	Drilling Foreman		<u> </u>		1	<u></u>		$ar{ar{ar{\Lambda}}}$	-
Sampler	3" O.D. Cal. Mod. &	2" O.D. Split Spoon		Field Engineer	Je	eff						
Sampler Hamn		Weight (lbs) 140 lbs.	Drop (in) 30 inches	Troid Engineer	Da	aniel Judge			_			
MATERIAL SYMBOL (tt) +193.0		Sample Description	ı	Depth Scale Env	Type	Recov. (in) Penetr. resist BL/6in	N-V (Blow 10 20	vs/ft)	(Drilling Fluid Loss	Rema Fluid, De i, Drilling F	I rks pth of Casing Resistance, et	c.)
102/02/01		eposits (Qvoma+aa) AND, (SM), dry.		1 - 2	НА				Hand a	ugered	0 to 5 fee	t.
TECHNING LOGS - ZOTT IGNO DAILE DATE: GRO	Medium dense, tar	n, silty fine SAND, (SM	l), dry.	5 - 1-0 - 6 - 1-0	SPT	6 10 10	20•					
	Medium dense, tar	n, silty fine SAND, trac	e clay, (SM), dry.	12 -	SPT	10 12 14 16	30					
NEANGARIACORIDA MIRY DA TROCTORON TENGING DA MAGEO TECHNICALIGIN LLOGGNOCORIDA MAGEO TECHNICALIGIN LLOGGNOCO	Medium dense, tar	n, silty fine SAND, (SM	l), dry.	13 - 14 - 15 - F · · · · · · · · · · · · · · · · · ·	CR	₹ 16 50/6"		50/6"				



Log of Boring **B-2** Sheet 2 of 4 Project Project No. 4302 Ford Road 700048801 Location Elevation and Datum Approximately 193 feet (NAVD 88) 4302 Ford Road, Newport Beach, CA Sample Data Remarks Elev (ft) Depth N-Value (Blows/ft) Penetr. resist BL/6in Sample Description (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.) Scale 10 20 30 40 173. 20 Dense, tan-brown-red, silty fine to medium SAND, (SM), SPT S-4 18 15 21 16 22 23 10/26/2017 2:01:18 PM 24 25 Medium dense, silty fine SAND, (SM), moist. 18 9 2017-10-05 DRILL DATE.GPJ 27 28 29 30 Medium dense, brown-red, silty fine SAND, trace clay, ". ANGAN. COMIDATAIIRVIDATA81700048801/ENGINEERING DATAIGEOTECHNICALIGINTLOGS\700048801-BORING LOGS (SM), moist. S-6 16 10 31 10 Capistrano Formation [Tcs] 32 33 34 35 Stiff, grey, fine sandy SILTSTONE, moist. S-7 9 CR 12 36 16 37 38 39 Firm, grey, fine sandy SILTSTONE, moist. 3 S-S 18 4 42 43



LANGAN Log of Boring **B-2** Sheet of 4 Project Project No. 4302 Ford Road 700048801 Location Elevation and Datum Approximately 193 feet (NAVD 88) 4302 Ford Road, Newport Beach, CA Sample Data Remarks Elev (ft) Depth N-Value (Blows/ft) Penetr. resist BL/6in Number Sample Description Type (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.) Scale 148.0 10 20 30 40 45 Very stiff, grey, fine sandy SILTSTONE, moist. S-9 CR 8 17 22 48 49 1" fine to coarse brown-red Very stiff, dark grey, fine sandy SILTSTONE, moist. clayey sand layer mid-way in S-10 9 9 sampler. 12 52 53 Hammer pinging noise Very stiff, dark grey, fine sandy SILTSTONE, moist. 10 during sampling, possible 50/5" cobble. 56 57 58 59 Very stiff, dark grey, fine sandy SILTSTONE, moist. SPT S-12 18 7 14 62 63 S-13CR 5 Collected sample within the Hard, dark grey, fine sandy SILTSTONE, moist. 50/5" full length of the California Modified Sampler, however 66 Hard, grey, fine sandy SILTSTONE, dry. driving the sampler only recorded 50 blows for the 67 first 5-inches. 68 69



Log of Boring B-2 Sheet of 4 Project Project No. 4302 Ford Road 700048801 Elevation and Datum Location 4302 Ford Road, Newport Beach, CA Approximately 193 feet (NAVD 88) Sample Data Remarks Elev. (ft) Depth Scale N-Value (Blows/ft) Penetr. resist BL/6in Sample Description (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.) 10 20 30 40 123.0 70 Very stiff, grey, fine sandy SILTSTONE, dry. SPT S-14 18 NLANGAN.COMIDATAIRVIDATA8/700048801ENGINEERING DATA/GEOTECHNICAL/GINTLOGS/700048801-BORING LOGS - 2017-10-05 DRILL DATE.GPJ ... 10/26/2017 2:01:19 PM ... Report: Log - LANGAN 12 28 16 72 73 74 75 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94

LA	NGA	A/V	Log	of Boring _			B-3			Sheet	1	of	3
Project	4202 Ford Dood			Project No.		_	70004000	14					
Location	4302 Ford Road			Elevation and	Dati		70004880)					
Drilling Compa	4302 Ford Road, Ne	wport Beach, CA		Date Started		A	Approxim	ately 1		et (NAVD Finished	88)		
Drilling Equipn	2R Drilling			10/5/17 10					0/5/17				
Drilling Equipn	Limited Access Rig			Completion Depth Rock Depth 51.5 ft					_				
Size and Type	of Bit 8" diameter Hollow S	Stem Auger		Number of Sa	mple	es I	Disturbed	10	Ur	ndisturbed	_	Core	_
Casing Diame Casing Hamm Sampler Sampler Hamr			Casing Depth (ft)	Water Level (f	t.)		First	_		ompletion	_	24 HR. V	_
ငasing Hamm	er_	Weight (lbs)	Drop (in)	Drilling Forem	an	·					ı		
Sampler	3" O.D. Cal. Mod. &		D ('.)	Field Engineer	r	Jet	П						
	ner Automatic	Weight (lbs) 140 lbs.	Drop (in) 30 inches	<u> </u>		Da	niel Judg Sample D						
MATERIAL MATERIAL (#)		Sample Description		Depth Scale	Number	Type	Recov. (in) Penetr. resist	N-V (Blov	alue vs/ft) 30 40	(Drilling Fluid Loss	Rema Fluid, De s, Drilling I	arks pth of Casing, Resistance, et	c.)
				0 +		}				Handa	ugarad	0 to 5 fee	4
V Z Z Z Z Z	Marine Terrace De	eposits (Qvoma+aa)				ł				Папи а	ugerea	0 10 5 166	ι.
	Brown, clayey fine	to medium SAND, (SC	C), moist.	2 -	B-1	₹							
2017-10-05 DRILL DATE: GPJ				3 -									
' Z · Z · Z · Z ·]	Medium dense, bro some silt, (SC), mo	own-yellow-white, claye oist.	ey fine SAND,	5	S-1	S	6 © 12	28					
185.5				7 -			16	_ 20					
185.5	5												
10058/70				9 =									
AL/GINT	Medium dense bro	own, silty fine SAND, (SM) drv	10			10	_					
NLANGAN COMIDATANKUDATA877000488011ENGINEEKING DATAKSEOTECHNICALKS		, ., , (11 =	S-2	SPT	∞ 13 16	29					
I ANGEO				12									
KING DA				13									
NGINEE NGINEE				14									
B8010	Vary dance too br	cours silty fine CAND	(CM) dn/	15									
87,0004	very delise, tall-bl	own, silty fine SAND, (Oivi), ury.		S-3	ਲ ਲ	15 25						
\$WDATA				17			50/5"		50/5'	"			
DATAILE STANF													
COM				- 18 -									
NGAN				19									
≨ [<u> </u>						/			



Log of Boring **B-3** Sheet of 3 Project Project No. 4302 Ford Road 700048801 Location Elevation and Datum Approximately 193 feet (NAVD 88) 4302 Ford Road, Newport Beach, CA Sample Data Remarks Elev Depth N-Value (Blows/ft) Sample Description (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.) (ft) Scale 10 20 30 40 173. 20 Medium dense, tan-light brown, silty fine to medium SAND, SPT (SM), dry. S-4 18 14 21 14 22 23 10/26/2017 2:01:23 PM 24 25 Hard, brown, fine sandy SILT, (ML), moist. 12 30 26 36 2017-10-05 DRILL DATE.GPJ 27 28 29 30 Medium dense, brown, silty fine SAND, (SM), moist. ". ANGAN. COMIDATAIIRVIDATA81700048801/ENGINEERING DATAIGEOTECHNICALIGINTLOGS\700048801-BORING LOGS S-6 9 8 31 13 32 33 34 Capistrano Formation [Tcs] 35 Very stiff, grey, fine sandy SILTSTONE, moist. 9 S-7 CR 11 36 17 37 38 39 Stiff, grey, fine sandy SILTSTONE, moist. S-S 18 5 42



Log of Boring **B-3** Sheet 3 of 3 Project Project No. 4302 Ford Road 700048801 Location Elevation and Datum 4302 Ford Road, Newport Beach, CA Approximately 193 feet (NAVD 88) Sample Data Remarks Elev (ft) Depth Scale N-Value (Blows/ft) Penetr. resist BL/6in Number Sample Description (Drilling Fluid, Depth of Casing, Fluid Loss, Drilling Resistance, etc.) 148.0 10 20 30 40 45 Very stiff, grey, fine sandy SILTSTONE, moist. S-9 CR 8 10/26/2017 2:01:23 PM ... Report: Log - LANGAN 12 30 48 49 50 Very stiff, grey, fine sandy SILTSTONE, moist. S-10 18 10 15 NLANGAN, COMIDATANIRVIDATA81700048801/ENGINEERING DATA/GEOTECHNICAL/GINTLOGS/700048801-BORING LOGS - 2017-10-05 DRILL DATE.GPJ 52 End boring at 51.5 feet. No groundwater encountered. Boring backfilled with bentonite-grout mixture tremie style. 53 54 55 56 58 59 60 61 62 63 64 65 66 67 68 69

	4	IVGAIV	Log	of Boring		P-1	_	Sheet 1	of	1
Project		4302 Ford Road		Project No.	70	00048801				
Location				Elevation and Datu	ım		102 for	St (NIA)/D 99)		
Drilling C	ompai			Date Started	A	oproximately		inished		
Drilling E	quipm	2R Drilling ent		Completion Depth		10/5/17	Rock I		10/5/17	
Size and	Type	Limited Access Rig			ח	10 ft isturbed	Une	disturbed	- Core	
		8" diameter Hollow Stem Auger	Casing Depth (ft)	Number of Sample	S	-	.	mpletion	24 HR.	-
Casing H		-	Drop (in)	Water Level (ft.) Drilling Foreman		rst <u>V</u> -			<u>Ā</u>	-
Sampler	amme				Jeff					
Casing D Casing H Sampler Sampler	Hamm	er Weight (lbs)	Drop (in)	_ Field Engineer	Dan	iel Judge				
MATERIAL SYMBOL	Elev. (ft) +193.0	Sample Description		Depth Scale		Sample Data Lesist BL/6in BL/6in		Ren (Drilling Fluid, Fluid Loss, Drillin	narks Depth of Casing, g Resistance, etc	c.)
NEARGARCOMIDATAIRANDA DO TOUGHEENING DATAIGEO I ECHNICALIGINI LOGGIODOGGO POORTA DATAIGEO DATAIL DATEL	+183.0	End drilling at 10 feet below ground surfa Boring was backfilled with soil cuttings up Percolation Test. No groundwater was encountered.	ce. con completion of	1 1						

Project No. Project No. Project No. T00048801	
Elevation and paturn Agoptor Road, Newport Beach, CA Date Finished Agoptoximately 200 feet (NAVD 88)	
A302 Ford Road, Newport Beach, CA Date Started 2R Drilling 2R Drilling 2R Drilling 2R Drilling 2R Drilling 3R decay by service of the started of the starte	
Delte Started 10/5/17	
Completion Depth To fit Rock Depth	
Limited Access Rig size and Type of Sit 8" diameter Hollow Stem Auger 9 diameter Hollow Stem Auger 8" diameter Hollow Stem Auger 8" diameter Hollow Stem Auger 8" diameter Hollow Stem Auger 9 diameter Hollow Stem Auger 8" diameter Hollow Stem Auger 9 diameter Hollow Stem Auger 8" diameter Hollow Stem Auger 9 diameter Hollow Stem Auger 8" diameter Level (it.) First 9 diameter Level (it.) First 9 diameter Hollow Stem Auger 9 diameter Hollow Stem Auger 8" diameter Hollow Stem Auger 9 diameter Hollow Stem Auger 8" diameter Level (it.) First 9 diameter Hollow Stem Auger 9 diameter Hollow Stem Auger 8" diameter Level (it.) First 9 diameter Hollow Stem Auger 10 diameter Holl	
Second Parameter Second Para	
8" diameter Hollow Stem Auger asing Diameter (in) Weight (bs) Drop (in) D	
asing Hammer Weight (bs) Drop (in) Drilling Foreman Jeff	
asing Hammer Weight (ibs) Drop (in) Indicated the property of	_
ampler Hammer Weight (ibs) Drop (in) Paniel Judge Sample Description Sample Description Brown, silty fine SAND, (SM), moist Field Engineer Daniel Judge Sample Data Remarks (Drilling Russ, Drilling Resistor) 1	
### Description Description	
Brown, silty fine SAND, (SM), moist Sample Description Sample Desc	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
Brown, silty fine SAND, (SM), moist - 1 - 1 - 2	
Brown, silty fine SAND, (SM), moist - 1 - 1 - 2 - 3 - 4 - 4 - 4 - 4 - 4 - 4 - 4 - 4 - 4	ising, ce, etc.)
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
End drilling at 10 feet below ground surface. Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
Boring was backfilled with soil cuttings upon completion of Percolation Test. No groundwater was encountered.	
No groundwater was encountered.	
- 15	
- 16	
F 17	
<u> </u>	
- 19 19	

APPENDIX C CPT LOGS





Kehoe Testing and Engineering 714-901-7270 rich@kehoetesting.com

www.kehoetesting.com


Project: Langan Eng. & Environmental Services

Location: Bonita Canyon Dr & MacArthur Blvd Newport Beach, CA

CPT-1

Total depth: 70.41 ft, Date: 10/5/2017

Cone Type: Vertek





Kehoe Testing and Engineering

714-901-7270 rich@kehoetesting.com www.kehoetesting.com


Project: Langan Eng. & Environmental Services

Location: Bonita Canyon Dr & MacArthur Blvd Newport Beach, CA

CPT-2

Total depth: 70.41 ft, Date: 10/5/2017

Cone Type: Vertek



APPENDIX D LABORATORY TEST RESULTS




MOISTURE DENSITY TESTS

PROJECT Langan # 700048801 JOB NO. 2012-0057 BY LD DATE 10/14/17

Sample No.	B-1 / S-5	B-2 / S-3	B-3 / S-3			1
	D-1 / 3-3	D-2 / 3-3	D-3 / 3-3			
Depth (ft)						
Testing						
Soil Type	Brown, Silty Sand	Brown, Silty Sand	Brown, Silty Sand			
Wet+Tare	848.8	850.2	889.3			
No. Ring	5	5	5			
Wet Weight						
Dry Weight						
Wet density	103.7	105.5	105.1			
% Water	9.4	6.0	8.0			
Dry Density	94.7	99.5	97.3			
O.B.Press(psf)						
Sample No.						
Depth (ft)						
Testing						
Soil Type						
Wet+Tare						
No. Ring						
Wet Weight						
Dry Weight						
Wet density						
% Water						
Dry Density						
O.B.Press(psf)						

PLASTICITY INDEX _ ASTM D4318



Sample	Depth	LL	PL	PI	USCS	Material Description
B-2 / S-8		44	19	25	CL	
B-3 / S-7		49	21	28	CL	

Job Name: Langan # 700048801 Date: 10/14/17

Job No.: 2012-0057




WASH #200 SIEVE - ASTM D 1140-92


Job Name Langan # 700048801 Date 10-15


Job No.	2012-0057				By LD
Sample	B-1 / S-1	Sample	B-1 / S-6	Sample	B-2 / S-5
Soil Type		Soil Type		Soil Type	
% water	6.8	% water	10.6	% water	14.1
Wet weight	211.4	Wet weight	210.1	Wet weight	207.6
Dry weight	197.9	Dry weight	190.0	Dry weight	181.9
+ 200 sieve	159.3	+ 200 sieve	131.7	+ 200 sieve	95
% Retained	80.5	% Retained	69.3	% Retained	52.2
%Pass. #200	20	%Pass. #200	31	%Pass. #200	48
Sample	B-3 / S-5	Sample		Sample	
Soil Type		Soil Type		Soil Type	
% water	12.7	% water		% water	
Wet weight	213.3	Wet weight		Wet weight	
Dry weight	189.3	Dry weight		Dry weight	
+ 200 sieve	95	+ 200 sieve		+ 200 sieve	
% Retained	50.2	% Retained		% Retained	
%Pass. #200	50	%Pass. #200		%Pass. #200	
	1	<u> </u>			
Sample		Sample		Sample	
Soil Type		Soil Type		Soil Type	
% water		% water		% water	
Wet weight		Wet weight		Wet weight	
Dry weight		Dry weight		Dry weight	
+ 200 sieve		+ 200 sieve		+ 200 sieve	
% Retained		% Retained		% Retained	
%Pass. #200		%Pass. #200		%Pass. #200	
Sample	1	Sample		Sample	1
Soil Type		Soil Type		Soil Type	1
% water		% water		% water	
Wet weight		Wet weight		Wet weight	
Dry weight		Dry weight		Dry weight	
+ 200 sieve		+ 200 sieve		+ 200 sieve	
% Retained		% Retained		% Retained	
%Pass. #200		%Pass. #200		%Pass. #200	















Langan Engineering # 700040001		0012 1201 112002	-	_	00140: 2012 0007
SAMPLE NO.:	B-1 / B-1 @ 0 - 5'				
DESCRIPTION	Silty Sand				
DIRECT SHEAR TEST (type)					
Initial Moisture Content %					
Dry Density (pcf)					
Normal Stress (psf)					
Peak Shear Stress (psf)					
Ultimate Shear Stress (psf)					
Cohesion (psf)					
Internal Friction Angle (degrees)					
EXPANSION TEST UBC STD 18-2					
Initial Dry Density (pcf)					
Initial Moisture Content %					
Final Moisture Content %					
Pressure (psf)	1	Ţ			
Expansion Index Swell %					
CORROSIVITY TEST					
Resistivity (CTM643) (ohm-cm)	2,400				
pH (CTM643)	8.1				
CHEMICAL TESTS					
Soluble Sulfate (CTM 417) (ppm)	1,111				
Chloride Content (CTM 422) (ppm)	73				
Wash #200 Sieve (ASTM-1140) %					
Sand Equivalent (ASTM D2419)					



APPENDIX E PERCOLATION TEST RESULTS



PERCOLATION TEST DATA SHEET							LANGAN				
Project:	430	2 Ford Road, Newport Beach, Californi		fornia	Project No.:	700048801	Date of Test:	10/5/2017			
Test Hole No.:			P-1		Tested By:	DJJ					
Depth of Test Hole (ft):		10			USCS Soil Classification:		clayey fine SAND (SC)				
Casing Depth (ft):		10.0' PVC Pipe; Perforated entire length of pipe			Test Hole Diameter (in):		8				
Trial No.	Date	Time of Measurement	Initial Depth to Water (Feet)	Time of Measurement	Final Depth to Water (Feet)	Time Interval (min)	Change in Water Level (Feet)	Percolation Rate (in/min)	Infiltration Rate (in/hr)		
Sandy soil criteria 1	10/5/2017	12:00 PM	4.00	12:25 PM	4.11	25	0.11	0.05			
Sandy soil criteria 2	10/5/2017	12:25 PM	4.11	12:50 PM	4.20	25	0.09	0.04			
1	10/6/2017	6:40 AM	4.20	7:10 AM	4.35	30	0.15	0.06			
2	10/6/2017	7:11 AM	4.35	7:41 AM	4.49	30	0.14	0.06			
3	10/6/2017	7:42 AM	4.49	8:12 AM	4.55	30	0.06	0.02			
4	10/6/2017	8:13 AM	4.55	8:43 AM	4.71	30	0.16	0.06			
5	10/6/2017	8:44 AM	4.72	9:14 AM	4.88	30	0.16	0.06			
6	10/6/2017	9:15 AM	4.88	9:45 AM	5.04	30	0.16	0.06			
7	10/6/2017	9:46 AM	5.04	10:16 AM	5.2	30	0.16	0.06			
8	10/6/2017	10:17 AM	5.20	10:47 AM	5.35	30	0.15	0.06			
9	10/6/2017	10:48 AM	5.35	11:18 AM	5.51	30	0.16	0.06			
10	10/6/2017	11:19 AM	5.51	11:49 AM	5.67	30	0.16	0.06			
11	10/6/2017	11:50 AM	5.67	12:20 PM	5.82	30	0.15	0.06			
12	10/6/2017	12:21 PM	5.82	12:51 PM	5.96	30	0.14	0.06	0.1		
								1 2010			
	 Percolation test was performed in accordance with the Orange County - Technical Guidance Document dated 20 December 2013. Infiltration Rate was calculated using Porchet Method. 										
	3. Per the procedures for shallow percolation tests in non-sandy soils, a minimum of twelve measurements were taken in 30-minute intervals for six hours after sandy soil criteria was not met.										
	4. Weather: Sunny, 65-80°F										
	5. Measurements were collected from the Top of PVC Pipe										




- 1. LP-1 percolation test was performed approximately 10 feet below existing grade.
- 2. Refer to Figure 1 for percolation test locations.



Preliminary Geotechnical Study Report 4302 Ford Road, Newport Beach, California

Langan Project No.: 700048801

PERCOLATION TEST DATA SHEET							LANGAN				
Project:	430	2 Ford Road, Newport Beach, California		Project No.:	700048801	Date of Test:	10/6/2017				
Test Hole No.:			P-2		Tested By:	DJJ					
Depth of Test Hole (ft):		10			USCS Soil Classification:		silty SAND (SM)				
Casing Depth (ft):		10.0' PVC Pipe; Perforated entire length of pipe			Test Hole Diameter (in):		8				
Trial No.	Date	Time of Measurement	Initial Depth to Water (Feet)	Time of Measurement	Final Depth to Water (Feet)	Time Interval (min)	Change in Water Level (Feet)	Percolation Rate (in/min)	Infiltration Rate (in/hr)		
Sandy soil criteria 1	10/6/2017	9:00 AM	5.35	9:25 AM	8.80	25	3.45	1.66			
Sandy soil criteria 2	10/6/2017	9:26 AM	7.40	9:51 AM	8.45	25	1.05	0.50			
1	10/6/2017	9:52 AM	7.00	10:02 AM	7.80	10	0.80	0.96			
2	10/6/2017	10:03 AM	6.60	10:13 AM	7.40	10	0.80	0.96			
3	10/6/2017	10:14 AM	6.65	10:24 AM	7.30	10	0.65	0.78			
4	10/6/2017	10:25 AM	7.30	10:35 AM	7.80	10	0.50	0.60			
5	10/6/2017	10:36 AM	7.40	10:46 AM	7.90	10	0.50	0.60			
6	10/6/2017	10:47 AM	7.30	10:57 AM	7.80	10	0.50	0.60	2.3		
Comments:	1. Percolation to	est was performed	d in accordance w	vith the Orange Co	ounty - Technical	Guidance Docu	ment dated 20 Deco	ember 2013.			
Comments.	 Percolation test was performed in accordance with the Orange County - Technical Guidance Document dated 20 December 2013. Infiltration Rate was calculated using Porchet Method. Per the procedures for shallow percolation tests in sandy soils, a minimum of twelve measurements were taken in 30-minute intervals for six hours after sand soil criteria was met. 										
	4. Weather: Sunny, 65-80°F										
	5. Measurements were collected from the Top of PVC Pipe										



- 1. P-2 percolation test was performed approximately 10 feet below existing grade.
- 2. Refer to Figure 1 for percolation test locations.

